



PRELIMINARY GEOLOGIC AND GEOTECHNICAL ENGINEERING INVESTIGATION,
UPTOWN NEWPORT, 4321 JAMBOREE ROAD, NEWPORT BEACH, CALIFORNIA
Project No.: 116-02, Date: November, 2011

PRELIMINARY GEOLOGIC AND GEOTECHNICAL ENGINEERING INVESTIGATION, UPTOWN NEWPORT, 4321 JAMBOREE ROAD, NEWPORT BEACH, CALIFORNIA



By: Ginter & Associates
For: UPTOWN NEWPORT, LP
8951 Research Drive,
Irvine, CA 92618
Project No.: 116-02
Date: November, 2011

**PRELIMINARY GEOLOGIC AND GEOTECHNICAL
ENGINEERING INVESTIGATION,
UPTOWN NEWPORT VILLAGE
4311 JAMBOREE ROAD, NEWPORT BEACH, CALIFORNIA
Project # 116-02 November, 2011**

Prepared for:

Uptown Newport, L.P.
8951 Research Drive
Irvine, CA 92618

Prepared by:

Ginter & Associates, Inc.
27631 Durazno
Mission Viejo, CA 92692

PRELIMINARY GEOLOGIC AND GEOTECHNICAL ENGINEERING INVESTIGATION,
UPTOWN NEWPORT, 4321 JAMBOREE ROAD, NEWPORT BEACH, CALIFORNIA

Project # 116-02
November, 2011

TABLE OF CONTENTS

1.0 INTRODUCTION	1
1.1 Purpose	1
1.2 Site location and Description	1
1.3 Previous Investigations	3
2.0 SCOPE OF WORK	4
3.0 REGIONAL GEOLOGY	4
3.1 Geomorphic Setting:	4
3.2 Regional Geologic Setting	5
3.3 Tectonic Setting	5
3.4 Aerial Photo Lineament Analysis	7
3.5 Regional Hydrogeology	8
4.0 SITE GEOLOGY CONDITIONS	8
4.1 Stratigraphic Framework	8
4.2 Surficial Deposits	8
4.2.1 Artificial Fill (Af)	8
4.2.2 Compacted Artificial Fill (Caf)	9
4.2.3 Terrace Deposits (Qtm)	9
4.3 Bedrock Units (Ql)	9
5.0 SITE GROUNDWATER CONDITIONS	9
6.0 GEOTECHNICAL CONDITIONS	10
6.1 Soil Properties	10
6.2 Expansive Soils	10
6.3 Corrosive Soils	11
6.4 Removals	11
6.5 Shrinkage	11
7.0 POTENTIAL GEOLOGIC/SEISMIC HAZARDS, SIGNIFICANCE AND MITIGATION MEASURES	11
7.1 General	12
7.2 Fault Induced Ground Rupture	12
7.3 Ground Shaking	12
7.4 Subsidence	13
7.5 Flooding	13
7.6 Erosion	13
7.7 Landsliding	13
7.8 Loss of Mineral Resources	13
7.9 Liquefaction Potential	13
7.10 Slope Stability	15
7.11 Tsunamis	15
8.0 SUMMARY OF GEOLOGIC AND ENVIRONMENTAL HAZARDS AND POTENTIAL MITIGATION MEASURES	15

PRELIMINARY GEOLOGIC AND GEOTECHNICAL ENGINEERING INVESTIGATION,
UPTOWN NEWPORT, 4321 JAMBOREE ROAD, NEWPORT BEACH, CALIFORNIA

9.0 PRELIMINARY GRADING CONSIDERATIONS	16
10.0 FOUNDATION CONSIDERATION	18
10.1 General	18
10.2 Other Construction Considerations	18
11.0 CONCLUSIONS	18
12.0 LIMITATIONS	19

LIST OF FIGURES

Figure 1	Site Location Map
Figure 2	Master Plan- Phase I
Figure 3	Phasing Diagram
Figure 4	Regional Geologic Map
Figure 4a	Regional Geologic Legend
Figure 5	Geologic/Geomorphc Provinces of southern California
Figure 6	Los Angeles Basin & Vicinity Showing Geomorphic & Tectonic Features
Figure 7	Aerial Photo Lineament Analysis
Figure 8	Geotechnical Map
	also included is Tsunami Inundation Map for Emergency Planning-Newport Beach Quadrangle



GINTER & ASSOCIATES, INC.

27631 DURAZNO
MISSION VIEJO, CA 92692
OFC (949) 581-2363 CELL (714) 478-1167

Uptown Newport LP
8951 Research Drive
Irvine, CA 92618

November 17, 2011

Project # 116-02

Attn: Mr. Brian Rupp
Project Manager

Subject: Preliminary Geologic and Geotechnical
Engineering Investigation, Uptown Newport
4321 Jamboree Road, Newport Beach, California

References: See attached List of References

1.0 INTRODUCTION:

1.1 Purpose:

This report has been prepared to provide a preliminary geologic and geotechnical evaluation for the Uptown Newport development site in the city of Newport Beach, California.

The document presents the data and analyses regarding the geology, soil properties, hydrogeology, geologic hazards and associated mitigation measures and general grading and foundation considerations and incorporates the findings of and supersedes previous investigation reports by other geotechnical firms.

1.2 Site Location and Description:

The subject site is rectangular in shape located northeast of the intersection of Jamboree Road and MacArthur Blvd. as shown on Figure 1. Uptown Newport Planned Community Development Plan, hereinafter referred to as "Uptown Newport PC", is a planned residential community of 1,244 high-density

residential units and 11,500 square feet of retail uses located on 25 acres located at 4311-4321 Jamboree Road in Newport Beach, California, within the City's Airport Area. Local access to the project site is provided by Jamboree Road to the southeast, Birch Street to the northwest, Von Karman Avenue to the northeast and MacArthur Boulevard to the southwest. The site is immediately bounded by Jamboree Road to the southeast, a fast food restaurant to the northeast and by existing office development within the Koll Center to the northwest and southwest.

Uptown Newport is in close proximity to numerous regional transportation corridors and amenities. Uptown Newport is located near regional open space including Upper Newport Bay, Mason Regional Park in Irvine and San Joaquin Freshwater Marsh. It is also located near the University of California-Irvine (UCI) with immediate adjacency to the UCI North Campus opposite the Subject Property on Jamboree Road. Uptown Newport has convenient access to the 405, 73 and 55 Freeways via MacArthur Boulevard and Jamboree Road.

The Uptown Newport site was originally developed as part of the Koll Center, and has been used for manufacturing telecommunications equipment and computer chips since the 1970's, and is currently used for office and computer chip manufacturing. The property currently includes a single-story office building and a two- and three-story semiconductor chip manufacturing facility. The property is currently accessed via two entries on Jamboree Road, a drive access via Birch, and a drive access via Von Karman Avenue. The Uptown Newport project will include redevelopment of the 25-acre property into a high-density mixed use residential project. Up to 1,244 residential units, 11,500 square feet of retail, and 2 acres of park space are planned as part of the project. The plan calls for the approximate 25-acre site to be configured with a pattern of streets and development areas that provide a pedestrian-friendly environment, with strong connectivity to adjacent commercial/office areas.

Residential buildings may include low-rise row-houses; 4 and 5-story apartments or condominiums featuring a range of floor plan sizes and configurations. Mid-rise to high-rise buildings are also possible.

The project is anticipated to be developed in two primary phases. Phase 1 will include demolition of the existing single-story office building at 4311 Jamboree (the "Half Dome Building"), and development of the westerly portion of the property, including the frontage along Jamboree Road. Phase 1 development will include approximately 680 units on approximately 12.85 acres, and is projected to commence in mid-2014 with build-out of Phase 1 through 2017. Phase 2 will include demolition of the existing Jazz Semiconductor fabrication building (the "Jazz Building"), and development of approximately 564 units on 12.20 acres on the easterly portion of the property. Development of Phase 2 is




Figure 1
SITE
LOCATION
MAP



PROJECT NO.:


116-02

DATE:

Nov., 2011



UPTOWN NEWPORT
4.25.11




SITE BOUNDARY

EXISTING CONDITIONS
CONTEXT AERIAL PHOTOGRAPH



SCALE: 1"=200' 0 100' 200' 400'



BIRCH STREET

JAMBOREE ROAD

Figure 2



PROJECT NO. :
116-02
DATE :
Nov., 2011


Master Plan - Phase 1
Uptown Newport
 Uptown Newport LP

Developable Area: 9.33 ac
 Park Area: 1.03 ac
 Right of Way Area: 2.49 ac
 Total Site (Phase 1): 12.85 ac






Figure 3



PROJECT NO.:
116-02
DATE:
Nov., 2011



Phasing Diagram
Uptown Newport
Uptown Newport LP



anticipated to commence in the spring of 2017. Timing for Phase 2 development is contingent on the existing lease of the Jazz Building, which is currently set to expire in March 2017.

1.2 Previous Investigations:

Maurseth-Howe-Lockwood & Associates performed the original geotechnical investigation for development of the existing facilities in 1967. This consisted of a field investigation involving drilling and sampling of 96 borings to depths ranging from 20 ft. to 40 ft. They reported relatively heterogeneous subsurface conditions consisting of a silty-clay top soil overlying competent, interbedded sands, silts and clays of varying thickness. Groundwater was encountered between 15 ft. and 30 ft. below existing grade. Grading recommendations indicated 4 to 8 ft. of cut and fill were required in order to prepare the site for construction of building pads. An allowable bearing capacity of 4,000 pounds per square foot was recommended for design of spread footings established in native or engineered fill soils.

Dames & Moore performed a preliminary geotechnical investigation for the seismic retrofit of Buildings 503 and 505 summarizing their findings and recommendations in the report dated April 28, 1995. Two borings were drilled and sampled to 51½ ft. which encountered stiff to very stiff clays with interbedded sand and silty sands. Groundwater was encountered between 16 ft. and 20 feet.

Dames & Moore performed a geotechnical investigation for the 3-story addition to the east of Building 503. Their summary of findings and recommendations were summarized in a report dated April 8, 1996 (not available for review).

On December 24, 1996, Dames & Moore compiled a report titled "Geotechnical Investigation – Phase I, Building 503 Base Isolation Project". The proposed project involved underpinning of the building foundations, excavation of the soils below the building, and installation of base isolation devices below the existing footings. This report evaluated the subsurface conditions, conceptual design of foundation underpinning,, and planning for the pilot program and related testing. Their subsurface exploration involved drilling and sampling 15 borings inside Building 503 and 9 borings outside this building to depths of 15 ft. to 100 ft. using hand-auger equipment, limited access hollow-stem auger rig and truck-mounted hollow-stem auger rig.

Solvents were detected in soil at the site in January 1984 during an investigation of a broken water line northwest of Building 503. The environmental consultant, Jacob & Hefner Associates, Inc. (JHA), have prepared various reports regarding

groundwater monitoring and sampling and soil and soil vapor investigations. Pertinent geotechnical data from these investigations are included in this report.

2.0 SCOPE OF WORK


The scope of work for this evaluation included the following:

- Review of regional and local geologic literature and maps from federal, state, county and local agencies
- Review of site geotechnical and environmental investigations and reports by others
- Review and transfer pertinent geologic data from previous investigations to the new plan
- Subsurface investigation consisting of hollow-stem auger borings and cone penetrometer (CPT's) including logging and soil sampling
- Laboratory analyses on select soil samples
- Liquefaction analyses
- Provide current CBC seismic design parameters
- Geologic hazards evaluation
- Preparation of this report, incorporating pertinent data from the previous investigations and providing preliminary conceptual site grading recommendation and foundation considerations pertinent to the currently planned development


3.0 REGIONAL GEOLOGY

3.1 Geomorphic Setting:

The subject site is situated near the northeastern edge of the Newport Mesa, a flat-topped platform deeply dissected by stream erosion (Figure 4). San Diego Creek is located just east of the site and is one of the major drainage courses that transects the mesa. Originally formed by wave abrasion, this platform, which is also called a marine terrace, is now elevated well-above the water at an approximate elevation of 50 feet above mean sea level (msl) and is bounded by steep bluffs along the shoreline.



SOURCE: Morton & Miller, 1981
*SEE FIGURE 4a FOR LEGEND



Scale≈1:48,000





















Figure 4
REGIONAL
GEOLOGIC MAP



PROJECT NO.:
116-02
DATE:
Nov., 2011

EXPLANATION

SYMBOLS



Holocene
Quaternary
Pleistocene
Pliocene
Miocene
Tertiary
Eocene
Paleocene
Upper Cretaceous
Jurassic




Figure 4a
REGIONAL
GEOLOGIC
LEGEND

GA
inc.

PROJECT NO.:
116-02

DATE:
Nov., 2011

During development of this site (1967-1969), the area was cut and filled with local materials.

3.2 Regional Geologic Setting:

The subject site is located at the southeastern edge of the Los Angeles Basin near San Diego Creek, which separates the basin from the Peninsular Ranges geomorphic province (Figure 5) and the San Joaquin Hills, a major structural uplift.

The Newport Mesa consists of several hundred feet of marine terrace deposits including clays, silts, sands and gravels overlying a suite of Tertiary sedimentary bedrock units, which in turn overlay Cretaceous granitoid basement.

3.3 Tectonic Setting:

Uptown Newport PC is located in a structurally complex and tectonically active region of southern California. The geologic complexity of the region is due in part to its position between the geologic/geomorphic provinces of the Transverse Ranges and Peninsular Ranges (Figure 6). The Transverse Ranges border the Peninsular Range to the north and form the northern boundary of the Los Angeles Basin. The Transverse Ranges are characterized by east-west trending faults with histories of seismic activity within the Los Angeles Basin. In contrast, the Peninsular Ranges are traversed by dominant northwest trending faults consisting of the San Andreas Fault, San Jacinto Fault, Newport-Inglewood Fault and the Whittier-Elsinore Fault. These faults are all major fault systems capable of producing magnitudes up to 7.5 on the Richter Scale.

Faults which potentially could have the greatest effect on the site include the Newport-Inglewood fault and its offshore extension, the Whittier-Elsinore Fault (approximately 28 km. from the site), and the Palos Verdes Fault (27 km. from the site). Evidence for the location of these faults is found through surface traces, historic seismicity and micro-seismic activity. The San Andreas Fault, although capable of producing very large earthquakes with ground shaking lasting about two minutes or more, does not dominate the seismic hazard for this site because of the distance from it (76 km.). Rather, due to its proximity to the site, the Newport-Inglewood Fault zone is the most significant contributor to ground shaking hazard.

In addition to these active faults, blind thrust faults have also been postulated in the Los Angeles Basin. The 1994 Northridge earthquake occurred on this type of fault. Several major blind thrust systems have been identified; the Compton Thrust System, consisting of three segments (Baldwin Hills, Central and Santa Ana) is closest to the site. The southern edge of the Santa Ana segment is




Figure 5. Geologic/geomorphic provinces of southern California. Stippled areas are the Los Angeles (LA) and Ventura-Santa Barbara (V, SB) basins, Rectangle shows area of Figure 6.

ADAPTED FROM WRIGHT (1991)



PROJECT NO. :

116-02

DATE :

Nov., 2011




Figure 6. Los Angeles basin and vicinity, showing principal geomorphic and tectonic features. Stippled areas are Quaternary basinal areas. A(D)F= Anacapa (Dume) fault, CS= Capistrano syncline, CHF= Chino Hingeline fault, CuF= Cucamonga fault, EF= Elsinore fault, HF= Hollywood fault, LK= Lasuen Knoll, MCF= Malibu Coast fault, NIFZ= Newport-Inglewood fault zone, PB= Perris block, PH= Puente (and San Jose) Hills, PVF= Palos Verdes fault, RCF= Redondo Canyon fault, RF= Raymond fault, SAF= San Andreas fault, SBI= Santa Barbara Island, SBM= San Bernardino Mountains, SBV= San Bernardino Valley, SCI= Santa Catalina Island, SCOF= South Coast Offshore fault, SFV= San Fernando Valley, SGF= San Gabriel fault, SGV= San Gabriel Valley, SJF= San Jacinto fault, SJH= San Joaquin Hills, SMB= Santa Monica Bay, SMF= Sierra Madre fault, SMoF= Santa Monica fault, SPB= San Pedro Bay, SPBF= San Pedro Basin fault zone, SPEF= San Pedro Escarpment fault, VF= Verdugo fault, WF= Whittier fault, WN= Whittier Narrows. -G- illustrates approximate limits of San Joaquin Hills gravity high.



PROJECT NO. :

116-02

DATE :

Nov., 2011

inferred to be located beneath the site, but uncertainty associated with the recurrence of large earthquakes on this segment or others is great.

The major tectonic feature of the area is the Newport-Inglewood fault zone (NIFZ), which trends N45°W and extends nearly 40 miles from Culver City southeast to Newport Beach (Figure 6). It is located approximately 7 kilometers to the southwest of the site. Active Tectonism was made obvious by the 1920 Inglewood earthquake (est. $M_L=4.9$) and the 1933 Long Beach earthquake ($M_L=6.3$).

Geologic data from oil wells in the Newport and West Newport oil fields indicate a complexly faulted zone southwest of the NIFZ and a north-dipping monocline northeast of it; West Newport's offshore production is from a west-trending anticline on the Offshore Newport ridge (C. Wright, 1991)

South of the Newport field, the alignment of the NIFZ coincides with a steep submarine scarp having 1200-1500 feet of vertical relief. Deep-penetration seismic reflection profiles and other geophysical data (Barrows, 1974) have revealed a feature called the South Coast Offshore Fault, which follows that submarine scarp. This is considered by most to be the continuation of the NIFZ.

Movement along the NIFZ is predominately right-lateral slip with some vertical components that have formed as a series of en echelon faults. Data indicates over 6 miles± of right-lateral offset and 3500 feet to 5,000 feet± of vertical offset.

The Pelican Hills Fault is located approximately 2 miles southwest of the site and is overlapped by Pliocene beds west of the site (Figure 4). implying that its last movement occurred in Late Miocene time. However, data cited by Ziony and Yerkes (1985) suggest that the Pelican Hills Fault has been active during late Quaternary time. The California Geologic Survey (CGS) also designates this fault as Late Quaternary (potentially active).

The San Joaquin Hills area to the south (Figure 4) appears to be defined by a combination of fault blocks, each with homoclinal structure, that form overall anticlinal-synclinal patterns, essentially without folding (Bender, 2000). The Shady Canyon Fault is the dominant fault of these hills and nearly bisects the area in a northwesterly direction and has a stratigraphic throw of approximately 5,000 feet (Morton et al., 1974). The Shady Canyon Fault is nearly vertical and separates the area into an up-thrown block exposing early Miocene and older rocks on the east, and a down-thrown block exposing rocks of middle Miocene and younger age to the west (Figure 4) implying a middle Miocene age of faulting.

Its projection to the north where it is concealed by basin sediments would be approximately 3 miles east of the site.

Prior to the construction of the UCI campus to the south of the subject site, Petra Geotechnical, Inc., in 1991, performed a fault investigation that discovered what they designated as the UCI Campus Fault. They concluded that the fault is potentially active and is capable of generating earthquakes up to 7.5 in magnitude. UCI adopted a Restricted Use Zone (RUZ), which is 50 feet on either side of the UCI Campus Fault. No full-time occupied structures can be placed within the RUZ unless a focused project specific analysis is conducted.

3.4 Aerial Photo Lineament Analysis:

A collage of over 50 photographs from 1927 through 1973 was reviewed from the archives of UC Santa Barbara and Continental Aerial Photo, Incorporated. The following are those selected for detailed analysis:

a. From UC Santa Barbara		
<u>FLIGHT #</u>	<u>FRAME #</u>	<u>DATE</u>
113	1092, 1093, 1094	1927
AXK-1K	44, 45	1952
b. From Continental Aerial Photo, Inc.		
AXK-1K	45, 46	11/18/52
261-3-15	96, 97	3/25/59
I	40, 41	3/1/67
9C2	7	1/24/67
94	13, 14	6/28/71
132-6	14, 15	10/29/73

The lineament analysis was performed in order to aid the determination for the presence and/or absence of active faults transgressing the subject site. In order to qualify the lineament designations, the following criteria were used:

LINEAMENT DESIGNATION	CHARACTERISTICS
Moderate	usually traceable for over a one mile distance and can be associated with offset stream drainages, changes in topography and resistant beds; can be related to faulting
Weak	usually traceable for less than one mile; commonly associated with tonal variations caused by variations in lithology and vegetation; possibly related to Pre-Holocene faulting

The results of our analysis are presented in Figure 7.



Legend

- MODERATE LINEAMENT
- WEAK LINEAMENT
- 4 LINEAMENT NUMBER

Figure 7
AERIAL PHOTO
LINEAMENT
ANALYSIS



PROJECT NO. :

116-02

DATE :

Nov., 2011

Lineament 1 is relatively well-pronounced and is probably associated with the Pelican Hills Fault, southeast of the site. It is not distinguishable through the Newport Mesa. Lineaments 2 through 4 are sub-parallel to Lineament 1 and are probably associated with older faults, differential erosion and/or lithologic differences in bedrock lithologies. None of the lineaments can be traced across the Newport Mesa.

3.5 Regional Hydrogeology:

The site is located within the San Diego Creek watershed which drains to the southwest through an artificial channel into Upper Newport Bay. Two ornamental lakes, which are flood control basins, are located northwest of the site. A subsurface sand drain extends from north of Building 503 to these lakes (JHA, 2010).

The site is underlain by a portion of the Coastal Plain hydrogeologic unit and is positioned at the boundary of the Orange County Main Basin to the northwest and the Irvine Groundwater Basin to the northeast. A shallow aquifer system (15 ft. – 30 ft. to 35 – 45 ft. bgs.) consists of perched water-bearing units within the Pleistocene marine terrace deposits. Deep aquifers in this area are reported to consist of the Alpha, Beta and Lambda Aquifers, which are part of the late Pleistocene age Lakewood Formation.

4.0 SITE GEOLOGY CONDITIONS

4.1 Stratigraphic Framework:

The geologic units present within the site can be characterized as generally stiff to very stiff silty to sandy clay fill soils overlying native sands, silts, clays and gravels of marine terrace deposits to the depths explored. The site was graded in 1967-1969 utilizing conventional cut and fill techniques.

4.2 Surficial Deposits

4.2.1 Artificial Fill (Af)

Various landscape and open space areas have been re-worked to provide soils for vegetation in the form of shrubs, trees and grass. These areas are generally 2-3 feet thick adjacent to existing structures.

Borings by Dames & Moore within Building 503 indicate a floor slab 7 to 8.5 inches thick underlain by a visqueen sheeting and 4-6 inches of aggregate base. All areas have lime-treated soils up to 4 feet thick under the slab.

4.2.2 Compacted Artificial Fill (Caf):

The subsurface investigation for this evaluation involved drilling in accessible areas of the parking lots and driveways. In general, Drill Logs (Appendix II) indicate a 12" thick section of asphalt concrete and base material overlying 2-5 feet± of compacted artificial fill. This unit consists of reddish brown to brown sand, silty sand, sandy clay, sandy silt and clayey sands. Thicknesses vary from 2-24 feet (Dames and Moore, 1995).

4.2.3 Terrace Deposits (Qtm):

Underlying the engineered fills, native terrace deposits consisting of crudely stratified sequences of sand, silts, clays and gravels occur to the depths explored. See Appendices II and VI for more detailed descriptions.

The thickness of this unit is considered to be approximately 100-200 feet.

4.1 Bedrock Units (Ql):

The Lakewood Formation named by Thomas (1961) lies at depth beneath the marine terrace deposits and is reported by others as consisting of well-sorted gray, poorly cemented sands inter-bedded with silty fine-grained sands. Lack of well data in this area indicates little information is available for this unit in the Upper Newport Bay area.

5.0 SITE GROUNDWATER CONDITIONS

Jacob & Hefner Associates, Inc. (2010) have divided the sediments underlying the site, in descending order by depth, into the following hydrogeologic units:

- Unsaturated Zone (0 to 15-30 feet bgs)
- Shallow Groundwater Zone (15-30 to 35-45 feet bgs)
- Aquitard A (45-65 feet bgs)
- Intermediate Groundwater Zone (65-100 feet bgs)
- Aquitard B (100-140 feet bgs)

- Lower Groundwater Zone (140-225 feet bgs)
- Aquitard C (top of zone at 225 feet bgs)

Based on a review of Jacob & Hefner's well monitoring data, the Intermediate Groundwater Zone from 1989 to 2010 has lowered by as much as 25 feet, in general.

The boring logs by G&A (2011, Appendix II) indicate these borings only penetrated the Shallow Groundwater Zone. Our borings also indicate this Shallow Groundwater Zone is not present over the entire site and that local intermittent and perched conditions exist as shown in Cross-Section A-A' (attached).

6.0 GEOTECHNICAL CONDITIONS

This report addresses various geotechnical engineering factors which should be considered during the design and grading of the proposed development.

The development of the site is considered feasible provided the geologic and geotechnical engineering issues are taken into consideration in the design and construction of the plan and appropriate measures, as recommended herein, are implemented.

6.1 Soil Properties:

The site, in general, consists of marine terrace and bay deposits to the depths explored (101 feet bgs). These sediments vary from fine to medium grained sands with minor gravels, silty sands, sandy clays and clays. They are crudely stratified with lenses and pods interspersed indicative of terrace and backbay environments. A distinctive olive-green to olive-gray clay to silty clay horizon is present throughout the site commonly found at an approximate depth of 30 feet bgs, as depicted in Section A-A' (attached). This unit contains occasional bivalve mollusk shell fragments and is very moist and stiff.

These terrace deposits are well-consolidated and suitable for support of the proposed development.

6.2 Expansive Soils:

In general, the fine to medium-grained sands with some gravels will exhibit low expansion indices. The silty clays, sandy clays and clays will exhibit medium to high expansion indices. Three expansion index tests (Appendix IV) performed on sandy to silty clays indicate medium to high expansion indices.

During grading operations in the upper 5 ft.±, the mixing and placement of various on-site soils as compacted fills should reduce this hazard to a less than significant impact.

Additional testing should be performed at a more refined plan stage of grading plans for the proposed development.

6.3 Corrosive Soils:

Future Corrosion tests (chloride, sulfate, resistivity, and pH) of the sub-grade soils should be performed near the completion of grading. A Corrosion Engineer should be retained to evaluate the corrosion potential of as-graded site soils on under-ground metallic installations and to develop appropriate recommendations and mitigation measures, if required.

6.4 Removals:

Demolition of the existing structures and utilities will be challenging, especially since the Jazz Semiconductor Building had a seismic retrofit/upgrade. This retrofit included helical test pile installations up to 14 inches in diameter. All footings will require removal and over-excavation laterally may be required to minimize differential settlement for the proposed structures.

Removals in driveways, parking lots and landscape areas are expected to be 5 ft. in depth with possible deeper localized areas.

In order to reduce potential adverse settlement and subsidence on the site, we recommend for current planning purposes that the uppermost 5 ft. of materials below planned finish grade be removed and replaced with approved compacted (90% relative compaction) engineered fill. If deleterious materials are exposed at the base of the general over-excavation, consideration should be given to remove such debris and replace with acceptable materials in accordance with the Project Geotechnical Engineer's recommendations. No oversized materials (greater than 6" in diameter will be allowed in this zone).

6.5 Shrinkage:

It is estimated that site soils will shrink on the order of 3 to 5 %.

7.0 POTENTIAL GEOLOGIC/SEISMIC HAZARDS, SIGNIFICANCE AND MITIGATION MEASURES

The following is a summary of the principal geologic and geotechnical engineering conditions that occur in the study area and the potential impact that each of the conditions may have on the site which is rated using a qualitative scale of less than significant, potentially significant, and significant. The assessment was performed by

comparing the severity of the impact at the site with the range of hazard severity generally representative of southern California

7.1 General:

The geologic hazards in the general area of the site are those primarily associated with landslides, flooding and earthquakes. Due to the topography and other factors, landsliding is not a hazard for the subject site. The potential for flooding with respect to the subject site is considered remote, since the proposed development envelope is outside the 100-year flood plain.

The site is similar to most of southern California with respect to hazards associated with earthquakes. A detailed seismic hazard evaluation is present in Appendix I. The study reviewed the hazards associated with earthquakes that include primary hazards (i.e. ground shaking, surface rupture) and secondary hazards (i.e. liquefaction, seismic settlement, tsunamis, seiches) and the effect of these on the subject site. The major cause of damage from earthquakes is the shaking from earthquake waves and the much less frequent damage due to actual displacement or fault movement beneath a structure. The shaking would occur not only immediately adjacent to the earthquake epicenter, but within areas for many miles in all directions.

The removal of the unsuitable materials and replacement with engineered compacted fill for the proposed structures and structural design based on the seismic parameters recommended herein will help mitigate the primary and secondary hazards.

7.2 Fault Induced Ground Rupture:

The site is not within an Alquist-Priolo Earthquake Fault Zone for surface fault rupture hazards (Hart, 1997). Also, no faults or fault-related features were observed during our subsurface investigations and field reconnaissance. Based on the available geologic data, active, or potentially active faults, with the potential for surface fault rupture at the site during the design life of the proposed development is considered low and a less-than significant impact.

7.3 Ground Shaking:

Based on the seismic hazard analysis for the subject site presented in Appendix I, the peak ground acceleration that, as a minimum has a 10% probability of being exceeded in 50 years, is 0.345g. Due to the proximity of the active Newport-Inglewood Fault Zone approximately 7 km. southwest of the site capable of a maximum magnitude of 7.5, ground shaking during an earthquake is considered a potentially significant impact.

Mitigation Measures: It should be noted that there is no realistic way in which the seismic shaking hazard can be avoided; however, it should be recognized that it is not considered feasible to make structures totally resistant to seismic shaking. Seismic performance goals may expect that some property damage will be sustained in a moderate to large earthquake, but damage should be repairable and not life-threatening. For residential development, structures should be able to:

- Resist minor earthquakes with no damage
- Resist moderate earthquakes with some nonstructural damage
- Resist major earthquakes with some structural damage, but with a low likelihood of collapse.

7.4 Subsidence:

The undocumented fills within the stress influence of proposed development area are recommended to be removed and replaced with engineered fill derived from approved onsite and offsite sources. The removal of the compressible materials and replacement with engineered fill, and the presence of dense underlying alluvial terrace deposits and bedrock materials, will mitigate potential for subsidence. Thus, subsidence is considered a less-than significant impact after development.

7.5 Flooding:

Refer to the Civil Engineer's hydrologic study.

7.6 Erosion:

The proposed plan will be essentially flat, thus, erosion is considered to be a less-than significant impact after development.

7.7 Landsliding:

No evidence for deep-seated landsliding was observed on or in the immediate vicinity of the site, in the field, or on the aerial photographs reviewed. Due to the lack of significant topography, landsliding is not expected on the site and therefore is considered a less-than significant impact after development.

7.8 Loss of Mineral Resources:

No economic mineral resources are present. Therefore, the loss of mineral resources is considered a less-than significant impact.

7.9 Liquefaction Potential:

Liquefaction is a phenomenon which tends to occur in saturated cohesionless soils during relatively severe earthquake ground motions. In general, during ground motion, saturated sands tend to compact and decrease in volume, and if drainage is

unable to occur, an increase in pore water pressure may result. If the pore water pressure becomes equivalent to the overburden pressure, the effective stress becomes zero and, consequently, the soil loses its strength and is considered to be in a liquefied state.

Liquefaction analyses were performed by this firm based on procedures developed at the NCEER (National Center for Earthquake Engineering Research) Workshop (Youd and Idriss, 1997), and available field data obtained by Gregg In Situ, Inc., utilizing CPT soundings (CPT-1, CPT-2, CPT-4 and CPT-8). Additional field exploration consisting of hollowstem auger borings, were also performed to augment the CPT field data. A computer program "LiquefyPro" developed by CivilTech Software, USA., was utilized to evaluate the liquefaction potential and liquefaction induced settlement.

Based on stabilized ground water levels measured by others in the subject site and the vicinity, the design groundwater level of 15 feet below existing grade was used in our liquefaction analyses. A peak ground acceleration of 0.36g and earthquake magnitude of 6.6 were assumed in the liquefaction analyses. Our liquefaction analysis using the CPT data indicates that isolated, thin, and discontinuous layers of medium dense granular soil below the groundwater table in the CPT's are susceptible to liquefaction as summarized below:

ZONES OF POTENTIAL SOIL LIQUEFACTION

CPT No.	Depth Range of Potential Liquefaction Zones Below Existing Grade, (ft.)	Total Liquefaction Induced Settlement (Inches)
CPT-1	27.4-28.0, 31.4-31.7, 46.6-48.0	0.43
CPT-2	30.0-31.8, 43.2-44.4, 49.8-50.0	0.24
CPT-4	29.3-30.1, 37.1-37.7	0.19
CPT-8	30.9-31.1, 33.7-33.9, 35.0-35.6, 38.8-39.4, 40.8-41.3, 41.5-42.3, 43.0-43.2, 44.1- 44.2,	0.18

The results of our liquefaction analyses indicate there are isolated and discontinuous thin layers of medium dense sand and silty sand below the groundwater table that are susceptible to liquefaction during a major earthquake. Based on our liquefaction analyses using the CPT's, we conclude that up to about 1/2 inch of liquefaction-induced total settlement may occur at isolated locations within the site. Because liquefaction will likely occur in isolated areas, differential settlement may be abrupt; therefore, differential settlements equivalent to the total settlements described above may occur over short distances.

The potential for liquefaction-induced ground rupture and sand boils to occur at the site depends on the thickness of the liquefiable soil layer relative to the thickness of the overlying non-liquefiable material. Ishihara (1985) presented an empirical relationship that provides criteria that can be used to evaluate whether liquefaction-induced surface ruptures and sand boils would be expected to occur under a given level of shaking for a liquefiable layer overlain by a non-liquefiable surficial layer. The potentially liquefiable soil layers encountered in the borings and CPTs are generally relatively thin (less than two feet thick), and are located below a depth of 27 feet below ground surface. Therefore, we conclude that the potential for surface manifestations of liquefaction to be low under the current site conditions.

Site specific liquefaction analyses should be performed for each future building during design phase considering the locations of each building and configurations such as subterranean construction, etc. To mitigate potential adverse effects associated with soil liquefaction, reinforced shallow foundations or deepened foundations may be used.

7.10 Slope Stability:


No significant slopes are proposed, therefore slope stability is a less-than significant impact.

7.11 Tsunamis:

Tsunamis are rare events, due to lack of known occurrences in the historical record, therefore, there is no information about the probability of any tsunamis affecting the site within a specific period of time. Based on the California Geologic Survey's Tsunami Inundation Map for Emergency Planning, Newport Beach Quadrangle (attached), the subject site will not be inundated. Also, since the site is elevated to 50 ft.± above sea level, tsunamis can be considered a less-than significant impact.

8.0 SUMMARY OF GEOLOGIC AND ENVIRONMENTAL HAZARDS AND POTENTIAL MITIGATION MEASURES

The California Division of Mines and Geology (CDMG) (1982), now known as the California Geologic Survey (CGS), has prepared guidelines for geologic and seismic considerations in environmental impact reports in order to identify potential geologic hazards and assist in recognizing data needed for design analysis and mitigation measures. These guideline have been followed in this report. The potential geologic and geotechnical engineering impacts to development identified herein are summarized in the following Table 6 – Summary of Engineering Geologic/Geotechnical Engineering Impacts and Corresponding Mitigation Measure. This analysis pertains to the area where structures are proposed.



METHOD OF PREPARATION

Initial tsunami modeling was performed by the University of Southern California (USC) Tsunami Research Center funded through the California Emergency Management Agency (CalEMA) by the National Tsunami Hazard Mitigation Program. The tsunami modeling process utilized the MOST (Method of Splitting Tsunamis) computational program (Version 0), which allows for wave evolution over a variable bathymetry and topography used for the inundation mapping (Titov and Gonzalez, 1997; Titov and Synolakis, 1998).

The bathymetric/topographic data that were used in the tsunami models consist of a series of nested grids. Near-shore grids with a 3 arc-second (75- to 90-meters) resolution or higher, were adjusted to "Mean High Water" sea-level conditions, representing a conservative sea level for the intended use of the tsunami modeling and mapping.

A suite of tsunami source events was selected for modeling, representing realistic local and distant earthquakes and hypothetical extreme undersea, near-shore landslides (Table 1). Local tsunami sources that were considered include offshore reverse-thrust faults, restraining bends on strike-slip fault zones and large submarine landslides capable of significant seafloor displacement and tsunami generation. Distant tsunami sources that were considered include great subduction zone events that are known to have occurred historically (1960 Chile and 1964 Alaska earthquakes) and others which can occur around the Pacific Ocean "Ring of Fire."

In order to enhance the result from the 75- to 90-meter inundation grid data, a method was developed utilizing higher-resolution digital topographic data (3- to 10-meters resolution) that better defines the location of the maximum inundation line (U.S. Geological Survey, 1993; Intermap, 2003; NOAA, 2004). The location of the enhanced inundation line was determined by using digital imagery and terrain data on a GIS platform with consideration given to historic inundation information (Lander, et al., 1993). This information was verified, where possible, by field work coordinated with local county personnel.

The accuracy of the inundation line shown on these maps is subject to limitations in the accuracy and completeness of available terrain and tsunami source information, and the current understanding of tsunami generation and propagation phenomena as expressed in the models. Thus, although an attempt has been made to identify a credible upper bound to inundation at any location along the coastline, it remains possible that actual inundation could be greater in a major tsunami event.

This map does not represent inundation from a single scenario event. It was created by combining inundation results for an ensemble of source events affecting a given region (Table 1). For this reason, all of the inundation region in a particular area will not likely be inundated during a single tsunami event.

References:

Intermap Technologies, Inc., 2003, Intermap product handbook and quick start guide: Intermap NEXTmap document on 5-meter resolution data, 112 p.

Lander, J.F., Lockridge, P.A., and Kozuch, M.J., 1993, Tsunamis Affecting the West Coast of the United States 1806-1992: National Geophysical Data Center Key to Geophysical Record Documentation No. 29, NOAA, NESDIS, NGDC, 242 p.

National Atmospheric and Oceanic Administration (NOAA), 2004, Interferometric Synthetic Aperture Radar (ISAR) Digital Elevation Models from GeoSAR platform (EarthData): 3-meter resolution data.

Titov, V.V., and Gonzalez, F.I., 1997, Implementation and Testing of the Method of Tsunami Splitting (MOST): NOAA Technical Memorandum ERL PMEL – 112, 11 p.

Titov, V.V., and Synolakis, C.E., 1998, Numerical modeling of tidal wave runup: Journal of Waterways, Port, Coastal and Ocean Engineering, ASCE, 124 (4), pp 157-171.

U.S. Geological Survey, 1993, Digital Elevation Models: National Mapping Program, Technical Instructions, Data Users Guide 5, 48 p.

TSUNAMI INUNDATION MAP
FOR EMERGENCY PLANNING

State of California ~ County of Orange

NEWPORT BEACH QUADRANGLE

March 15, 2009




Table 1: Tsunami sources modeled for the Orange County coastline.

Sources (M = moment magnitude used in modeled event)		Areas of Inundation Map Coverage and Sources Used		
		Long Beach Harbor	Newport Harbor	Dana Point
Local Sources	Catalina Fault	X	X	X
	Channel Island Thrust Fault		X	X
	Newport-Inglewood Fault	X	X	X
	San Mateo Thrust Fault			X
	Palos Verdes Submarine Landslide #1	X	X	
Distant Sources	Palos Verdes Submarine Landslide #2	X	X	
	Cascadia Subduction Zone #3 (M9.2)	X		X
	Central Aleutians Subduction Zone#1 (M8.9)	X		X
	Central Aleutians Subduction Zone#2 (M8.9)	X	X	X
	Central Aleutians Subduction Zone#3 (M9.2)	X	X	X
	Chile North Subduction Zone (M9.4)	X	X	X
	1960 Chile Earthquake (M9.3)	X	X	X
	1952 Kamchatka Earthquake (M9.0)		X	X
	1964 Alaska Earthquake (M9.2)	X	X	X
	Japan Subduction Zone #2 (M8.8)	X		X
	Kuril Islands Subduction Zone #2 (M8.8)	X		X
	Kuril Islands Subduction Zone #3 (M8.8)	X		X
	Kuril Islands Subduction Zone #4 (M8.8)	X		X

MAP EXPLANATION

- Tsunami Inundation Line
- Tsunami Inundation Area

PURPOSE OF THIS MAP

This tsunami inundation map was prepared to assist cities and counties in identifying their tsunami hazard. It is intended for local jurisdictional, coastal evacuation planning uses only. This map, and the information presented herein, is not a legal document and does not meet disclosure requirements for real estate transactions nor for any other regulatory purpose.

The inundation map has been compiled with best currently available scientific information. The inundation line represents the maximum considered tsunami runup from a number of extreme, yet realistic, tsunami sources. Tsunamis are rare events; due to a lack of known occurrences in the historical record, this map includes no information about the probability of any tsunami affecting any area within a specific period of time.

Please refer to the following websites for additional information on the construction and/or intended use of the tsunami inundation map:

State of California Emergency Management Agency, Earthquake and Tsunami Program: <http://www.oes.ca.gov/WebPage/oeswebsite.nsf/Content/B1EC51BA215931768825741F005E8D80?OpenDocument>

University of Southern California – Tsunami Research Center: <http://www.usc.edu/dept/tsunamis/2005/index.php>

State of California Geological Survey Tsunami Information: http://www.conservation.ca.gov/cgs/geologic_hazards/Tsunami/index.htm


National Oceanic and Atmospheric Agency Center for Tsunami Research (MOST model): <http://nctr.pmel.noaa.gov/time/background/models.html>

MAP BASE

Topographic base maps prepared by U.S. Geological Survey as part of the 7.5-minute Quadrangle Map Series (originally 1:24,000 scale). Tsunami inundation line boundaries may reflect updated digital orthophotographic and topographic data that can differ significantly from contours shown on the base map.

DISCLAIMER

The California Emergency Management Agency (CalEMA), the University of Southern California (USC), and the California Geological Survey (CGS) make no representation or warranties regarding the accuracy of this inundation map nor the data from which the map was derived. Neither the State of California nor USC shall be liable under any circumstances for any direct, indirect, special, incidental or consequential damages with respect to any claim by any user or any third party on account of or arising from the use of this map.



**TABLE 6 – SUMMARY OF ENVIRONMENTAL GEOLOGIC/GEOTECHNICAL
ENGINEERING IMPACTS AND CORRESPONDING MITIGATION MEASURES**
(Modified from CDMG Note 46)

	Degree of Impact Prior to or During Development			Mitigation Measures		Degree of Impact After Development		
Geologic/ Geotechnical Engineering Impacts	Less-Than Significant Impact	Potentially Significant Impact	Significant Impact	Code Conformance	Code Conformance with Mitigation Measures as Outlined in this Report	Less-Than Significant Impact	Potentially Significant Impact	Significant Impact
Seismic Hazards		x		x		x		
Seismic Ground Shaking								
Liquefaction		x			x	x		
Seismically Induced Settlement		x			x	x		
Ground Lurching	x				x	x		
Flooding (due to dam or levee failure)	x				x	x		
Surface Fault Rupture	x			x		x		
Tsunami	x					x		
Seiches not applicable								
Slope Stability								
Landslides and Slope Instability not applicable								
Trench-Wall Stability		x		x		x		
Groundwater	x				x	x		
Change in Ground Water Level								
Foundation Stability	x					x		
Compressible Soils/Collapsible Soils								
Expansive Soils		x			x	x		
Corrosive Soils unknown								
Rippability not applicable								
Regional Subsidence	x					x		
Erosion	x					x		
Flooding (due to inclement weather; 100-year flood)	x				x	x		
Loss of Mineral Resources	x					x		
Volcanic Hazards	x					x		
Lava Flow								
Ash Fall	x					x		

9.0 PRELIMINARY GRADING CONSIDERATIONS

The preliminary grading considerations presented herein are provided for use in preliminary planning for development of the site. Specific details of grading recommendations will be presented in a future report during the design phase based on formal grading plan at the 40-scale level, when they are developed. Presented in the

following are grading considerations which should be included in future planning phases for the subject development:

- Prior to grading operations it will be necessary to remove all existing construction, including utilities, within the limits of the planned grading. Structure removal should include foundations and flatwork. Concrete fragments and debris from site demolition operations should be disposed off-site.
- Abandoned underground utilities should be cut off at least 5 feet from the planned limits of planned structures. The ends of cut-off lines should be plugged and capped in accordance with local ordinances.
- Following site preparation operations, it is recommended that the existing native soils disturbed by demolition activities should be removed completely and replaced with engineered compacted fill. The extent of removals will be determined after the demolition of the existing improvements.
- In general, temporary excavations greater than 5 feet in vertical height should be made no steeper than 1:1 (horizontal to vertical). Special construction techniques, such as slot cutting, may be utilized if excavations are greater than 5 feet vertical and site constraints preclude use of temporary slope cuts.
- The acceptability of excavation bottoms should be evaluated by the Project Geotechnical Engineer prior to placing approved fill soils. Approved excavation bottoms should be thoroughly moisture conditioned, as necessary, to 1-3 percentage points above optimum moisture content depending on the soil type exposed, scarified to a depth of about 8 inches and compacted to minimum 90 percent of the laboratory maximum dry density (ASTM: D 1557). Fill materials should be placed in loose lifts not exceeding 6-inches in thickness, moisture conditioned to 1-3 percentage points above optimum moisture content, depending on the soil type, and compacted to at least 90 percent relative compaction based on the laboratory maximum dry density. All grading should be performed under the observation and testing of the Project Geotechnical Engineer or his representative.
- Fill materials should consist of clean onsite or imported soils and should be free of vegetation, hazardous materials, over-size rocks, construction debris and any other organic or deleterious materials.
- The shrinkage of excavated soils (within upper 5 feet from the existing grade) upon compaction as engineered fill is anticipated to be on the order of 5 percent. The above shrinkage factor does not include losses due to stripping and removal of organic soils, if present.

10.0 FOUNDATION CONSIDERATION

10.1 General:

Site remedial grading is recommended as noted previously and will provide a site suitable for the proposed development. Foundation considerations should include the following:

- Portions of the site soils exhibit expansive characteristics. In order to reduce the effects of expansive soils and potential settlement, the use of post-tensioned slab on grade foundations can be considered. These slabs should be designed in accordance with the applicable Uniform Building Code and local jurisdictional requirements.
- Specific recommendations for foundations are planned to be provided at a later date during subsequent design/plan development phases and the types of structures are known.

10.2 Other Construction Considerations:

Recommendations for streets, paved areas, utilities, and geotechnical drainage considerations are to be provided once design concepts are finalized and preliminary grading and development plans are formulated. For preliminary planning purposes, the general specification given in the current Standard Specifications for Public Works (Green Book), County of Orange and City jurisdictional guidelines may be used, as applicable.

Special considerations should be given to provide appropriate environmental control of drainage and surface/subsurface runoff. Many of the BMP's for responsible drainage control can be incorporated as the project progresses into the planned development without significant obtrusiveness. These devices can be incorporated with landscape features to recover water resources from drainage for beneficial uses. The design and incorporation of drainage control devices should be a focus of future study.

11.0 CONCLUSIONS

This report presents general geotechnical and engineering geologic guidelines and considerations that should be taken into account to appropriately develop more detailed grading plans and design criteria from the preliminary grading plans. Additional study and refinement of the recommendations present is anticipated concordant with more detailed plan development.

It is the conclusion of this firm that the site can be remediated to address the main geotechnical issues. Further, it is our opinion that provided the project is developed and constructed with appropriate engineering and design, the project is feasible from geotechnical and engineering geologic standpoints. It is also our opinion that from an engineering geologic stand point provided the project is developed and constructed with appropriate engineering, design and mediation considerations, the project will not adversely impact adjacent properties.

12.0 LIMITATIONS

This report has been prepared for the exclusive use of Uptown Newport LP and their design consultants relative to the design and construction of the proposed project. This report is not intended for other parties, and it may not contain sufficient information for other purposes. The recommendations presented herein are of a general/conceptual nature and will be refined and detailed in forthcoming reports specific to various aspects of development. As such, the current recommendations may be subject to revision as additional detail of the project is made and additional data is developed, as well as in response to jurisdictional review requirements. This report is based on the project as described and the information obtained as described herein.


The Owner or Owner Representative should make sure that the information and preliminary recommendations presented in this report are brought to the attention of the Project Architect and Project Engineer and incorporated into the project plans.

The findings contained in this report are based upon our evaluation and interpretation of the information obtained from limited borings and the results of the laboratory testing and engineering analysis. The opinions and recommendations provided were based on the assumption that geotechnical conditions, which exist across the site, are similar to those observed in the test excavation. The condition and characteristics of the subsurface materials at locations and depths other than those excavated and observed may be different and no representations are made as to their quality and engineering properties. Should any conditions encountered during construction differ from those described herein, this office should be contacted immediately for evaluation of the actual conditions and for appropriate recommendations prior to continuation or work.


The findings and recommendations present herein were obtained in accordance with currently accepted professional engineering principles and practice in the field of geologic and geotechnical engineering and reflect our best professional judgment. We make no other warranty, either express or implied.

We appreciate the opportunity to be of service and look forward to working with you and the other project consultants. If you have any questions or require additional information, please contact our office.

Respectfully submitted,
GINTER & ASSOCIATES, INC.


By: 
David H. Ginter
President



By: 
Vela "Ganesh" Ganeshwara
Consulting Geotechnical Engineer



Addressee: 4 hard copies/4 digital copies
Gavin Powell, Hall & Foreman, Inc. (1 hard copy/1 digital)



CROSS-SECTION A-A'

HORIZONTAL SCALE: 1"=200'
VERTICAL SCALE: 1"= 50'

Legend




OLIVE GREEN CLAY AND SILTY CLAY

FINE TO COARSE GRAINED SANDS
WITH SOME SILTS AND GRAVELS



PERCHED GROUNDWATER



APPROXIMATE GEOLOGIC CONTACT



PROJECT NO. :

116-02

DATE :

Nov., 2011

OVERALL SITE
1 SUBTERRANEAN PARKING LEVEL



OVERALL EARTHWORK QUANTITIES

RAW CUT: 98,500 C.Y.
RAW FILL: 114,100 C.Y.

EARTHWORK VOLUME RANGES			
Color	Range	Beg. Range	End Percent Area (S.F.)
	-15.00	-10.00	0.0 132
	-10.00	-5.00	28.5 311,313
	-5.00	0.00	18.4 200,805
	0.00	5.00	28.1 306,032
	5.00	10.00	19.6 214,117
	10.00	15.00	4.2 46,283
	15.00	20.00	1.1 12,313

Legend

GB-16 APPROXIMATE LOCATION OF HOLLOWSTEM BORING BY GINTER & ASSOCIATES, 2011

CPT-9 APPROXIMATE LOCATION OF CPT BY GINTER & ASSOCIATES, 2011


B APPROXIMATE LOCATION OF BORING BY JACOB & HERNER, 2010

B APPROXIMATE LOCATION OF BORING BY GLOBUS, 1987

B-24 APPROXIMATE LOCATION OF HOLLOWSTEM BORING BY DAVIES & MOORE, Sept/Oct. 1986

APPROXIMATE LOCATION OF HOLLOWSTEM BORING BY DAVIES & MOORE, Sept/Oct. 1986

A CROSS-SECTION LINE



LAST REVISED: 10/23/11

GEOTECHNICAL MAP

PROJECT NO.: 116-02
DATE: Nov., 2011

LIST OF APPENDICES

APPENDIX I	CBC Seismic Design Parameters
APPENDIX II	Boring Logs GB-1 through GB-16 by Ginter & Associates, Inc.
APPENDIX III	Cone Penetrometer Tests Assigned by Ginter & Associates, Inc.
APPENDIX IV	Laboratory Testing Assigned by Ginter & Associates, Inc.
APPENDIX V	Liquefaction Analysis for Ginter & Associates, Inc.
APPENDIX VI	Boring Logs by Others
APPENDIX VII	Laboratory Testing by Others

APPENDIX I

CBC SEISMIC DESIGN PARAMETERS

CBC SEISMIC DESIGN PARAMETERS

Upper Newport Village

Project No. 116-02

Determined Utilizing

USGS EARTHQUAKE GROUND MOTION PARAMETERS

Version 5.1.0 (Revised 2/10/2011)

Conterminous 48 States

2005 ASCE 7 Standard

Latitude = 33.662924

Longitude = -117.859706

Spectral Response Accelerations Ss and S1

Ss and S1 = Mapped Spectral Acceleration Values

Site Class B - Fa = 1.0 ,Fv = 1.0

Data are based on a 0.01 deg grid spacing

Period	Sa
--------	----

(sec)	(g)
-------	-----

0.2	1.588 (Ss, Site Class B)
-----	--------------------------

1.0	0.563 (S1, Site Class B)
-----	--------------------------

Conterminous 48 States

2005 ASCE 7 Standard

Latitude = 33.662924

Longitude = -117.859706

Spectral Response Accelerations SMs and SM1

SMs = Fa x Ss and SM1 = Fv x S1

Site Class B - Fa = 1.0 ,Fv = 1.0

Period	Sa
--------	----

(sec)	(g)
-------	-----

0.2	1.588 (SMs, Site Class B)
-----	---------------------------

1.0	0.563 (SM1, Site Class B)
-----	---------------------------

Conterminous 48 States

2005 ASCE 7 Standard

Latitude = 33.662924

Longitude = -117.859706

Design Spectral Response Accelerations SDs and SD1

SDs = 2/3 x SMs and SD1 = 2/3 x SM1

Site Class B - Fa = 1.0 ,Fv = 1.0

Period	Sa
--------	----

(sec)	(g)
-------	-----

0.2	1.058 (SDs, Site Class B)
-----	---------------------------


1.0	0.375 (SD1, Site Class B)
-----	---------------------------

Peak Ground Acceleration Data
Upper Newport Villiage
Project No. 116-02
Dertermined Utilizing
EARTHQUAKE GROUND MOTION PARAMETERS
Version 5.1.0 (Revised 2/10/2011)

Conterminous 48 States
2002 Data
Hazard Curve for PGA
Latitude = 33.662924
Longitude = -117.859706
Data are based on a 0.05 deg grid spacing
Frequency of Exceedance values less than
1E-4 should be used with caution.

Ground Motion (g)	Frequency of Exceedance (per year)
0.005	7.9551E-01
0.007	7.0548E-01
0.010	5.9594E-01
0.014	4.7454E-01
0.019	3.528E-01
0.027	2.4532E-01
0.038	1.599E-01
0.053	9.6607E-02
0.074	5.4074E-02
0.103	2.8307E-02
0.145	1.3772E-02
0.203	6.6168E-03
0.284	3.2092E-03
0.397	1.5477E-03
0.556	6.8763E-04
0.778	2.6442E-04
1.090	8.2816E-05
1.520	2.0254E-05
2.130	3.3477E-06

Ground Motion (g)	Freq. of Exceed. (per year)	Return Pd. %	P.E. (years)	Exp. Time (years)
0.3447	2.1053E-03	475.00	10.00	50.0



SOURCE: USGS SEISMIC HAZARD MAPS FOR THE CONTERMINOUS UNITED STATES, 2005

PEAK HORIZONTAL ACCELERATION 10 PERCENT PROBABILITY OF EXCEEDANCE IN 50 YEARS

APPENDIX II

BORINGS GB-1 THROUGH GB-16
BY GINTER & ASSOCIATES, INC.



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02
DATE STARTED: 9/8/11
DATE FINISHED: 9/8/11
DRILLER: Gregg
TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village
GROUND ELEV: 49
KELLEY WT/DRIVE/DROP: 140 lb./30"

BORING DESIG. GB-16
LOGGED BY: BW
SHEET 2 OF 2

NOTES:

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
40			R	7/10/13		Clay, bluish gray and olive gray, moist, stiff, plastic, frequent fossil bivalve mollusk shell fragments.	87	32
45			SPT	5/6/6		Clay and Silty Clay, dark bluish gray, very moist, stiff, occasional bivalve mollusk shell fragments.		
50			R	10/22/30		Clayey Sand and Sandy Clay, dark gray, olive gray and olive brown, moist, stiff/dense.	119	9
						Total Depth 51.5 Feet. No Water.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #	116-02	PROJECT NAME	Upper Newport Village	BORING DESIG.	GB-1
DATE STARTED	8/29/11	GROUND ELEV.	53.5	LOGGED BY:	BW
DATE FINISHED	8/29/11	KELLEY WT/DRIVE/DROP:	140 lb./30"	SHEET	1 OF 2
DRILLER	Gregg	NOTES:			
TYPE OF DRILL RIG	Hollow Stem				

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
5						Artificial Fill (Af): 0-6": Asphaltic Concrete and base material. 6" to 4.75 feet: Clayey Silt, brown and yellowish brown, moist, stiff.		
10			R	6/11/17		Terrace/Bay Deposits: Sandy Clay, and Silty Clay, tan, brown, gray, and reddish brown, moist, medium stiff.		
			R	7/11/19		Silty Sand, reddish brown, yellowish brown and light gray, slightly moist to moist, dense, fine grained.	101	11
			R	8/13/16		Silty Sand, grayish tan and brown, slightly moist to moist, dense, fine grained.	110	12
15			SPT	7/9/14		Silty Sand, grayish tan and light gray, slightly moist to moist, dense, fine grained, micaceous.		
20			R	18/20/25		Sand, tan and yellowish tan, moist, dense, medium-grained, increasing moisture.	106	8
25			SPT	11/14/22		Silty Sand, yellowish gray and yellowish tan, very moist to saturated, dense, medium-grained, occasional fossil mollusk fragments and subround pebbles (to ½ inch)		
30			R	10/13/15		▽ Water at approximately 30 feet Clay and Silty Clay, olive green and olive gray, very moist, stiff, occasional bivalve mollusk shell fragments.	86	36
35			SPT	8/9/12		Silty Clay and Clay, dark gray, very moist, stiff, occasional bivalve mollusk shell fragments.		
40			R	7/9/11		Clay, dark gray, very moist, stiff.	90	31



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02

DATE STARTED: 8/29/11

DATE FINISHED: 8/29/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 53.5

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-1

LOGGED BY: BW

SHEET 2 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	7/9/11		Clay, dark gray, very moist, stiff.	90	31
45			SPT	5/6/8		Sandy Clay, medium gray to dark gray, very moist, stiff.		
50			R	7/9/12		Sandy Clay and Clayey Sand, dark gray and dark bluish gray, very moist, stiff, secondary carbonate along clay/sand interfaces.	107	19
55			SPT	9/11/14		Silty Sand and Fine-Grained Sand, light gray, slightly moist to moist, dense.		
60			R	7/10/13		Sandy Clay and Clay, gray and dark bluish gray, very moist, stiff.	113	10
65			SPT	13/15/20		Fine-Grained Sand, light gray, slightly moist to moist, dense.		
70			R	13/25/30		Medium-Grained Sand, reddish brown, tan and gray, slightly moist to moist, dense to hard.	99	7
						Total Depth 71.5 Feet. Water at 30 Feet.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

DATE STARTED: 8/30/11

DATE FINISHED: 8/30/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 53

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-2

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-12": Asphaltic Concrete and base material 12" to 4 feet: Sand and lesser Silty Sand, reddish brown, moist, dense, medium grained.		
5			R	6/8/13		Terrace/Bay Deposits: Sandy Silt, tan, gray, and reddish brown, moist, stiff, micaceous.	105	18
10			R	8/14/23		Sandy Silt and Silty Clay, olive gray, olive brown, reddish brown and tan, moist, stiff, occasional carbonate blebs and stringers.	107	19
			R	10/22/27		Silty Sand and Sandy Silt, gray, tan and reddish brown, slightly moist to moist, dense/stiff.	99	21
15			SPT	8/8/10		Silty Sand, reddish brown and tan, slightly moist dense, fine grained, micaceous. At 16.4 feet: Sandy Clay, light gray to olive gray, moist, stiff.		
20			SPT	7/10/16		Clayey Silt, olive gray to olive green, moist, stiff.		
25			R	8/13/11		Sandy Clay, olive gray and light olive green, moist, stiff, medium plastic, occasional fossil mollusk fragments. Minor Free water on outside of sampler.	108	19
30			SPT	7/10/12		Sandy Clay and Silty Clay, olive brown and yellowish brown, moist, stiff.		
35			R	8/9/10		Silty Clay and Clay, olive green to olive brown, moist, stiff, plastic.	92	31
40			SPT	7/8/10		Clay, dark bluish gray, very moist, stiff, highly plastic.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02
DATE STARTED: 8/30/11
DATE FINISHED: 8/30/11
DRILLER: Gregg
TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village
GROUND ELEV: 53
KELLEY WT/DRIVE/DROP: 140 lb./30"

BORING DESIG. GB-2
LOGGED BY: BW
SHEET 2 OF 2

NOTES:

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
40			SPT	7/8/10		Clay, dark bluish gray, very moist, stiff, highly plastic.		
45			R	8/9/12		Clay, dark bluish gray, very moist, stiff, highly plastic.	102	22
50			SPT	7/8/10		Clay and Clayey Sand, gray and bluish gray, very moist, stiff. Total Depth 51.5 Feet. Minor Water at 25 Feet.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT # 116-02

DATE STARTED: 8/30/11

DATE FINISHED: 8/30/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 55

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-3

LOGGED BY BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-10": Asphaltic Concrete and base material. 10" to 4.75 feet: Sand and Silty Sand, reddish brown to brown moist, dense.		
5			R	8/10/12		Terrace/Bay Deposits: Silty Sand, reddish brown to brown, moist, dense.	109	10
10			R	9/10/18		Sand, tan and grayish brown, slightly moist to moist, dense, micaceous, fine-grained.	99	3
			R	12/18/24		Sand and Silty Sand, yellowish brown to brown, slightly moist to moist, dense, micaceous, fine-grained.	103	20
15			SPT	11/12/16		Silty Sand, grayish tan and light gray, slightly moist to moist, dense, fine grained, micaceous.		
20			R	8/13/20		Silty Sand and Sand, reddish brown, tan and yellowish brown, slightly moist to moist, dense, fine grained, micaceous.	105	14
25			SPT	19/30/35		Sand and lesser Silty Sand, yellowish tan to olive tan, slightly moist, dense, micaceous.		
30			R	11/14/16		▽ Water at approximately 30 feet Sand and Gravelly Sand, with lesser Silty Sand, tan, yellowish brown, reddish brown, very moist to saturated, frequent bivalve mollusk shell fragments. Minor free water on sampler.	103	20
35			SPT	6/8/11		Silty Clay and Clay, olive brown and yellowish brown, moist, stiff, plastic.		
40			R	9/10/13		Clay, bluish gray and gray, very moist, stiff, plastic, fossil fragments.	94	28



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02		PROJECT NAME: Upper Newport Village		BORING DESIG. GB-3	
DATE STARTED: 8/30/11		GROUND ELEV: 55		LOGGED BY: BW	
DATE FINISHED: 8/30/11		KELLEY WT/DRIVE/DROP: 140 lb./30"		SHEET 2 OF 2	
DRILLER: Gregg		NOTES:			
TYPE OF DRILL RIG: Hollow Stem					

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	9/10/13		Clay, bluish gray and gray, very moist, stiff, plastic,fossil fragments.	94	28
45			SPT	6/9/13		Clayey Silt and Clay, greenish gray to olive gray, very moist, stiff, medium plastic, frequent bivalve mollusk shell fragments.		
50			R	7/10/13		Silty Clay, dark bluish gray to gray, moist, stiff, plastic, frequent bivalve mollusk shell fragments.	101	23
55			SPT	8/10/16		Sandy Clay and Clay, dark bluish gray, moist, stiff, locally plastic, occasional bivalve mollusk shell fragments.		
60			R	10/14/28		Sandy Clay and Clay, dark bluish gray, moist, stiff, low plasticity, occasional bivalve mollusk shell fragments.	105	22
65			SPT	7/8/13		Silty Clay, olive green, dark bluish gray and dark gray, moist, stiff medium plastic.		
70			R	11/23/30		Sand, light gray and bluish gray, moist to very moist, dense to very dense.	109	11
						Total Depth 71.5 Feet. Minor Water at 30 Feet.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

DATE STARTED: 8/31/11

DATE FINISHED: 8/31/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 51

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-4

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-10": Asphaltic Concrete and base material 10" to 4.75 feet: Silty Clay and Clayey Silt, brown to reddish brown, moist, stiff		
5			R	10/11/13		Terrace/Bay Deposits: Silty Clay and Clayey Silt, yellowish brown, brown and olive brown, moist, stiff.	97	22
10			R	9/12/20		Silty Clay and Silty Sand olive brown and yellowish brown, moist, stiff/dense. Hard calcified layers at Clay/Sand contact- 8.25 feet	90	19
			R	8/12/17		Clayey Silt, olive gray to yellowish brown, moist, stiff.	109	15
15			SPT	10/16/19		Sand and Gravelly Sand, yellowish tan, slightly moist, dense, clean, well-sorted.		
20			R	13/16/30		Sand and lesser Gravelly Sand, light grayish tan, slightly moist, dense, micaceous, clean, well-sorted. Increasing moisture 23-25 feet.	106	2
25			SPT	7/10/14		Sand and Gravelly Sand, brown and grayish brown, saturated, dense.		
30			R	12/12/16		Base of Sand and gravelly Sand @ 30.25 Feet. Silty Clay and Clay, olive green to olive brown, moist, stiff, plastic.	91	32
35			SPT	6/7/9		Silty Clay and lesser Sandy Silty lenses, olive brown, dark gray and olive gray, very moist, stiff, medium plastic to very plastic.		
40			R	11/4/18/27		Clay, dark bluish gray, very moist, stiff, highly plastic, frequent bivalve mollusk shell fragments.	87	34



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #:1016-02

DATE STARTED: 8/31/11

DATE FINISHED: 8/31/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 51

KELLEY WT/DRIVE/DROP: 140 lb./30"

BORING DESIG. GB-4

LOGGED BY: BW

SHEET 2 OF 2

NOTES:

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	14/18/27		Clay, dark bluish gray, very moist, stiff, highly plastic, frequent bivalve mollusk shell fragments.	87	34
45			SPT	5/7/8		Clay, dark bluish gray, very moist, stiff, highly plastic, frequent bivalve mollusk shell fragments. Occasional thin Silty Sand lenses.		
50			R	10/12/17		Silty Sand and lesser Clayey Sand, gray and light gray, very moist, stiff, occasional bivalve mollusk shell fragments.. Total Depth 51.5 Feet. Perched Water at 24 Feet.	110	17



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

PROJECT NAME: Upper Newport Village

BORING DESIG.: GB-5

DATE STARTED: 8/31/11

GROUND ELEV.: 50.5

LOGGED BY: BW

DATE FINISHED: 8/31/11

KELLEY WT/DRIVE/DROP: 140 lb./30"

SHEET 1 OF 2

DRILLER: Gregg

NOTES:

TYPE OF DRILL RIG: Hollow Stem

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-10": Asphaltic Concrete and base material 10" to 4.5 feet: Silty Clay and Clayey Silt, brown to reddish brown, moist, stiff		
5			B	6/8/9		Terrace/Bay Deposits: Silty Clay and Clayey Silt, brown to yellowish brown, moist, stiff.	94	22
10			R	6/15/19		Sand and lesser Silty Sand, tan, grayish tan and reddish brown, slightly moist, dense, fine-grained, micaceous.		
			R	13/20/30		Sand and lesser Silty Sand, tan, grayish tan and reddish brown, slightly moist, dense, fine-grained, micaceous.	103	15
15			SPT	11/18/22		Sand, light grayish brown, slightly moist, dense, fine-grained, micaceous.		
20			R	16/25/27		Sand, reddish brown and tan, slightly moist to moist, dense, fine-grained, micaceous.	101	7
25			SPT	9/13/20		Sand and Gravelly Sand, reddish tan and grayish tan, slightly moist, dense, fine-grained, micaceous.		
30			R	7/10/18		Silty Clay and Clay, olive gray to olive brown and reddish brown, moist, stiff, plastic.	89	33
35			SPT	6/7/11		Silty Clay and Clay olive brown to olive gray, moist, stiff, plastic.		
40			R	8/9/10		Clay and lesser Silty Clay, olive gray to olive brown and reddish brown, moist to very moist, stiff, plastic.	83	42



GINTER AND ASSOCIATES, INC
LOG OF EXPLORATORY BORING

PROJECT #:1016-02

DATE STARTED: 8/31/11

DATE FINISHED: 8/31/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 50.5

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-5

LOGGED BY: BW

SHEET 2 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	14/18/27		Clay and lesser Silty Clay, olive gray to olive brown and reddish brown, moist to very moist, stiff, plastic.	83	42
45			SPT	5/7/8		Clay, dark bluish gray, very moist, stiff, highly plastic, frequent bivalve mollusk shell fragments. Occasional thin Silty Sand lenses.		
50			R	10/12/17		Silty Sand and lesser Clayey Sand, gray and light gray, very moist, stiff, occasional bivalve mollusk shell fragments.. Total Depth 51.5 Feet. Minor Water at 24 Feet.	102	19



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

DATE STARTED: 9/7/11

DATE FINISHED: 9/7/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 55

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-6

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-10": Asphaltic Concrete and base material 10" to 3 feet: Silty Clay, dark brown, moist, stiff, minor organics.		
5			B @ 4.5' R	7/9/12		Terrace/Bay Deposits: Silty Sand and Sandy Silt, reddish brown, slightly moist to moist, soft to stiff.	104	15
10			R	8/9/13		Sand and lesser Silty Sand, tan to brown, slightly moist, loose to medium dense, micaceous.	101	2
			R	10/10/13		Sand and Silty Sand, brown and light brown, slightly moist to moist, dense, fine-grained.	96	5
15			SPT	6/10/13		Clayey Sand and Clayey Silt, brown and reddish brown, moist, dense.		
20			R	8/10/14		Silty Sand and Clayey Sand, brown and yellowish tan, slightly moist to moist, dense, fine-grained.	102	19
25			SPT	13/15/22		Sand, yellowish tan, slightly moist to moist, dense, fine-medium grained.		
30			R	14/30/35		Sand, yellowish tan, slightly moist to moist, dense, fine-medium grained, micaceous.	99	25
35			SPT	13/15/18		Silty Sand and lesser Clayey Sand, olive brown and tan, moist, dense, micaceous. Fining Downward.		
40			R	5/7/11		Clayey Sand, olive brown and reddish brown, moist to very moist, medium dense.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02
DATE STARTED: 9/7/11
DATE FINISHED: 9/7/11
DRILLER: Gregg
TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village
GROUND ELEV: 55
KELLEY WT/DRIVE/DROP: 140 lb./30"

BORING DESIG. GB-6
LOGGED BY: BW
SHEET 2 OF 2

NOTES:

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
40			R	14/18/27		Clayey Sand, olive brown and reddish brown, moist to very moist, medium dense.		
45			SPT	5/7/8		Sand, yellowish tan, moist to very moist, dense to very dense.		
50			R	10/12/17		Sand, reddish brown and yellowish brown, slightly moist to moist, dense to very dense. Total Depth 51.5 Feet. Minor Water at 24 Feet.	92	6



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

DATE STARTED: 9/2/11

DATE FINISHED: 9/2/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 50

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-7

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-9": Asphaltic Concrete and base material. 9" to 4.75 feet: Sand and Silty Sand, reddish brown to brown slightly moist, dense.		
5			B			Terrace/Bay Deposits: Silty Sand, reddish brown to brown, moist, dense to hard.		
10			R	6/7/11		Clayey Sand and Silty Sand, reddish brown, slightly moist, dense to hard.	120	8
			R	17/25/33		Clayey Sand and Silty Sand, reddish brown, slightly moist, dense to hard.	98	18
15			SPT	11/16/20		Silty Clay and Clay, reddish brown to olive brown, moist, stiff.		
20			R	12/18/25		Clay, greenish gray and olive gray, moist, stiff, occasional carbonate blebs.	96	23
25			SPT	8/11/14		Clay and Silty Clay, greenish gray and olive brown, very moist, stiff, medium plastic, occasional mollusk shell fragments. ∇ Water at approximately 27 feet		
30			R	13/20/34		Sand and Silty Sand, reddish brown and olive gray, very moist, dense.	99	6
35			SPT	7/7/10		Silty Clay and Clay, reddish brown and olive gray, very moist, soft to stiff, very plastic.		
40			R	10/11/18		Clayey Sand and Silty Sand, reddish brown to olive gray, very moist, dense.	104	21



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02

DATE STARTED: 9/2/11

DATE FINISHED: 9/2/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 50

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-7

LOGGED BY BW

SHEET 2 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	10/11/18		Clayey Sand and Silty Sand, reddish brown to olive gray, very moist, dense.	104	21
45			SPT	7/9/11		Silty Clay and Clay, olive brown to olive gray, very moist to saturated, stiff, very plastic. Minor Sand lenses; top 0.25 feet. Perched water at 45.25 feet (Sand/Clay contact)		
50			R	8/10/14		Silty Clay, dark bluish gray to gray, moist, stiff, plastic, frequent bivalve mollusk shell fragments.	106	21
55			SPT	10/14/16		Sandy Clay and Clay, olive brown and olive gray, moist, stiff, occasional bivalve mollusk shell fragments.		
60			R	7/9/12		Silty Clay and Clay, olive brown and olive gray, moist, stiff, occasional bivalve mollusk shell fragments.	91	29
65			SPT	6/7/14		Silty Clay and Clay, olive brown and olive gray, moist, stiff, occasional bivalve mollusk shell fragments.		
70			R	10/11/15		Clay, dark gray and olive gray, moist, stiff, occasional bivalve mollusk shell fragments.	75	41
						Total Depth 71.5 Feet. Minor Water at 27 and 42.25 Feet.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

DATE STARTED: 9/1/11

DATE FINISHED: 9/1/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 49.5

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-8

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-12": Asphaltic Concrete and base material 12" to 4.5 feet: Silty Clay and Clayey Silt, dark brown, moist, stiff.		
5			B	6/8/9		Terrace/Bay Deposits: Silty Clay and Clayey Silt, brown and dark brown, slightly moist to moist, stiff.	102	22
10			R	7/9/10		Silty Clay and Clayey Silt, brown and reddish brown, slightly moist to moist, stiff.	113	16
			R	7/7/10		Silty Clay and Clayey Silt, brown and reddish brown, moist, stiff.	113	13
15			SPT	5/6/8		Clayey Silt and Sandy Silt, reddish brown, moist, stiff.		
20			R	9/13/15		Clayey Sand and Silty Sand, reddish brown to brown, moist dense.	105	15
25			SPT	6/7/9		Silty Clay and Sandy Clay, yellowish brown and reddish brown, moist, stiff.		
30			R	6/10/11		Silty Clay and Clay, olive brown and reddish brown, moist, stiff.		
35			SPT	5/6/7		Silty Clay and Sandy Clay, olive brown to brown, moist, soft to stiff, occasional bivalve shell fragments		
40			R	6/8/15		Silty Clay and Sandy Clay, olive brown to brown, moist, soft to stiff, occasional bivalve shell fragments	92	30



GINTER AND ASSOCIATES, INC
LOG OF EXPLORATORY BORING

PROJECT #: 1016-02		PROJECT NAME: Upper Newport Village		BORING DESIG. GB-8	
DATE STARTED: 9/1/11		GROUND ELEV: 49.5		LOGGED BY: BW	
DATE FINISHED: 9/1/11		KELLEY WT/DRIVE/DROP: 140 lb./30"		SHEET 2 OF 2	
DRILLER: Gregg		NOTES:			
TYPE OF DRILL RIG: Hollow Stem					

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	8/10/14		Silty Clay and Sandy Clay, olive brown to brown, moist, soft to stiff, occasional bivalve shell fragments	92	30
45			SPT	12/20/32		Sand, olive gray to gray, mosit, dense to very dense.		
50			R	17/26/32		Sand, dark gray to gray, saturated, dense to very dense, frequent bivalve shell fragments. Total Depth 51.5 Feet. Water at 49 Feet.	113	16



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #:	116-02	PROJECT NAME:	Upper Newport Village	BORING DESIG.:	GB-9
DATE STARTED:	9/1/11	GROUND ELEV.:	49.5	LOGGED BY:	BW
DATE FINISHED:	9/1/11	KELLEY WT/DRIVE/DROP:	140 lb./30"	SHEET	1 OF 2
DRILLER:	Gregg	NOTES:			
TYPE OF DRILL RIG:	Hollow Stem				

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-12": Asphaltic Concrete and base material 12" to 4.5 feet: Silty Clay, dark brown, moist, stiff.		
5			B	6/8/10		Terrace/Bay Deposits: Silty Clay and Clayey Silt, reddish brown, gray and olive brown, moist, stiff. Occasional Sandy Clay lenses.	104	17
10			R	5/6/12		Silty Clay and Clayey Silt, reddish brown, gray and olive brown, moist, stiff. Occasional Sandy Clay lenses.	107	19
			R	8/10/16		Silty Clay and Clayey Silt, dark brown, slightly moist, porous, frequent rootlets.	109	11
15			SPT	9/16/20		Clay and Sandy Clay, reddish brown, moist, stiff to hard.		
20			R	5/7/14		Clay and lesser Silty Clay, light grayish white, moist, stiff, frequent secondary carbonate nodules (leachate/hardpan).	96	20
25			SPT	5/7/8		Silty Sand and Clayey Sand, olive gray, reddish brown, and olive brown, moist, dense.		
30			R	5/6/8		Sand, light gray, saturated, dense, medium to coarse grained, well sorted/clean.	116	11
35			SPT	7/10/16		Numerous bivalve fossils in basal portion (35-35.25 Feet)		
40			R	6/8/15		Silty Clay and Sandy Clay, olive brown to olive gray, moist, stiff, occasional bivalve shell fragments		
						Clay, dark bluish gray and dark gray, moist, stiff, plastic.	86	37



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02

DATE STARTED: 9/1/11

DATE FINISHED: 9/1/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 49.5

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-9

LOGGED BY: BW

SHEET 2 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	6/8/15		Clay, dark bluish gray and dark gray, moist, stiff, plastic.	86	37
45			SPT	14/16/17		Clayey Sand, dark gray and bluish gray, saturated, dense, frequent bivalve mollusk shell fragments.		
50			R	11/19/22		Clayey Sand, dark gray and bluish gray, saturated, dense, frequent bivalve mollusk shell fragments.	110	20
55			SPT	10/11/17		Sandy Clay and Clay, dark gray very moist, stiff/dense, medium plastic		
60			R	17/20/25		Silty Sand, Sand and lesser Clay lenses, dark gray and light gray, very moist, dense.	104	22
65			SPT	27/50 for 5"		Sand, light gray, very moist, dense, medium to coarse grained, well sorted.		
70			R	20/36/50		Silty Sand, Sand, dark gray and light gray, very moist, dense. Total Depth 71.5 Feet. Minor Water at 24 and 68 Feet.	100	22



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

DATE STARTED: 9/2/11

DATE FINISHED: 9/2/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 49.5

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-10

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-9": Asphaltic Concrete and base material 9" to 4 feet: Clayey Sand and Calyey Silt, reddish brown and brown, moist, stiff.		
5			R	8/11/12		Terrace/Bay Deposits: Clayey Sand, reddish brown and tan, slightly moist, dense, frequent carbonate nodules from 5.75 to 6 feet.	93	6
10			R	7/8/14		Sand and Gravelly Sand, reddish brown and tan, dry to slightly moist, dense, occasional pebble clasts, clean, well sorted.	104	2
			R	15/17/30		Sand, tan and grayish tan, slightly moist, dense, fine to medium-grained, micaceous.	108	1
15			SPT	10/12/22		Clayey Sand, reddish brown and olive brown, moist, dense, micaceous.		
20			R	10/10/16		Clayey Sand and Gravelly Sand, reddish brown and olive brown, slightly moist to moist, dense, micaceous.	105	13
25			SPT	12/14/18		Silty Clay and Clay, olive brown and reddish brown, moist, stiff.		
30			R	7/9/12		Silty Clay and Clay, olive brown and reddish brown, moist, stiff.	106	19
35			SPT	7/8/11		Silty Clay and Clay, brown to olive brown, moist, stiff, plastic, occasional fossil bivalve mollusk shell fragments..		
40			R	11/16/20		Clayey Sand and Sandy Clay, olive brown and yellowish brown, moist, stiff, medium plastic.	107	20



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02

DATE STARTED: 9/2/11

DATE FINISHED: 9/2/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 49.5

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-10

LOGGED BY: BW

SHEET 2 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	11/16/20		Clayey Sand and Sandy Clay, olive brown and yellowish brown, moist, stiff, medium plastic.	107	20
45			SPT	7/9/12		Clayey Sand and Sandy Clay, olive brown and yellowish brown, moist, stiff, medium plastic.		
50			R	8/8/14		Silty Clay, greenish gray and bluish gray, moist, stiff, medium plastic.	101	23
						Total Depth 51.5 Feet. No Water.		



GINTER AND ASSOCIATES, INC








LOG OF EXPLORATORY BORING

PROJECT #:	116-02	PROJECT NAME:	Upper Newport Village	BORING DESIG.:	GB-11
DATE STARTED:	9/12/11	GROUND ELEV.:	50.5	LOGGED BY:	BW
DATE FINISHED:	9/12/11	KELLEY WT/DRIVE/DROP:	140 lb./30"	SHEET	1 OF 2
DRILLER:	Gregg	NOTES: Hand Augered to 8.5 feet per Jazz Facilities Dept. request			
TYPE OF DRILL RIG: Hollow Stem					

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
5			B			Artificial Fill (Af): 0-18": Asphaltic Concrete and base material. 18" to 8.5 feet: Trench shading sand from local sewer lateral. 8.5 to 12.5 feet: Silty Clay, dark brown, moist, stiff.		
10			R	6/9/10			109	14
15			SPT	4/5/7		Terrace/Bay Deposits: Silty Sand and Sand, reddish brown to brown, moist, dense. Silty Sand and Fine-Grained Sand, reddish brown and brown, slightly moist to moist, loose to dense, micaceous.		
20			R	10/16/19			118	9
25			SPT	16/18/19		Sand, olive brown and tan, moist, dense, fine grained, increasing moisture with depth.		
30			R	8/10/17		Water at approximately 28 feet Clay and Gravelly Sand, dark gray to light gray, very moist to saturated, dense, frequent bivalve shell fragments.	80	20
35			SPT	12/18/30		Gravelly Sand, light gray to medium gray, saturated, very dense, poor recovery (approx 50% of sample fell out of sampler)		
40			R	8/9/13		Gravelly Sand, gray, saturated, dense, coarse-grained, dark gray clay in sampler shoe (approx lower 2").	120	13



NOTES:

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
40			R	8/9/13		Gravelly Sand, gray, saturated, dense, coarse-grained, dark gray clay in sampler shoe (approx lower 2").	120	13
45			SPT	7/10/13		Clay and lesser Clayey Sand, dark gray, very moist, stiff, frequent bivalve mollusk shell fragments.		
50			R	8/14/22		Clay and lesser Clayey Sand, dark gray, very moist, stiff, frequent bivalve mollusk shell fragments.	104	21
55			SPT	15/40/42		Sand, light gray and greenish gray, saturated, very dense, pervasive bivalve mollusk shell fragments from 55.5-56.5 feet		
60			R	38/50 for 5"		Sandstone (Topanga Fm?), yellowish tan to tan, slightly moist to moist, dense to hard, micaceous.	107	3
65			SPT	32/50 for 5"		Sandstone (Topanga Fm?), yellowish tan to reddish brown, slightly moist to moist, dense to hard, micaceous.		
70			R	38/50 for 5"		Sandstone (Topanga Fm?), yellowish tan to light brown, dry to slightly moist, very dense to hard, micaceous	104	2
						Total Depth 70.4 Feet. Water at 28 and 54 Feet.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

DATE STARTED: 9/9/11

DATE FINISHED: 9/9/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 51

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES: Hand Augered to 8.5 feet per Jazz Facilities Dept. request

BORING DESIG. GB-12

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
5						Artificial Fill (Af): 0-12": Asphaltic Concrete and base material. 12" to 5 feet: Silty Clay and Clayey Silt, dark brown, moist, stiff.		
10			B			Terrace/Bay Deposits: Silty Clay and Clay, reddish brown to olive brown and olive gray, moist, stiff.		
15			R	8/11/17		Silty Clay and Clay, reddish brown to olive brown and olive gray, moist, stiff.	104	18
20			SPT	5/7/9		Silty Clay, olive brown and olive gray, moist, stiff.		
25			R	8/12/16		Silty Sand and lesser Clayey Sand, reddish brown, and olive brown, slightly moist to moist, dense, fine grained.	92	13
30			SPT	10/12/24		Sand and lesser Silty Sand, brown and tan, moist, dense.		
35			R	10/13/30		<input checked="" type="checkbox"/> Water at approximately 29 feet No Recovery, saturated gravel/sand fell out of sampler.		
40			SPT	11/15/14		Sand and lesser Clayey Sand, brown and olive gray, very moist, dense, fine to medium grained, micaceous, frequent bivalve mollusk shell fragments.		
			R	10/13/20		Clay, bluish gray, very moist, stiff, plastic, frequent bivalve mollusk shell fragments.	83	37



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02
DATE STARTED: 9/9/11
DATE FINISHED: 9/9/11
DRILLER: Gregg
TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village
GROUND ELEV: 51
KELLEY WT/DRIVE/DROP: 140 lb./30"

BORING DESIG. GB-12
LOGGED BY: BW
SHEET 2 OF 2

NOTES:

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
40			R	10/13/20		Clay, bluish gray, very moist, stiff, plastic, frequent bivalve mollusk shell fragments.	83	37
45			SPT	5/5/6		Clay, bluish gray and dark gray, very moist, stiff, plastic, frequent bivalve mollusk shell fragments.		
50			R	10/14/11		Clay and Silty Clay, gray to bluish gray, very moist, stiff, very frequent bivalve mollusk shell fragments.	86	37
55			SPT	8/10/14		Clay and Sandy Clay, lgray and dark gray, saturated, dense, very frequent bivalve mollusk shell fragments.		
60			R	14/18/27		Sand and lesser Clayey Sand, gray to dark gray, saturated, dense to very dense, very frequent bivalve shell fragments.	106	22
65			SPT	10/18/21		Sand and lesser Clayey Sand, gray to dark gray, very moist, dense.		
70			R	42/50 for 5"		Sand and lesser Clayey Sand, gray to dark gray, slightly moist, dense to hard, medium to coarse grained, micaceous.	129	2
						Total Depth 70.4 Feet. Water at 28 and 54 Feet.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #:	116-02	PROJECT NAME:	Upper Newport Village	BORING DESIG.	GB-13
DATE STARTED:	9/8/11	GROUND ELEV:	51.5	LOGGED BY:	BW
DATE FINISHED:	9/8/11	KELLEY WT/DRIVE/DROP:	140 lb./30"	SHEET	1 OF 2
DRILLER:	Gregg	NOTES: Hand Augered to 8.5 feet per Jazz Facilities Dept. request			
TYPE OF DRILL RIG: Hollow Stem					

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-12": Grass and soil with underlying 4" thick pavers. 12" to 3.5 feet: Silty Clay and Clayey Silt, brown, moist, stiff.		
5						Terrace/Bay Deposits: Sand, yellowish tan and tan, slightly moist, medium dense, fine grained, micaceous.		
10			R	6/8/13		Sand, yellowish tan and tan, slightly moist, medium dense, fine grained, micaceous.	91	12
15			SPT	4/6/9		Clayey Silt and Silty Clay, brown, reddish brown and olive gray, moist, stiff, medium plastic.		
20			R	6/8/9		Silty Clay, olive brown and olive gray, moist, stiff.	103	21
25			SPT	6/11/18		Silty Clay, olive brown and olive gray, moist, stiff (to 26 feet) @ 26 feet; Sand, reddish brown, very moist to saturated, dense, fine grained.		
30			R	11/16/23		Clayey Sand and Clay, olive gray to bluish gray, moist to very moist, stiff.	85	36
35			SPT	6/7/9		Clay and Sandy Clay, olive gray, bluish gray and olive brown, moist, stiff, plastic occasional bivalve mollusk shell fragments..		
40			R	5/7/14		Clay and Silty Clay, dark bluish gray, moist, stiff, plastic.	85	35



GINTER AND ASSOCIATES, INC
LOG OF EXPLORATORY BORING

PROJECT #: 1016-02

DATE STARTED: 9/8/11

DATE FINISHED: 9/8/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 51.5

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-13

LOGGED BY: BW

SHEET 2 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			R	5/7/14		Clay and Silty Clay, dark bluish gray, moist, stiff, plastic.	85	35
45			SPT	6/9/13		Silty Clay, dark bluish gray, moist, stiff, plastic.		
50			R	8/20/50 for 5"		Clayey Sand and Sand, dark gray to olive gray, very moist, dense to very dense.	116	13
						Total Depth 51.5 Feet. Minor Water at 26.5 Feet.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 116-02

DATE STARTED: 9/1/11

DATE FINISHED: 9/1/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 50

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-14

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-9": Asphaltic Concrete and base material. 9" to 1.75 feet: Clayey Silt, brown and yellowish brown, moist, stiff. Carbonate nodules near contact		
						Terrace/Bay Deposits: Silty Sand and Clayey Sand, reddish brown, olive brown and grayish tan, moist, dense, very fine grained.	116	5
5			R	7/13/15		Silty Sand and Clayey Sand, reddish brown, yellowish brown and olive gray, moist, dense, very fine grained.	97	23
10			R	8/11/15		Silty Sand and Clayey Sand, reddish brown, yellowish brown and olive gray, moist, dense, very fine grained.	100	23
15			SPT	7/7/12		Sandy Clay, olive brown to brown, moist, stiff		
20			R	9/14/20		Sand, light grayish tan and yellowish tan, slightly moist to moist, dense, fine to medium grained.	94	11
25			SPT	10/11/17		Sand, light grayish tan, slightly moist to moist, dense, fine to medium grained.		
30			R	8/8/11		Clay and Silty Clay, dark gray to dark greenish gray, moist, soft to stiff, very frequent bivalve mollusk shell fragments.	88	33
35			SPT	5/5/7		Clay and Silty Clay, dark greenish gray, moist, soft to stiff, very frequent bivalve mollusk shell fragments.		
40			R	6/8/9		Clay, dark gray, moist to very moist, stiff, plastic	84	36



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #: 1016-02
DATE STARTED: 8/29/11
DATE FINISHED: 8/29/11
DRILLER: Gregg
TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village BORING DESIG. GB-14
GROUND ELEV: 50 LOGGED BY: BW
KELLEY WT/DRIVE/DROP: 140 lb./30" SHEET 2 OF 2

NOTES:

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
40			R	6/8/9		Clay, dark gray, moist to very moist, stiff, plastic	84	36
45			SPT	5/7/8		Sandy Clay and Clayey Sand, light gray to dark gray, very moist, stiff, micaceous.		
50			R	10/29/50 for 3"		Sand, light grayish tan and tan, slightly moist to moist, dense to hard, micaceous, medium grained, well sorted.	101	7
55			SPT	15/26/30		Sand, tan and brownish tan, slightly moist to moist, dense, fine grained, micaceous.		
60			R	18/20/25		Sand, light gray, vslightly moist to moist, dense, fine to medium grained, micaceous.	105	15
65			SPT	9/10/22		Sand, light gray, vslightly moist to moist, dense, fine to medium grained, micaceous.		
70			SPT	19/25/38		Sand, light gray, vslightly moist to moist, dense, fine to medium grained, micaceous.		
						Total Depth 71.5 Feet. No Water.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT # 116-02

DATE STARTED: 9/7/11

DATE FINISHED: 9/7/11

DRILLER: Gregg

TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village

GROUND ELEV: 50.5

KELLEY WT/DRIVE/DROP: 140 lb./30"

NOTES:

BORING DESIG. GB-15

LOGGED BY: BW

SHEET 1 OF 2

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft ³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-10": Asphaltic Concrete and base material. 10" to 4.75 feet: Clayey Sand and Sandy Clay, brown to dark brown, moist, stiff.		
5			R	6/10/11		Terrace/Bay Deposits: Silty Sand, reddish brown to yellowish brown, moist, dense.	105	19
10			R	7/11/15		Sand, yellowish brown and olive brown, to moist, dense, micaceous.	111	10
			R	6/11/19		Silty Sand and Clayey Sand, brown and olive brown, moist, dense, micaceous, fine-grained.	100	24
15			R	5/8/9		Clayey Silt and Clayey Sand, brown and olive brown, moist, dense/stiff, micaceous.	91	28
20			SPT	5/6/5		Silty Sand and lesser Clayey Sand, olive brown and yellowish brown, moist, soft/loose to medium dense, micaceous.		
25			R	10/14/22		Sand and lesser Clayey Sand, brownish yellow, moist, dense, micaceous.	106	12
30			SPT	14/20/30		Sand, yellowish brown, slightly moist, dense, fine to medium grained, clean, micaceous.		
35			R	6/8/10		Clay, bluish gray and olive gray, moist, stiff, plastic, fossil bivalve mollusk shell fragments.	84	34
40			SPT	6/7/9		Clay, bluish gray and olive gray, moist, stiff, plastic, fossil bivalve mollusk shell fragments.		






GINTER AND ASSOCIATES, INC
LOG OF EXPLORATORY BORING

PROJECT #: 1016-02
DATE STARTED: 9/7/11
DATE FINISHED: 9/7/11
DRILLER: Gregg
TYPE OF DRILL RIG: Hollow Stem

PROJECT NAME: Upper Newport Village
GROUND ELEV: 50.5
KELLEY WT/DRIVE/DROP: 140 lb./30"

BORING DESIG. GB-15
LOGGED BY: BW
SHEET 2 OF 2

NOTES:

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
40			SPT	6/7/9		Clay, bluish gray and olive gray, moist, stiff, plastic, fossil bivalve mollusk shell fragments.		
45			R	7/7/10		Clay and Silty Clay, dark bluish gray, very moist, stiff, occasional bivalve mollusk shell fragments.	102	24
50			SPT	10/16/24		Silty Sand and lesser Clayey Sand, gray and light gray, moist, dense.		
						Total Depth 51.5 Feet. No Water.		



GINTER AND ASSOCIATES, INC

LOG OF EXPLORATORY BORING

PROJECT #	116-02	PROJECT NAME	Upper Newport Village	BORING DESIG.	GB-16
DATE STARTED	9/8/11	GROUND ELEV.	49	LOGGED BY:	BW
DATE FINISHED	9/8/11	KELLEY WT/DRIVE/DROP	140 lb./30"	SHEET	1 OF 2
DRILLER	Gregg	NOTES: Hand Augered to 8 feet per Jazz Facilities Dept. request			
TYPE OF DRILL RIG	Hollow Stem				

DEPTH (ft.)	ELEV. (ft.)	CLASSIFICATION	SAMPLE TYPE	BLOWS/6"	GRAPHIC LOG	DESCRIPTION	DRY DENSITY lb/ft³	MOISTURE CONTENT (%)
						Artificial Fill (Af): 0-10": Asphaltic Concrete and base material. 10" to 3.75 feet: Silty Clay and Clayey Silt, dark brown, moist, stiff.		
5			B			Terrace/Bay Deposits: Sand, reddish brown to yellowish brown, moist, dense.		
10			R	8/22/28		Sand, reddish brown to yellowish brown, slightly moist, dense to very dense, micaceous, fine grained.	99	8
15			SPT	7/8/11		Sand and Clayey Sand, grayish brown and yellowish brown, moist, dense.		
20			R	8/9/16		Sandy Clay and Silty Clay, olive brown and brown, moist, stiff.	106	20
25			SPT	10/16/25		Sand and Clayey Sand, olive brown and yellowish brown, moist, dense, micaceous, fine to medium grained.		
30			R	6/9/10		Clay, bluish gray and olive gray, moist, stiff, plastic, fossil bivalve mollusk shell fragments.	89	32
35			SPT	5/5/6		Clay, bluish gray and olive gray, moist, stiff, plastic, frequent fossil bivalve mollusk shell fragments.		
40			R	7/10/13		Clay, bluish gray and olive gray, moist, stiff, plastic, frequent fossil bivalve mollusk shell fragments.	87	32

APPENDIX III

CONE PENETROMETER TESTS ASSIGNED **BY GINTER & ASSOCIATES, INC.**



GREGG DRILLING & TESTING, INC.
GEOTECHNICAL AND ENVIRONMENTAL INVESTIGATION SERVICES

August 23, 2011

Ginter & Associates
Attn: Brian Weatherby

Subject: CPT Site Investigation
Uptown Newport Village
Newport Beach, California
GREGG Project Number: 11-602SH

Dear Mr. Weatherby:

The following report presents the results of GREGG Drilling & Testing's Cone Penetration Test investigation for the above referenced site. The following testing services were performed:

1	Cone Penetration Tests	(CPTU)	<input checked="" type="checkbox"/>
2	Pore Pressure Dissipation Tests	(PPD)	<input checked="" type="checkbox"/>
3	Seismic Cone Penetration Tests	(SCPTU)	<input type="checkbox"/>
4	UVOST Laser Induced Fluorescence	(UVOST)	<input type="checkbox"/>
5	Groundwater Sampling	(GWS)	<input type="checkbox"/>
6	Soil Sampling	(SS)	<input type="checkbox"/>
7	Vapor Sampling	(VS)	<input type="checkbox"/>
8	Pressuremeter Testing	(PMT)	<input type="checkbox"/>
9	Vane Shear Testing	(VST)	<input type="checkbox"/>
10	Dilatometer Testing	(DMT)	<input type="checkbox"/>

A list of reference papers providing additional background on the specific tests conducted is provided in the bibliography following the text of the report. If you would like a copy of any of these publications or should you have any questions or comments regarding the contents of this report, please do not hesitate to contact our office at (562) 427-6899.

Sincerely,

Peter Robertson
Technical Director, Gregg Drilling & Testing, Inc.



GREGG DRILLING & TESTING, INC.
GEOTECHNICAL AND ENVIRONMENTAL INVESTIGATION SERVICES

Cone Penetration Test Sounding Summary

-Table 1-

CPT Sounding Identification	Date	Termination Depth (Feet)	Depth of Groundwater Samples (Feet)	Depth of Soil Samples (Feet)	Depth of Pore Pressure Dissipation Tests (Feet)
CPT-1	8/19/11	65	-	-	54.8
CPT-2	8/19/11	70	-	-	47.2
CPT-3	8/19/11	30	-	-	-
CPT-3A	8/22/11	27	-	-	27.4
CPT-4	8/19/11	65	-	-	38.4
CPT-5A	8/22/11	33	-	-	33.0
CPT-8	8/19/11	68	-	-	65.1



Bibliography

Lunne, T., Robertson, P.K. and Powell, J.J.M., "Cone Penetration Testing in Geotechnical Practice"
E & FN Spon. ISBN 0 419 23750, 1997

Roberston, P.K., "Soil Classification using the Cone Penetration Test", Canadian Geotechnical Journal, Vol. 27,
1990 pp. 151-158.

Mayne, P.W., "NHI (2002) Manual on Subsurface Investigations: Geotechnical Site Characterization", available
through www.ce.gatech.edu/~geosys/Faculty/Mayne/papers/index.html, Section 5.3, pp. 107-112.

Robertson, P.K., R.G. Campanella, D. Gillespie and A. Rice, "Seismic CPT to Measure In-Situ Shear Wave Velocity",
Journal of Geotechnical Engineering ASCE, Vol. 112, No. 8, 1986
pp. 791-803.

Robertson, P.K., Sully, J., Woeller, D.J., Lunne, T., Powell, J.J.M., and Gillespie, D.J., "Guidelines for Estimating
Consolidation Parameters in Soils from Piezocone Tests", Canadian Geotechnical Journal, Vol. 29, No. 4,
August 1992, pp. 539-550.

Robertson, P.K., T. Lunne and J.J.M. Powell, "Geo-Environmental Application of Penetration Testing", Geotechnical
Site Characterization, Robertson & Mayne (editors), 1998 Balkema, Rotterdam, ISBN 90 5410 939 4 pp 35-47.

Campanella, R.G. and I. Weemeees, "Development and Use of An Electrical Resistivity Cone for Groundwater
Contamination Studies", Canadian Geotechnical Journal, Vol. 27 No. 5, 1990 pp. 557-567.

DeGroot, D.J. and A.J. Lutenegeger, "Reliability of Soil Gas Sampling and Characterization Techniques", International
Site Characterization Conference - Atlanta, 1998.

Woeller, D.J., P.K. Robertson, T.J. Boyd and Dave Thomas, "Detection of Polyaromatic Hydrocarbon Contaminants
Using the UVIF-CPT", 53rd Canadian Geotechnical Conference Montreal, QC October pp. 733-739, 2000.

Zemo, D.A., T.A. Delfino, J.D. Gallinatti, V.A. Baker and L.R. Hilpert, "Field Comparison of Analytical Results from
Discrete-Depth Groundwater Samplers" BAT EnviroProbe and QED HydroPunch, Sixth national Outdoor Action
Conference, Las Vegas, Nevada Proceedings, 1992, pp 299-312.

Copies of ASTM Standards are available through www.astm.org




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 1

Date: 8/19/2011 07:27



Max. Depth: 65.125 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 1

Date: 8/19/2011 07:27



Max. Depth: 65.125 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Sounding: CPT 2

Engineer: B.WEATHERBY

Date: 8/19/2011 12:31



Max. Depth: 70.046 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 2

Date: 8/19/2011 12:31



Max. Depth: 70.046 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 3A

Date: 8/22/2011 10:10



Max. Depth: 27.395 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 3A

Date: 8/22/2011 10:10



Max. Depth: 27.395 (ft)
Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 3

Date: 8/19/2011 03:33



Max. Depth: 29.364 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 3

Date: 8/19/2011 03:33



Max. Depth: 29.364 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Sounding: CPT 4

Engineer: B.WEATHERBY

Date: 8/19/2011 01:36



Max. Depth: 65.453 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 4

Date: 8/19/2011 01:36



Max. Depth: 65.453 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Sounding: CPT 5A

Engineer: B.WEATHERBY

Date: 8/22/2011 07:26



Max. Depth: 32.972 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 5A

Date: 8/22/2011 07:26



Max. Depth: 32.972 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Engineer: B.WEATHERBY

Sounding: CPT 8

Date: 8/19/2011 10:29



Max. Depth: 68.077 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)




GINTER & ASSOC.

Site: UPTOWN NEWPORT

Sounding: CPT 8

Engineer: B.WEATHERBY

Date: 8/19/2011 10:29



Max. Depth: 68.077 (ft)

Avg. Interval: 0.328 (ft)

SBT: Soil Behavior Type (Robertson 1990)



Cone Penetration Test Data & Interpretation

The Cone Penetration Test (CPT) data collected from your site are presented in graphical form in the attached report. The plots include interpreted Soil Behavior Type (SBT) based on the charts described by Robertson (1990). Typical plots display SBT based on the non-normalized charts of Robertson et al (1986). For CPT soundings extending greater than 50 feet, we recommend the use of the normalized charts of Robertson (1990) which can be displayed as SBT_n, upon request. The report also includes spreadsheet output of computer calculations of basic interpretation in terms of SBT and SBT_n and various geotechnical parameters using current published correlations based on the comprehensive review by Lunne, Robertson and Powell (1997), as well as recent updates by Professor Robertson. The interpretations are presented only as a guide for geotechnical use and should be carefully reviewed. Gregg Drilling & Testing Inc. do not warranty the correctness or the applicability of any of the geotechnical parameters interpreted by the software and do not assume any liability for any use of the results in any design or review. The user should be fully aware of the techniques and limitations of any method used in the software.

Some interpretation methods require input of the groundwater level to calculate vertical effective stress. An estimate of the in-situ groundwater level has been made based on the field observations and/or CPT results, but should be verified by the user.

A summary of locations and depths is available in Table 1. Note that all penetration depths referenced in the data are with respect to the existing ground surface.

Note that it is not always possible to clearly identify a soil type based solely on q_t , f_s , and u_2 . In these situations, experience, judgment, and an assessment of the pore pressure dissipation data should be used to infer the correct soil behavior type.




Figure SBT_n




Cone Penetration Test Data & Interpretation

The Cone Penetration Test (CPT) data collected from your site are presented in graphical form in the attached report. The plots include interpreted Soil Behavior Type (SBT) based on the charts described by Robertson (1990). Typical plots display SBT based on the non-normalized charts of Robertson et al (1986). For CPT soundings extending greater than 50 feet, we recommend the use of the normalized charts of Robertson (1990) which can be displayed as SBTn, upon request. The report also includes spreadsheet output of computer calculations of basic interpretation in terms of SBT and SBTn and various geotechnical parameters using current published correlations based on the comprehensive review by Lunne, Robertson and Powell (1997), as well as recent updates by Professor Robertson. The interpretations are presented only as a guide for geotechnical use and should be carefully reviewed. Gregg Drilling & Testing Inc. do not warranty the correctness or the applicability of any of the geotechnical parameters interpreted by the software and do not assume any liability for any use of the results in any design or review. The user should be fully aware of the techniques and limitations of any method used in the software.

Some interpretation methods require input of the groundwater level to calculate vertical effective stress. An estimate of the in-situ groundwater level has been made based on field observations and/or CPT results, but should be verified by the user.

A summary of locations and depths is available in Table 1. Note that all penetration depths referenced in the data are with respect to the existing ground surface.

Note that it is not always possible to clearly identify a soil type based solely on q_t , f_s , and u_2 . In these situations, experience, judgment, and an assessment of the pore pressure dissipation data should be used to infer the correct soil behavior type.



(After Robertson, et al., 1986)

ZONE	SBT
1	Sensitive, fine grained
2	Organic materials
3	Clay
4	Silty clay to clay
5	Clayey silt to silty clay
6	Sandy silt to clayey silt
7	Silty sand to sandy silt
8	Sand to silty sand
9	Sand
10	Gravely sand to sand
11	Very stiff fine grained*
12	Sand to clayey sand*

*over consolidated or cemented

Figure SBT



Cone Penetration Test (CPT) Interpretation

Gregg has recently updated their CPT interpretation and plotting software (2007). The software takes the CPT data and performs basic interpretation in terms of soil behavior type (SBT) and various geotechnical parameters using current published empirical correlations based on the comprehensive review by Lunne, Robertson and Powell (1997). The interpretation is presented in tabular format using MS Excel. The interpretations are presented only as a guide for geotechnical use and should be carefully reviewed. Gregg does not warranty the correctness or the applicability of any of the geotechnical parameters interpreted by the software and does not assume any liability for any use of the results in any design or review. The user should be fully aware of the techniques and limitations of any method used in the software.

The following provides a summary of the methods used for the interpretation. Many of the empirical correlations to estimate geotechnical parameters have constants that have a range of values depending on soil type, geologic origin and other factors. The software uses 'default' values that have been selected to provide, in general, conservatively low estimates of the various geotechnical parameters.

Input:

- 1 Units for display (Imperial or metric) (atm. pressure, $p_a = 0.96$ tsf or 0.1 MPa)
- 2 Depth interval to average results, (ft or m). Data are collected at either 0.02 or 0.05m and can be averaged every 1, 3 or 5 intervals.
- 3 Elevation of ground surface (ft or m)
- 4 Depth to water table, z_w (ft or m) – input required
- 5 Net area ratio for cone, a (default to 0.80)
- 6 Relative Density constant, C_{Dr} (default to 350)
- 7 Young's modulus number for sands, α (default to 5)
- 8 Small strain shear modulus number
 - a. for sands, S_G (default to 180 for SBT_n 5, 6, 7)
 - b. for clays, C_G (default to 50 for SBT_n 1, 2, 3 & 4)
- 9 Undrained shear strength cone factor for clays, N_{kt} (default to 15)
- 10 Over Consolidation ratio number, k_{ocr} (default to 0.3)
- 11 Unit weight of water, (default to $\gamma_w = 62.4$ lb/ft³ or 9.81 kN/m³)

Column

- 1 Depth, z , (m) – CPT data is collected in meters
- 2 Depth (ft)
- 3 Cone resistance, q_c (tsf or MPa)
- 4 Sleeve friction, f_s (tsf or MPa)
- 5 Penetration pore pressure, u (psi or MPa), measured behind the cone (i.e. u_2)
- 6 Other – any additional data, if collected, e.g. electrical resistivity or UVIF
- 7 Total cone resistance, q_t (tsf or MPa) $q_t = q_c + u(1-a)$

8	Friction Ratio, R_f (%)	$R_f = (f_s/q_t) \times 100\%$
9	Soil Behavior Type (non-normalized), SBT	see note
10	Unit weight, γ (pcf or kN/m ³)	based on SBT, see note
11	Total overburden stress, σ_v (tsf)	$\sigma_{vo} = \gamma z$
12	Insitu pore pressure, u_o (tsf)	$u_o = \gamma_w (z - z_w)$
13	Effective overburden stress, σ'_{vo} (tsf)	$\sigma'_{vo} = \sigma_{vo} - u_o$
14	Normalized cone resistance, Q_{tl}	$Q_{tl} = (q_t - \sigma_{vo}) / \sigma'_{vo}$
15	Normalized friction ratio, F_r (%)	$F_r = f_s / (q_t - \sigma_{vo}) \times 100\%$
16	Normalized Pore Pressure ratio, B_q	$B_q = u - u_o / (q_t - \sigma_{vo})$
17	Soil Behavior Type (normalized), SBT_n	see note
18	SBT_n Index, I_c	see note
19	Normalized Cone resistance, Q_{tn} (n varies with I_c)	see note
20	Estimated permeability, k_{SBT} (cm/sec or ft/sec)	see note
21	Equivalent SPT N_{60} , blows/ft	see note
22	Equivalent SPT $(N_1)_{60}$ blows/ft	see note
23	Estimated Relative Density, D_r , (%)	see note
24	Estimated Friction Angle, ϕ' , (degrees)	see note
25	Estimated Young's modulus, E_s (tsf)	see note
26	Estimated small strain Shear modulus, G_o (tsf)	see note
27	Estimated Undrained shear strength, s_u (tsf)	see note
28	Estimated Undrained strength ratio	s_u/σ'_v
29	Estimated Over Consolidation ratio, OCR	see note

Notes:

- 1 Soil Behavior Type (non-normalized), SBT listed below Lunne et al. (1997)
- 2 Unit weight, γ either constant at 119 pcf or based on Non-normalized SBT (Lunne et al., 1997 and table below)
- 3 Soil Behavior Type (Normalized), SBT_n Lunne et al. (1997)
- 4 SBT_n Index, I_c $I_c = ((3.47 - \log Q_{tl})^2 + (\log F_r + 1.22)^2)^{0.5}$
- 5 Normalized Cone resistance, Q_{tn} (n varies with I_c)

$Q_{tn} = ((q_t - \sigma_{vo})/p_a) (p_a/(\sigma'_{vo})^n$ and recalculate I_c , then iterate:

When $I_c < 1.64$, $n = 0.5$ (clean sand)
 When $I_c > 3.30$, $n = 1.0$ (clays)
 When $1.64 < I_c < 3.30$, $n = (I_c - 1.64)0.3 + 0.5$
 Iterate until the change in n , $\Delta n < 0.01$

- 6 Estimated permeability, k_{SBT} (based on Normalized SBT_n)
(Lunne et al., 1997 and table below)
- 7 Equivalent SPT N_{60} , blows/ft Lunne et al. (1997)
- $$\frac{(q_t/p_a)}{N_{60}} = 8.5 \left(1 - \frac{I_c}{4.6} \right)$$
- 8 Equivalent SPT $(N_1)_{60}$ blows/ft $(N_1)_{60} = N_{60} C_N$
where $C_N = (p_a/\sigma'_{vo})^{0.5}$
- 9 Relative Density, D_r , (%) $D_r^2 = Q_{tn} / C_{Dr}$
Only SBT_n 5, 6, 7 & 8 Show 'N/A' in zones 1, 2, 3, 4 & 9
- 10 Friction Angle, ϕ' , (degrees) $\tan \phi' = \frac{1}{2.68} \left[\log \left(\frac{q_c}{\sigma'_{vo}} \right) + 0.29 \right]$
Only SBT_n 5, 6, 7 & 8 Show 'N/A' in zones 1, 2, 3, 4 & 9
- 11 Young's modulus, E_s $E_s = \alpha q_t$
Only SBT_n 5, 6, 7 & 8 Show 'N/A' in zones 1, 2, 3, 4 & 9
- 12 Small strain shear modulus, G_o
a. $G_o = S_G (q_t \sigma'_{vo} p_a)^{1/3}$ For SBT_n 5, 6, 7
b. $G_o = C_G q_t$ For SBT_n 1, 2, 3 & 4
Show 'N/A' in zones 8 & 9
- 13 Undrained shear strength, s_u $s_u = (q_t - \sigma_{vo}) / N_{kt}$
Only SBT_n 1, 2, 3, 4 & 9 Show 'N/A' in zones 5, 6, 7 & 8
- 14 Over Consolidation ratio, OCR $\text{OCR} = k_{ocr} Q_{t1}$
Only SBT_n 1, 2, 3, 4 & 9 Show 'N/A' in zones 5, 6, 7 & 8

SBT Zones

The following updated and simplified SBT descriptions have been used in the software:

- 1 sensitive fine grained
- 2 organic soil
- 3 clay
- 4 clay & silty clay
- 5 clay & silty clay
- 6 sandy silt & clayey silt
- 7 silty sand & sandy silt
- 8 sand & silty sand
- 9 sand
- 10 sand

SBT_n Zones

- 1 sensitive fine grained
- 2 organic soil
- 3 clay
- 4 clay & silty clay
- 5 silty sand & sandy silt
- 6 sand & silty sand
- 7 sand

11	very dense/stiff soil*	8	very dense/stiff soil*
12	very dense/stiff soil*	9	very dense/stiff soil*

*heavily overconsolidated and/or cemented

Track when soils fall with zones of same description and print that description (i.e. if soils fall only within SBT zones 4 & 5, print 'clays & silty clays')

Estimated Permeability (see Lunne et al., 1997)

SBT _n	Permeability (ft/sec)	(m/sec)
1	3×10^{-8}	1×10^{-8}
2	3×10^{-7}	1×10^{-7}
3	1×10^{-9}	3×10^{-10}
4	3×10^{-8}	1×10^{-8}
5	3×10^{-6}	1×10^{-6}
6	3×10^{-4}	1×10^{-4}
7	3×10^{-2}	1×10^{-2}
8	3×10^{-6}	1×10^{-6}
9	1×10^{-8}	3×10^{-9}

Estimated Unit Weight (see Lunne et al., 1997)

SBT	Approximate Unit Weight (lb/ft ³)	(kN/m ³)
1	111.4	17.5
2	79.6	12.5
3	111.4	17.5
4	114.6	18.0
5	114.6	18.0
6	114.6	18.0
7	117.8	18.5
8	120.9	19.0
9	124.1	19.5
10	127.3	20.0
11	130.5	20.5
12	120.9	19.0



Pore Pressure Dissipation Tests (PPDT)

Pore Pressure Dissipation Tests (PPDT's) conducted at various intervals measured hydrostatic water pressures and determined the approximate depth of the ground water table. A PPDT is conducted when the cone is halted at specific intervals determined by the field representative. The variation of the penetration pore pressure (u) with time is measured behind the tip of the cone and recorded by a computer system.

Pore pressure dissipation data can be interpreted to provide estimates of:

- Equilibrium piezometric pressure
- Phreatic Surface
- In situ horizontal coefficient of consolidation (c_h)
- In situ horizontal coefficient of permeability (k_h)

In order to correctly interpret the equilibrium piezometric pressure and/or the phreatic surface, the pore pressure must be monitored until such time as there is no variation in pore pressure with time, *Figure PPDT*. This time is commonly referred to as t_{100} , the point at which 100% of the excess pore pressure has dissipated.

A complete reference on pore pressure dissipation tests is presented by Robertson et al. 1992.

A summary of the pore pressure dissipation tests is summarized in Table 1.




Figure PPDT

DAKOTA TECHNOLOGIES UVOST LOG REFERENCE

2008-12-12

Main Plot :

Signal (total fluorescence) versus depth where signal is relative to the Reference Emitter (RE). The total area of the waveform is divided by the total area of the Reference Emitter yielding the %RE. This %RE scales with the NAPL fluorescence. The fill color is based on relative contribution of each channel's area to the total waveform area (see callout waveform). The channel-to-color relationship and corresponding wavelengths are given in the upper right corner of the main plot.

Callouts :

Waveforms from selected depths or depth ranges showing the multi-wavelength waveform for that depth.

The four peaks are due to fluorescence at four wavelengths and referred to as "channels". Each channel is assigned a color.

Various NAPLs will have a unique waveform "fingerprint" due to the relative amplitude of the four channels and/or broadening of one or more channels.

Basic waveform statistics and any operator notes are given below the callout.

Conductivity Plot :


The Electrical Conductivity (EC) of the soil can be logged simultaneously with the UVOST data. EC often provides insight into the stratigraphy. Note the drop in EC from 10 - 13 ft, indicating a shift from consolidated to unconsolidated stratigraphy. This correlates with the observed NAPL distribution.

Rate Plot :

The rate of probe advancement. ~ 0.8in (2cm) per second is preferred.

A noticeable decrease in the rate of advancement may be indicative of difficult probing conditions (gravel, angular sands, etc.) such as that seen here at ~5 ft.

Notice that this log was terminated arbitrarily, not due to "refusal", which would have been indicated by a sudden rate drop at final depth.



Note A :

Time is along the x axis. No scale is given, but it is a consistent 320ns wide.

The y axis is in mV and directly corresponds to the amount of light striking the photodetector.


Note B :

These two waveforms are clearly different. The first is weathered diesel from the log itself while the second is the Reference Emitter (a blend of NAPLs) always taken before each log for calibration.

Note C :

Callouts can be a single depth (see 3rd callout) or a range (see 4th callout). The range is noted on the depth axis by a bold line. When the callout is a range, the average and standard deviation in %RE is given below the callout.


Waveform Signal Calculation



Data Files

*.lif.raw.bin	Raw data file. Header is ASCII format and contains information stored when the file was initially written (e.g. date, total depth, max signal, gps, etc., and any information entered by the operator). All raw waveforms are appended to the bottom of the file in a binary format.
*.lif.plt	Stores the plot scheme history (e.g. callout depths) for associated Raw file. Transfer along with the Raw file in order to recall previous plots.
*.lif.jpg	A jpg image of the OST log including the main signal vs. depth plot, callouts, information, etc.
*.lif.dat.txt	Data export of a single Raw file. ASCII tab delimited format. No string header is provided for the columns (to make importing into other programs easier). Each row is a unique depth reading. The columns are: Depth, Total Signal (%RE), Ch1%, Ch2%, Ch3%, Ch4%, Rate, Conductivity Depth, Conductivity Signal, Hammer Rate. Summing channels 1 to 4 yields the Total Signal.
*.lif.sum.txt	A summary file for a number of Raw files. ASCII tab delimited format. The file contains a string header. The summary includes one row for each Raw file and contains information for each file including: the file name, gps coordinates, max depth, max signal, and depth at which the max signal occurred.
*.lif.log.txt	An activity log generated automatically located in the OST application directory in the 'log' subfolder. Each OST unit the computer operates will generate a separate log file per month. A log file contains much of the header information contained within each separate Raw file, including: date, total depth, max signal, etc.

Common Waveforms (highly dependent on soil, weathering, etc.)






Laser Induced Fluorescence (UVOST)

Gregg Drilling conducts Laser Induced Fluorescence (LIF) Cone Penetration Tests using a UVOST module that is located behind the standard piezocone, *Figure UVOST*. The laser induced fluorescence cone works on the principle that polycyclic aromatic hydrocarbons (PAH's), mixed with soil and/or groundwater, fluoresce when irradiated by ultra violet light. Therefore, by measuring the intensity of fluorescence, the lateral and vertical extent of hydrocarbon contamination in the ground can be determined.

The UVOST module uses principles of fluorescence spectrometry by irradiating the soil with ultra violet light produced by a laser and transmitted to the cone through fiber optic cables. The light is then passes through a small window in the side of the cone into the soil. Any hydrocarbon molecules present in the soil absorb the light energy during radiation and immediately re-emit the light at a longer wavelength. This re-emission is termed fluorescence. The UVOST system also measures the emission decay with time at four different wavelengths (350nm, 400nm, 450nm, and 500nm). This allows the software to determine a product "signature" at each data point. This process allows determination of the type of contaminant as shown in *Figure Concept*.



*Figure UVOST: UVOST system
deployed with the CPT*

In general, the typical detection limit for the UVOST system is <100 ppm and it will operate effectively above and below the saturated zone. With the capability to push up to 600 feet per day, laser induced fluorescence offers a fast and efficient means for delineating PAH contaminant plumes. Color coded logs offer qualitative information in a quick glance and can be produced in the field for real-time decision making. Coupled with the data provided by the CPT, a complete site assessment can be completed with no samples or cuttings, saving laboratory costs as well as site and environmental impact.





Figure Concept (figure provided by
Dakota Technologies)

Hydrocarbons detected with UVOST	Hydrocarbons rarely detected using UVOST
Gasoline	Extremely weathered gasoline
Diesel	Coal tar
Jet (Kerosene)	Creosote
Motor Oil	Bunker Oil
Cutting fluids	Polychlorinated bi-phenols (PCB's)
Hydraulic fluids	Chlorinated solvent DNAPL
Crude Oil	Dissolved phase (aqueous) PAH's

Potential False Positives (fluorescence observed)	Potential False Negatives (do not fluoresce)
Sea-shells (weak-medium)	Extremely weathered fuels (especially gasoline)
Paper (medium-strong depending on color)	Aviation gasoline (weak)
Peat/meadow mat (weak)	Coal tars (most)
Calcite/calcareous sands (weak)	Creosotes (most)
Tree roots (weak-medium)	"Dry" PAHs such as aqueous phase, lamp black, purifier chips
Sewer lines (medium-strong)	Most chlorinated solvents
	Benzene, toluene, xylenes (relatively pure)



APPENDIX IV

LABORATORY TESTING

ASSIGNED BY GINTER & ASSOCIATES,
INC.

Engineering Geology and Geotechnical Engineering

9428 Eton Avenue, Unit M, Chatsworth, California 91311
Tel: (818) 341-1899 Fax: (818) 341-1897 Email: cygeotech@sbcglobal.net

September 29, 2011

P. N. CYG-11-6216

LABORATORY TESTING SERVICES

As requested by Mr. Vela Ganeshwara of Gantec Engineering, Inc. (GEI), C. Y. Geotech (CYG), Inc. has performed the laboratory tests as listed in Table 1 for GEI project PT 116-02, at Lots 1 & 2, Tract 7953, Newport Beach, California. The testing procedures of ASTM (American Society for Testing and Materials) Standards were followed in the laboratory tests. The CYG laboratory is certified by the City of Los Angeles Department of Building and Safety.

Client Name: Gantec Engineering, Inc.
Project Name: GEI/Upper Newport Village
GEI Project No: PT 116-02
Project Address: Lots 1 & 2, Tract 7953, Newport Beach, California

The type and quantity of laboratory tests are listed in Table 1. The results of laboratory tests are summarized in Table 2, Plates DS-1 to DS-11, Plates CS-1 to CS-21, Plates CM-1 to CM-3, and Plates GS-1 to GS-15. If you have any questions regarding the laboratory testing, please do not hesitate to call us.

Very truly yours,
C. Y. Geotech, Inc.



John T. Tsao
RCE 46886



TEST PROCEDURES

Moisture-Density Test

Onsite soils were classified in the field and laboratory in accordance with the USCS (Unified Soil Classification System) classification system. Moisture contents are determined in general accordance with ASTM Test Designation D2216-10. Unit weights were determined in general accordance with ASTM Test Designation D2937-10. The results of moisture-density tests are listed in Table 2.

Direct Shear Test

Eleven direct shear tests were performed on selected ring samples to determine the shear strength parameters of onsite soil. The direct shear test was performed in accordance with ASTM Standard D-3080-04 by using a strain control type direct shear machine and under an artificially saturated condition. The samples were submerged into water for one or two days to saturate the samples prior to testing. The samples were tested under the following procedures: 1) the sample is placed in the shear box and then a selected normal stress is applied to the specimen, 2) the sample is compressed by the normal stress until an equilibrium state is reached, 3) the sample is sheared under a constant rate of shear displacement of 0.004 inches per minute, 4) the peak value of shear strength during shearing was recorded as the peak shear strength, 5) back-shear the sample to the original position and then reshear the sample to record the peak value as the ultimate shear strength. Three samples were tested with different normal loads following the abovementioned testing procedures. The results were plotted on a normal-stress vs. shearing strength diagram to determine the shear strength parameters: cohesion and angle of internal friction. The results of direct shear tests are presented in Plates DS-1 to DS-11.

Consolidation Test

Twenty one consolidation tests were performed on selected ring samples to determine the compressibility and hydroconsolidation potential of onsite soil. The consolidation test was performed in general accordance with ASTM Standard D-2435-11. The ring sample was contained in a 2.4-inch-diameter and 1.0-inch-high sampling ring. This test was performed primarily on materials which would be most susceptible to consolidation under anticipated foundation loading. The sample was tested under the following procedures: 1) the sample is placed in a loading frame under a seating pressure of 200 psf, 2) apply vertical loads to the sample in several geometric increments and record the resulting deformations at selected time intervals, 3) adds water to the test cell and records the vertical consolidation when the applied stress reaches a simulated foundation pressure (often 2000 psf) and the sample has consolidated under that pressure, 4) repeat step 2 until a loading pressure of 4000 psf or 8000 psf and record the equilibrium consolidation, 5) unload the sample to an applied stress of 1000 psf and record the rebound of the sample. The results of these tests are presented in terms of percent volume change versus applied vertical stress. The results of consolidation tests are presented in Plates CS-1 to CS-21.

Compaction Test

Three compaction tests were performed on bulk soil samples to determine the maximum dry density and optimum moisture content of onsite soil. The compaction tests were performed in general accordance with ASTM Test Designation D1557-09. The procedure A of compaction test was used in the subject project. The following materials and criteria were followed in test: 1) soil sample passing No.4 sieve was used in test, 2) a 4-inch mode was used in test, 3) a 10-pound hammer with a free fall distance of 18 inches was used in

test, 4) five layers of soil sample were compacted in the 4-inch mode, 5) the blow for each layer of soil sample is 25. A minimum of three soil samples were performed to determine the corresponding dry density and moisture content. The results of the tests are presented in terms of moisture content verses dry density to generate a compaction curve. The maximum dry density and optimum moisture content can be determined from the compaction curve. The results of the compaction tests are presented in Plates CM-1 to CM-3.

Expansion Index Test

Three expansion index tests were performed on bulk soil samples to determine the expansion potential of the soil. The expansion index tests were performed in general accordance with expansion test procedures in ASTM D4829-08a to provide an assessment of the potential for expansion or heave that could be detrimental to foundation or slab performance. The following procedures were followed in the test: 1) compact the soil sample at degree of saturation between 48 and 52 percent in a 4.01-inch-diameter, 1.0-inch-high ring, 2) apply a vertical seating pressure of 144 psf to the sample, 3) add water to the test cell and saturate the soil sample, 4) record the soil expansion until the expansion of soil sample stops. The volume of swell is converted to an expansion index. Laboratory expansion index tests indicated an expansion indexes of 74, 114 and 105 for the tested native soil. A soil with an expansion index in the range of 51 to 90 is classified as medium expansive soil. A soil with an expansion index in the range of 91 to 130 is classified as high expansive soil.

Grain Size Distribution Test

Fifteen mechanical sieve tests and nine hydrometer tests were performed on selected soil samples to determine their grain size distributions in accordance with ASTM Standard D-422-63 (2007). Mechanical sieve analyses establish gradation for the coarse-grained particles (i.e., sand and gravel). Hydrometer tests establish gradation for the fine-grained particles (i.e., silt and clay). The results of gradation analyses are presented in Plates GS-1 through GS-15.

Table 1. Type and Quantity of Laboratory Test

Laboratory Test	Quantity	ASTM Standard
Density and Moisture Content	111	D-2216
Direct Shear Test	11	D-3080
Consolidation Test	21	D-2435
Compaction Test	3	D-1557
Expansion Index Test	3	D-4829
Grain Size Distribution Test	15	D-422

Table 2. Results of the Dry Density-Moisture Content Test

Location	Depth ft	Soils Description	Dry Density, pcf	Moisture Content, %
GB-1	5	Tan clayey sandy silt	99	23

GB-1	7.5	Light gray silty sand	101	11
GB-1	10	Grayish brown silty sand	110	12
GB-1	20	Yellowish tan sand	106	8
GB-1	30	Olive gray silty clay	86	36
GB-1	40	Dark gray clay	90	31
GB-1	50	Dark gray clayey sand	107	19
GB-1	60	Dark bluish gray clayey sand	113	10
GB-1	70	Reddish brown sand	99	7
GB-2	5	Brown clayey sandy silt	105	18
GB-2	7.5	Olive brown clayey sandy silt	107	19
GB-2	10	Reddish brown silty sand	99	21
GB-2	25	Olive gray sandy clay	108	19
GB-2	35	Olive brown silty clay	92	31
GB-2	45	Dark bluish gray clay	102	22
GB-3	5	Reddish brown clayey silty sand	109	10
GB-3	7.5	Grayish brown sand	99	3
GB-3	10	Light brown silty sandy clay	103	20
GB-3	20	Yellowish brown silty sand	105	14
GB-3	30	Yellowish brown sand	103	20
GB-3	40	Bluish gray silty clay	94	28
GB-3	50	Dark bluish gray silty clayey sand	101	23
GB-3	60	Dark gray silty clay	105	22
GB-3	70	Light gray sand	109	11
GB-4	5	Yellowish brown silty clay	97	22
GB-4	7.5	Olive brown silty clay	90	19
GB-4	10	Olive gray clayey silt	109	15
GB-4	20	Light grayish tan sand	106	2

GB-4	30	Olive gray silty clay	91	32
GB-4	40	Dark bluish gray silty clay	87	34
GB-4	50	Gray silty sand	110	17
GB-5	5	Brown clayey silty sand	94	22
GB-5	10	Grayish brown sand	103	15
GB-5	20	Reddish brown sand	101	7
GB-5	30	Olive brown silty clay	89	33
GB-5	40	Olive brown silty clay	83	42
GB-5	50	Olive brown clayey sand	102	19
GB-6	5	Brown clayey sandy silt	104	15
GB-6	7.5	Brown sand	101	2
GB-6	10	Brown silty sand	96	5
GB-6	20	Brown silty clay	102	19
GB-6	30	Yellowish tan sand	99	25
GB-6	50	Reddish brown sand	92	6
GB-7	7.5	Reddish brown clayey silty sand	120	8
GB-7	10	Reddish brown silty clay	98	18
GB-7	20	Greenish gray clay	96	23
GB-7	30	Reddish brown silty sand	99	6
GB-7	40	Reddish brown clayey silty sand	104	21
GB-7	50	Dark bluish gray clay	106	21
GB-7	60	Dark gray clay	91	29
GB-7	70	Olive gray silty clay	75	41
GB-8	5	Dark brown sandy silty clay	102	22
GB-8	7.5	Dark brown clayey silty sand	113	16
GB-8	10	Reddish brown clayey silty sand	113	13
GB-8	20	Reddish brown sandy clayey silt	105	15


GB-8	40	Olive gray silty clay	92	30
GB-8	50	Gray sand	113	16
GB-9	5	Grayish brown silty clayey sand	104	17
GB-9	7.5	Olive brown silty clay	107	19
GB-9	10	Dark brown silty clayey sand	109	11
GB-9	20	Light gray silty clay	96	20
GB-9	30	Light gray sand	116	11
GB-9	40	Dark gray clay	86	37
GB-9	50	Dark gray clayey sand	110	20
GB-9	60	Light gray silty sandy clay	104	22
GB-9	70	Light gray sand	100	22
GB-10	5	Reddish brown clayey sand	93	6
GB-10	7.5	Brown sand	104	2
GB-10	10	Tan sand	108	1
GB-10	20	Reddish brown clayey sand	105	13
GB-10	30	Reddish brown clayey sand	106	19
GB-10	40	Olive brown clayey sand	107	20
GB-10	50	Greenish gray silty clay	101	23
GB-11	10	Reddish brown clayey sand	109	14
GB-11	20	Reddish brown sand	118	9
GB-11	30	Dark gray clayey sand	80	20
GB-11	40	Medium gray sand	120	13
GB-11	50	Dark gray sandy clay	104	21
GB-11	60	Yellowish tan sand	107	3
GB-11	70	Yellowish tan sand	104	2
GB-12	10	Reddish brown silty clay	104	18
GB-12	20	Reddish brown silty sand	92	13

GB-12	40	Bluish gray clay	83	37
GB-12	50	Dark gray silty clay	86	37
GB-12	60	Bluish gray clayey sand	106	22
GB-12	70	Light gray clayey sand	129	2
GB-13	10	Yellow tan sand	91	12
GB-13	20	Olive brown silty clay	103	21
GB-13	30	Bluish gray silty clay	85	36
GB-13	40	Dark gray silty clay	85	35
GB-13	50	Dark gray clayey sand	116	13
GB-14	5	Reddish brown gravelly sand	116	5
GB-14	7.5	Olive brown clayey silty sand	97	23
GB-14	10	Olive brown clayey silty sand	100	23
GB-14	20	Light grayish tan sand	94	11
GB-14	30	Greenish gray silty clay	88	33
GB-14	40	Dark gray clay	84	36
GB-14	50	Light grayish tan sand	101	7
GB-14	60	Light gray sand	105	15
GB-15	5	Reddish brown clayey silty sand	105	19
GB-15	7.5	Yellowish brown silty sand	111	10
GB-15	10	Brown clayey silty sand	100	24
GB-15	15	Olive brown clayey silt	91	28
GB-15	25	Brownish yellow sand	106	12
GB-15	35	Bluish gray clay	84	34
GB-15	45	Bluish gray sandy clay	102	24
GB-16	10	Yellowish brown sand	99	8
GB-16	20	Olive brown sandy clay	106	20
GB-16	30	Olive brown clay	89	32

GB-16	40	Olive brown clay	87	32
GB-16	50	Olive brown clayey sand	119	9

Table 3. Result of Compaction Tests and Expansion Index Tests

Location	Depth ft	Soil Description	Maximum Dry Density, pcf	Optimum Moisture Content, %	Expansion Index
GB-2	3	Reddish brown sandy silty clay	122	10	74
GB-4	4.5	Brown silty clay	114.5	13.5	114
GB-5	3	Brown silty clay	114.5	13	105



- Peak - At Saturation Moisture Content
- Ultimate - At Saturation Moisture Content

C = 180 psf $\phi = 30.5^\circ$
 C = 120 psf $\phi = 29^\circ$

Field Dry Density = 101 pcf
 Field Moisture Content = 11 %
 Saturation Moisture Content = 24 %

Boring: GB-1
 Depth : 7.5 feet
 Description : Light gray silty sand

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N.No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content
- Ultimate - At Saturation Moisture Content

$C = 170 \text{ psf}$ $\phi = 30.5^\circ$
 $C = 100 \text{ psf}$ $\phi = 30^\circ$

Field Dry Density = 99 pcf
 Field Moisture Content = 21 %
 Saturation Moisture Content = 25 %

Boring: GB-2
 Depth : 10 feet
 Description : Reddish brown silty sand

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content $C = 80$ psf $\phi = 32^\circ$
- Ultimate - At Saturation Moisture Content $C = 70$ psf $\phi = 31.5^\circ$

Field Dry Density = 99 pcf
 Field Moisture Content = 3 %
 Saturation Moisture Content = 25 %

Boring: GB-3
 Depth : 7.5 feet
 Description : Grayish brown sand


C. Y. GEOTECH, INC.

Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011 P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content $C = 120 \text{ psf}$ $\phi = 32^\circ$
- Ultimate - At Saturation Moisture Content $C = 90 \text{ psf}$ $\phi = 29.5^\circ$

Field Dry Density = 103 pcf
 Field Moisture Content = 15 %
 Saturation Moisture Content = 23 %

Boring: GB-5
 Depth : 10 feet
 Description : Grayish brown sand

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content
- Ultimate - At Saturation Moisture Content

C = 150 psf $\phi = 26^\circ$
 C = 150 psf $\phi = 23^\circ$

Field Dry Density = 102 pcf
 Field Moisture Content = 19 %
 Saturation Moisture Content = 24 %

Boring: GB-6
 Depth : 20 feet
 Description : Brown silty clay

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content $C = 330$ psf $\phi = 13^\circ$
- Ultimate - At Saturation Moisture Content $C = 330$ psf $\phi = 11^\circ$

Field Dry Density = 96 pcf
 Field Moisture Content = 23 %
 Saturation Moisture Content = 27 %

Boring: GB-7
 Depth : 20 feet
 Description : Greenish gray clay

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content
- Ultimate - At Saturation Moisture Content

$C = 500$ psf $\phi = 11.5^\circ$
 $C = 460$ psf $\phi = 11^\circ$

Field Dry Density = 102 pcf
 Field Moisture Content = 22 %
 Saturation Moisture Content = 24 %

Boring: GB-8
 Depth : 5 feet
 Description : Dark brown sandy silty clay

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content
- Ultimate - At Saturation Moisture Content

C = 570 psf $\phi = 27.5^\circ$
 C = 510 psf $\phi = 24.5^\circ$

Field Dry Density = 107 pcf
 Field Moisture Content = 19 %
 Saturation Moisture Content = 21 %

Boring: GB-9
 Depth : 7.5 feet
 Description : Olive brown silty clay

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content
- Ultimate - At Saturation Moisture Content

C = 430 psf $\phi = 16^\circ$
 C = 290 psf $\phi = 15^\circ$

Field Dry Density = 104 pcf
 Field Moisture Content = 18 %
 Saturation Moisture Content = 23 %

Boring: GB-12
 Depth : 10 feet
 Description : Reddish brown silty clay

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content
- Ultimate - At Saturation Moisture Content

$C = 180 \text{ psf}$ $\phi = 28^\circ$
 $C = 70 \text{ psf}$ $\phi = 28^\circ$

Field Dry Density = 100 pcf
 Field Moisture Content = 23 %
 Saturation Moisture Content = 25 %

Boring: GB-14
 Depth : 10 feet
 Description : Olive brown clayey silty sand

C. Y. GEOTECH, INC.


Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Shear Diagram



- Peak - At Saturation Moisture Content
- Ultimate - At Saturation Moisture Content

$C = 180 \text{ psf}$ $\phi = 33.5^\circ$
 $C = 110 \text{ psf}$ $\phi = 28^\circ$

Field Dry Density = 111 pcf
 Field Moisture Content = 10 %
 Saturation Moisture Content = 19 %

Boring: GB-15
 Depth : 7.5 feet
 Description : Yellowish brown silty sand

C. Y. GEOTECH, INC.

Geotechnical Engineering
 and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Shear Diagram

C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


P.N. No: CYG-11-6216

Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before	Water Content (%) After	Height (inches)	Diameter (inches)
GB-1	5	23	25	1.0	2.4

Classification : Tan clayey sandy silt
Hydroconsolidation = 0.2 %



C. Y. GEOTECH, INC.
Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


P.N. No: CYG-11-6216

Date : 10-2011

Consolidation Test

Boring	GB-2	7.5	19	21	1.0	2.4
Depth (feet)			Water Content (%)	Before	Height (inches)	Diameter (inches)

Classification : Olive brown clayey sandy silt
Swelling = 1.8 %



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology


GEI / Upper Newport Village

P.N. No: CYG-11-6216


Date : 10-2011

Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter (inches)
GB-3	5	10	20	2.4
Classification : Reddish brown clayey silty sand				
Swelling = 1.3 %				

Consolidation Test



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology		GEI / Upper Newport Village				Date : 10-2011		P.N. No: CYG-11-6216									
Consolidation Test		Boring	GB-3	Depth (feet)	10	Water Content (%)	20	Before	23	After	1.0	Height (inches)	2.4	Classification : Light brown silty sandy clay		Swelling = 0.2 %	



C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011


P.N. No: CYG-11-6216

Consolidation Test

Boring	Depth (feet)	Water Content (%)	Before	After	Height (inches)	Diameter (inches)
GB-4	20	2	21	1.0	2.4	

Classification : Light grayish tan sand

Hydroconsolidation = 0.4 %



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology


GBI / Upper Newport Village

P.N. No: CYG-11-6216

Date : 10-2011

Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter (inches)
GB-5	5	22	29	1.0
Classification : Brown clayey silty sand				
Hydroconsolidation = 0.3 %				

Consolidation Test



C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology


GEI / Upper Newport Village

P.N. No: CYG-11-6216

Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter (inches)
GB-6	5	15	23	1.0
Classification : Brown clayey sandy silt				
Swelling = 0.2 %				



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


P.N. No: CYG-11-6216

Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before After	Height (inches)	Diameter (inches)
GB-6	10	27	1.0	2.4

Classification : Brown silty sand
Hydroconsolidation = 0.7 %



C. Y. GEOTECH, INC.


Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No: CYG-11-6216

Consolidation Test					
Boring	Depth (feet)	Water Content (%) Before	After	Height (inches)	Diameter (inches)
GB-7	10	18	26	1.0	2.4
Classification : Reddish brown silty clay					
Hydroconsolidation = 1.1 %					



C. Y. GEOTECH, INC.
Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


Date : 10-2011

P.N. No: CYG-11-6216

Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter (inches)
GB-9	5	17	23	1.0
				2.4

Classification : Grayish brown silty clayey sand
Swelling = 0.9 %

Consolidation Test



C. Y. GEOTECH, INC.
Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

P.N. No: CYG-11-6216


Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before	After	Height (inches)	Diameter (inches)
GB-9	20	20	27	1.0	2.4

Classification : Light gray silty clay

Hydroconsolidation = 1.5 %



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


P.N. No: CYG-11-6216

Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter (inches)
GB-10	5	29	1.0	2.4

Classification : Reddish brown clayey sand
Hydroconsolidation = 9.1 %



C. Y. GEOTECH, INC.
Geotechnical Engineering and Engineering Geology


GEI / Upper Newport Village

P.N. No: CYG-11-6216

Date : 10-2011

Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter
GB-10	10	1	1.0	2.4
Classification : Tan sand				
Hydroconsolidation = 0.9 %				

Consolidation Test



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology


GEI / Upper Newport Village

P.N. No: CYG-11-6216

Date : 10-2011

Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter (inches)
GB-11	10	14	20	2.4
Classification : Reddish brown clayey sand				
Swelling = 0.5 %				

Consolidation Test



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


P.N. No: CYG-11-6216

Date : 10-2011

Boring	Depth (feet)	Water Content (%) Before	After	Height (inches)	Diameter (inches)
GB-12	20	13	30	1.0	2.4

Classification : Reddish brown silty sand
 Hydroconsolidation = 1.6 %

Consolidation Test



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


P.N. No: CYG-11-6216

Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before	Height (inches) After	Diameter (inches)
GB-13	10	12	31	1.0
				2.4

Classification : Yellow tan sand
Hydroconsolidation = 0.3 %



C. Y. GEOTECH, INC.
 Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


P.N. No: CYG-11-6216

Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter (inches)
GB-13	20	21	1.0	2.4

Classification : Olive brown silty clay
 Swelling = 3.3 %



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village


P.N. No: CYG-11-6216

Date : 10-2011

Classification : Olive brown clayey silty sand
Swelling = 0.1 %

Boring	Depth (feet)	Water Content (%) Before	After	Height (inches)	Diameter (inches)
GB-14	7.5	23	27	1.0	2.4

Consolidation Test



C. Y. GEOTECH, INC.
Geotechnical Engineering and Engineering Geology

GBI / Upper Newport Village

P.N. No: CYG-11-6216


Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before	After	Height (inches)	Diameter (inches)
GB-15	5	19	22	1.0	2.4

Classification : Reddish brown clayey silty sand

Hydroconsolidation = 0 %



C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology


GEI / Upper Newport Village

P.N. No: CYG-11-6216

Date : 10-2011

Consolidation Test

Boring	Depth (feet)	Water Content (%) Before	After	Height (inches)	Diameter (inches)
GB-15	15	28	31	1.0	2.4
Classification : Olive brown clayey silt					
Swelling = 1.2 %					



C. Y. GEOTECH, INC.
Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

P.N. No: CYG-11-6216


Date : 10-2011


Boring	Depth (feet)	Water Content (%) Before	Height (inches)	Diameter (inches)
GB-16	10	8	25	1.0
				2.4

Classification : Yellowish brown sand

Hydroconsolidation = 0.5 %

Consolidation Test





Maximum Dry Density = 122 pcf
Optimum Moisture Content = 10 %

Boring: GB-2
Depth : 3 feet
Description : Reddish brown sandy silty clay

C. Y. GEOTECH, INC.


Geotechnical Engineering
and Engineering Geology

GEL / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Compaction Curve



Maximum Dry Density = 114.5 pcf
Optimum Moisture Content = 13.5 %

Boring: GB-4
Depth : 4.5 feet
Description : Brown silty clay

C. Y. GEOTECH, INC.


Geotechnical Engineering
and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Compaction Curve



Maximum Dry Density = 114.5 pcf
Optimum Moisture Content = 13 %

Boring: GB-5
Depth : 3 feet
Description : Brown silty clay

C. Y. GEOTECH, INC.

Geotechnical Engineering
and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Compaction Curve

C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Boring
GB-1

Depth
(feet)

γ Field
(pcf)

γ Saturate
(pcf)

Fines
(%)

D_{50}
(mm)

Classification : Light gray silty sand
Clay Content = 5 %


Sieve / Hydrometer Analysis

HYDROMETER ANALYSIS

(Grain Size in Millimeters)

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)



COBBLES		GRAVEL			SAND		FINES	
Coarse	Fine	Coarse	Medium	Fine	Coarse	Medium	Silt	Clay

C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Sieve / Hydrometer Analysis

Boring	Depth (feet)	γ_{field} (pcf)	γ_{sat} (pcf)	Fines (%)	D_{50} (mm)
GB-2	15	--	--	35	0.176


Classification : Reddish brown clayey silty sand
Clay Content = 13 %

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES

Coarse

Fine

GRAVEL

Coarse

Medium

Fine

SAND

FINES

Silt

Clay

C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Sieve Analysis

Boring	Depth (feet)	γ_{Field} (pcf)	$\gamma_{Saturate}$ (pcf)	Fines (%)	D_{50} (mm)
GB-4	25	--	--	13	0.396


Classification : Brown sand

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES

Coarse

Fine

GRAVEL

Coarse

Medium

Fine

SAND

Silt

FINES

Clay

C. Y. GEOTECH, INC.						Geotechnical Engineering and Engineering Geology	
GEI / Upper Newport Village							
P.N. No.: CYG-11-6216				Date : 09-2011			
Boring	GB-4	Depth (feet)	45	γ_{Field} (pcf)	--	$\gamma_{Saturate}$ (pcf)	--
		Fines (%)	91	D ₅₀ (mm)	0.016		
Classification : Dark gray clayey silt Clay Content = 32 %							
Sieve / Hydrometer Analysis							

C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Sieve Analysis


Boring	Depth (feet)	γ Field (pcf)	γ Saturate (pcf)	Fines (%)	D_{50} (mm)
GB-5	45	--	--	10	0.213
Classification : Light gray sand					

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES

Coarse

Fine

GRAVEL

Coarse

Medium

Fine

SAND

Silt

FINES

Clay

C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Sieve Analysis

Boring	GB-6	Depth	7.5	γ Field	103	γ Saturate	126	Fines	7	D_{50}	0.355
		(feet)		(pcf)		(pcf)		(%)		(mm)	


Classification : Brown sand

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES

Coarse

GRAVEL

Fine

Coarse

Medium

SAND

Fine

FINES

Silt

Clay

C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GFI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Sieve / Hydrometer Analysis

Boring	Depth (feet)	γ_{field} (pcf)	γ_{sat} (pcf)	Fines (%)	D_{50} (mm)
GB-6	15	--	--	82	0.007


Classification : Brown sandy silty clay
Clay Content = 46 %

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES

Coarse

Fine

GRAVEL

Coarse

Medium

Fine

SAND

Silt

FINES

Clay

C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Sieve / Hydrometer Analysis

Boring GB-7
Depth (feet) 40
 γ_{Field} (pcf) 126
 $\gamma_{Saturate}$ (pcf) 128
Fines (%) 40
 D_{50} (mm) 0.100


Classification : Reddish brown clayey silty sand
Clay Content = 14 %

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES

Coarse

Fine

GRAVEL

Coarse

Medium

Fine

SAND

Silt

FINES

Clay

Grain size in Millimeters

C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Sieve / Hydrometer Analysis

Boring	Depth (feet)	γ_{field} (pcf)	γ_{sat} (pcf)	Fines (%)	D_{50} (mm)
GB-8	15	---	---	66	0.020


Classification : Reddish brown silty sandy clay
Clay Content = 36 %

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES		GRAVEL			SAND		FINES	
Coarse	Fine	Coarse	Medium	Fine	Coarse	Medium	Silt	Clay

C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 09-2011

P.N. No.: CYG-11-6216

Sieve Analysis

Boring	Depth (feet)	γ Field (pcf)	γ Saturate (pcf)	Fines (%)	D_{50} (mm)
GB-9	30	129	135	4	0.733


Classification : Light gray sand

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES		GRAVEL			SAND		FINES	
Coarse	Fine	Coarse	Medium	Fine	Coarse	Medium	Silt	Clay

C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Boring	Depth (feet)	γ field (pcf)	γ Saturate (pcf)	Fines (%)	D_{50} (mm)
GB-11	15	---	---	65	0.030

Classification : Reddish brown clayey sandy silt
Clay Content = 21 %


Sieve / Hydrometer Analysis

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES

Coarse

Fine

GRAVEL

Coarse

Medium

Fine

SAND

Silt

FINES

Clay

C. Y. GEOTECH, INC. Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Sieve Analysis

Boring	GB-12	Depth	35	γ Field	---	γ Saturate	---	Fines	7	D_{50}	0.346
		(feet)		(pcf)		(pcf)		(%)		(mm)	


Classification : Brown sand

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES		GRAVEL			SAND		FINES	
Coarse	Fine	Coarse	Medium	Fine	Coarse	Medium	Silt	Clay

C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Sieve Analysis

Boring	GB-14	Depth	25	γ Field	---	γ Saturate	---	Fines	9	D_{50}	0.317
		(feet)		(pcf)		(pcf)		(%)		(mm)	


Classification : Light gray sand

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES		GRAVEL			SAND		FINES	
Coarse	Fine	Coarse	Medium	Fine	Coarse	Medium	Silt	Clay

C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GEI / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Classification : Olive brown clayey silty sand
Clay Content = 30 %

Boring	Depth (feet)	γ_{field} (pcf)	γ_{sat} (pcf)	Fines (%)	D_{50} (mm)
GB-15	20	---	---	64	0.024


Sieve / Hydrometer Analysis

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES		GRAVEL			SAND		FINES	
Coarse	Fine	Coarse	Medium	Fine	Coarse	Medium	Silt	Clay

C. Y. GEOTECH, INC.

Geotechnical Engineering and Engineering Geology

GB1 / Upper Newport Village

Date : 10-2011

P.N. No.: CYG-11-6216

Sieve / Hydrometer Analysis

Boring	Depth (feet)	γ Field (pcf)	γ Saturate (pcf)	Fines (%)	D_{50} (mm)
GB-16	15	---	---	51	0.071


Classification : Yellowish brown clayey silty sand
Clay Content = 14 %

SIEVE ANALYSIS

(Number of Mesh Per Inch, U.S. Standard)

HYDROMETER ANALYSIS

(Grain Size in Millimeters)



COBBLES

Coarse

GRAVEL

Fine

Coarse

Medium

SAND

Fine

FINES

Silt

Clay

APPENDIX V


LIQUEFACTION ANALYSIS FOR **GINTER & ASSOCIATES, INC.**

LIQUEFACTION ANALYSIS

Uptown Newport Village, Newport Beach

Hole No.=CPT-1 Water Depth=15 ft

Magnitude=6.6
Acceleration=0.36g




LIQUEFACTION ANALYSIS

Uptown Newport Village, Newport Beach

Hole No.=CPT-2 Water Depth=15 ft

Magnitude=6.6
Acceleration=0.36g




LIQUEFACTION ANALYSIS

Uptown Newport Village, Newport Beach

Hole No.=CPT-4 Water Depth=15 ft

Magnitude=6.6
Acceleration=0.36g




LIQUEFACTION ANALYSIS

Uptown Newport Village, Newport Village

Hole No.=CPT-8 Water Depth=15 ft

Magnitude=6.6
Acceleration=0.36g



APPENDIX VI

BORING LOGS BY OTHERS

BORING B-1

LABORATORY TEST DATA										
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0									24	102
5									29	
10	-200 (39)								23	
15									31	
20									23	103
25	-200 (22)								20	
30									36	
35	-200 (6)								32	92
40									22	
45	-200 (32)								39	
50									32	91
55									21	
60									28	97

Boring completed to a depth of 51-1/2 feet on March 7, 1995.
Boring backfilled with cement/bentonite slurry upon completion.

LOG OF BORING **PROPOSED SEISMIC RETROFIT** **BUILDINGS 503 & 505** **For Rockwell International**

Dames & Moore
PLATE 11

BORING B-2

DEPTH IN FEET	LABORATORY TEST DATA									
	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)	BLOMS/F00T
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)				
0	TESTS REPORTED ELSEWHERE									
5	-200 (71)							21		8
10	-200 (54)							16	117	9
15	-200 (58)							16		19
20	-200 (74)							21	107	19
25	-200 (39)							21		25
30								26	100	20
35	-200 (9)							16		87
40	-200 (3)							21	106	57
45								45		16
50								45	79	10
55								38		17
60										

SYMBOL	DESCRIPTION
CL	5-inch thick concrete slab on 5-inch thick base Brown to dark brown and reddish-brown silty fine sandy CLAY (medium stiff to stiff) [Fill]
CL	Grades with AC fragments Brown to dark brown fine sandy silty CLAY (stiff to very stiff)
CL	Grades with some gravel and trace organics
CL	Grades to include light brown sand and clayey sand lenses
SP SM	Gray fine to coarse SAND with silt (very dense)
CL	Grades with less silt (dense) Olive-gray to gray silty CLAY with trace shell fragments

Boring completed to a depth of 51-1/2 feet on
March 7, 1995
Boring backfilled with cement/bentonite slurry upon completion.

LOG OF BORING

PROPOSED SEISMIC RETROFIT BUILDINGS 503 & 505 For Rockwell International

Dames & Moore
PLATE 12

BORING B-3

LABORATORY TEST DATA										
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5									25	100
10									22	
15	-200 (65)								19	110
20	-200 (92)								32	
25	-200 (61)								31	92
30									35	
35	-200 (78)								27	100
40									39	
45									43	82
50	-200 (48)								24	
55										
60										

SYMBOL	DESCRIPTION
CL	5-inch thick asphaltic concrete pavement Brown to yellowish-brown fine to coarse sandy silty CLAY (medium stiff)
	Grades (very stiff)
ML	Olive-gray to yellowish-brown fine sandy SILT (medium dense)
	Grades with trace clay
CL	Olive-gray and brown silty CLAY with yellowish staining (very stiff)
	Grades (soft)
	Grades olive-gray with more silt and iron staining (medium stiff to very stiff)
SC	Gray clayey fine SAND (dense)

Boring completed to a depth of 51-1/2 feet on
March 8, 1995.
Boring backfilled with a cement/bentonite slurry
upon completion.

LOG OF BORING **PROPOSED SEISMIC RETROFIT** **BUILDINGS 503 & 505** **For Rockwell International**

Dames & Moore
PLATE 13

UNIFIED SOIL CLASSIFICATION SYSTEM


MAJOR DIVISIONS			SYMBOL	DESCRIPTION
COARSE GRAINED SOILS	GRAVEL AND GRAVELLY SOILS MORE THAN 50% OF COARSE FRACTION RETAINED ON No. 4 SIEVE	CLEAN GRAVELS (LITTLE OR NO FINES)	GW	WELL-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
		GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES)	GP	POORLY-GRADED GRAVELS, GRAVEL-SAND MIXTURES, LITTLE OR NO FINES
	SAND AND SANDY SOILS MORE THAN 50% OF COARSE FRACTION PASSING No. 4 SIEVE	CLEAN SAND (LITTLE OR NO FINES)	GM	SILTY GRAVELS, GRAVEL-SAND-SILT MIXTURES
		SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES)	GC	CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES
FINE GRAINED SOILS	MORE THAN 50% OF MATERIAL IS LARGER THAN No. 200 SIEVE	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	SW	WELL-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
			SP	POORLY-GRADED SANDS, GRAVELLY SANDS, LITTLE OR NO FINES
		SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	SM	SILTY SANDS, SAND-SILT MIXTURES
			SC	CLAYEY SANDS, SAND-CLAY MIXTURES
HIGHLY ORGANIC SOILS	MORE THAN 50% OF MATERIAL IS SMALLER THAN No. 200 SIEVE	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50	ML	INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
			CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
		SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
			MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS
		SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50	CH	INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS
			OH	ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
			PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE CLASSIFICATIONS


KEY TO LOG OF BORINGS

SAMPLE TYPES	LABORATORY TESTS
<div>INDICATES HAMMER BLOWS PER FOOT OF PENETRATION</div> <div>INDICATES DAMES & MOORE TYPE U SAMPLE</div> <div>STANDARD PENETRATION TEST</div> <div>INDICATES DISTURBED OR BULK SAMPLE</div> <div>DAMES & MOORE TYPE U SAMPLER DRIVEN TYPICALLY 18 INCHES DROPPING A 380-POUND HAMMER 18-INCHES.</div>	<div>-200</div> <div>Percent passing the No. 200 Sieve (Test Results in Parentheses)</div>
<div>PROPOSED SEISMIC RETROFIT BUILDING 503 & 505 For Rockwell International</div> <div>Dames & Moore PLATE 14 - CONTINUED</div>	

SOIL SAMPLER TYPE U FOR SOILS DIFFICULT TO RETAIN IN SAMPLER



ALTERNATE ATTACHMENTS



Dames & Moore
PLATE 10

PLOT PLAN
BUILDING 503 BASE ISOLATION PROJECT
NEW PROT BEACH, CALIFORNIA
For Rockwell International

APPROXIMATE BORING LOCATION & DESIGNATION


KEY
B-23

DRAFT


BUILDING 503

BUILDING 503
ADDITION


SCALE IN FEET
0 40



SOIL SAMPLER TYPE U FOR SOILS DIFFICULT TO RETAIN IN SAMPLER



ALTERNATE ATTACHMENTS



Dames & Moore
PLATE 3

417.5 (68)

LABORATORY TEST DATA

DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA				MOISTURE CONTENT (%)	DRY DENSITY (PCF)
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)		
0								
5	46	29					21	106
10							15	118
15							15	122
20								
25								
30								
35								
40								

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA

For Rockwell International, Inc.

Dames & Moore
PLATE 4

BORING B-1

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
8.5-inch thick CONCRETE slab	
39.5-inch thick LIME STABILIZED SOIL	
CL	Mottled dark gray and dark brown silty CLAY with lenses of grayish-brown sandy silt (stiff) [FILL]
	Grades dark brown without sandy silt lenses
SC	Brown silty clayey fine SAND with trace organics (hard)

NOTES:

1. Boring drilled using a limited access hollow-stem auger drilling rig.
2. Boring completed to a depth of 16.5 feet on September 27, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LABORATORY TEST DATA






DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA					TESTS REPORTED ELSEWHERE
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)	MOISTURE CONTENT (%)	
0								DRY DENSITY (PCF)
5							22	103
10			UC		2293		21	104
15	-200 (90)						16	99
20	-200 (23)						24	97
25							27	95
30								
35								
40								

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

BORING B-2

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
	8-inch thick CONCRETE slab
	6-inch thick AGGREGATE BASE
	34-inch thick LIME STABILIZED SOIL
CL	Mottled dark brown and brown silty CLAY with trace sand (very stiff) [FILL]
	Grades with seams of tan fine to coarse sandy clay
ML	Brown to brownish-yellow fine sandy SILT (hard)
	Brown clayey silty fine SAND (very dense)
SM SC	
CL	Brown silty CLAY with trace sand (very stiff)

NOTES:

1. Boring drilled using a limited access hollow-stem auger drilling rig.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

Dames & Moore
PLATE 5

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5									22	103
		43	26						23	104
10	CON TXCU								22	107
									21	107
15									20	109
20										
25										
30										
35										
40										

BORING B-3

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
	8.5-inch thick CONCRETE slab
	6-inch thick AGGREGATE BASE
	34-inch thick LIME STABILIZED SOIL
CL	Mottled dark brown and brown silty CLAY with trace sand (very stiff) [FILL]
	Grades dark brown with less sand
	Grades mottled dark brown and brown with trace sand
	Grades grayish-brown with seams of white very fine sandy silt and trace iron staining (hard)

NOTES:

1. Boring drilled using a limited access hollow-stem auger drilling rig.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA

For Rockwell International, Inc.

Dames & Moore
PLATE 6

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5									18	109
10				UC		4868			17	108
-200 (74)									16	85
15									16	114
20										
25										
30										
35										
40										

BORING B-4

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
	8-inch thick CONCRETE slab
	6-inch thick AGGREGATE BASE
	34-inch thick LIME STABILIZED SOIL
CL	Mottled dark brown and brown silty CLAY (very stiff) [FILL]
	Grades with trace sand (hard)
	Grades dark brown with more sand, some silt and trace gravel and organics
CL	Reddish-brown silty fine sandy CLAY (hard)

NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
 ROCKWELL BUILDING 503
 NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
 PLATE 7


LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5									19	109
10									19	110
15	CON -200 (44)			UC		2952			15	111
20									14	121
25										
30										
35										
40										

BLOMS/FOOT
SAMPLE TYPE

BORING B-5

ELEVATION: +100.0 Feet (Rockwell Datum)



NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
PLATE 8


BORING B-6

ELEVATION: +100.0 Feet (Rockwell Datum)

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5	-200 (88)								16	113
10		44	18						17	112
15	-200 (16)								18	111
20									16	116
25	-200 (27)								17	105
30										
35										
40										

BLOMS/FOOT
SAMPLE TYPE



NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA

For Rockwell International, Inc.

Dames & Moore
PLATE 9

BORING B- 7

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE

DEPTH IN FEET	LABORATORY TEST DATA						
	TESTS REPORTED ELSEWHERE	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	STRENGTH LIMITS	STRENGTH TESTS		
				TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	PERCENT PASSING # 200 SIEVE
							MOISTURE CONTENT (%)
							DRY DENSITY (PCF)
0							
5							
10							
15							
20							
25							
30							
35							
40							

SYMBOL	DESCRIPTION
	8-inch thick CONCRETE slab
	6-inch thick AGGREGATE BASE
	34-inch thick LIME STABILIZED SOIL

Encountered subsurface utility

NOTES:

1. Boring pre-drilled using a concrete coring machine.
2. Boring terminated at a depth of 4 feet on September 29, 1996 due to presence of an underground utility.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

Dames & Moore
PLATE 10

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5									28	102
10									19	99
15									22	97
20										
25										
30										
35										
40										

BORING B-8

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
8'-4"	8-inch thick CONCRETE slab
	6-inch thick AGGREGATE BASE SEE NOTE (NO. 5)
	34-inch thick LIME STABILIZED SOIL
CL	Mottled dark brown and brown silty CLAY (very stiff) [FILL]
ML CL	Brownish-yellow clayey SILT to silty CLAY with some sand (stiff) [FILL]
ML	Brownish-yellow fine sandy SILT with trace clay (very stiff)
CL	Brownish-yellow silty CLAY with trace sand (hard)

NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 29, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.
5. Water refilling in hole through soil to a depth of 1 foot.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

Dames & Moore
PLATE 11

BORING B-9

ELEVATION: +100.0 Feet (Rockwell Datum)

LABORATORY TEST DATA									
DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA				TYPE OF TEST	PLASTICITY INDEX (%)	LIQUID LIMIT (%)
	TESTS REPORTED ELSEWHERE								
0									
5									
10	-200 (35) TXCU								
15									
20									
25									
30									
35									
40									

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
	8.5-inch thick CONCRETE slab
	4-inch thick AGGREGATE BASE
	35.5-inch thick LIME STABILIZED SOIL
CL	Mottled brown and brownish-yellow silty CLAY with seams of white clayey silt (very stiff) [POSSIBLE FILL]
	Grades brownish-yellow with trace sand and gravel
ML	Brownish-yellow fine sandy SILT with trace clay (hard)
	Grades with trace iron staining

NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 29, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

Dames & Moore
PLATE 12

LABORATORY TEST DATA

DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA						MOISTURE CONTENT (%)	DRY DENSITY (PCF)
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)				
0										
5										
10	-200 (69)	59 30							25	98
15	-200 (46)								20	102
20									17	95
25									28	96
30										
35										
40										

BORING B-10

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
	8-inch thick CONCRETE slab
	4-inch thick AGGREGATE BASE
	36-inch thick LIME STABILIZED SOIL
CL	Mottled dark brown and brown silty CLAY with seams of white clayey silt (very stiff) [FILL]
CH	Mottled brown and brownish-yellow CLAY with some sand and silt (hard)
ML	Brown very fine to fine sandy SILT with trace clay (hard)
SM	Brown silty clayey SAND (medium dense)
SC	Mottled brown and brownish-yellow silty CLAY (very stiff)

NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 29, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

Dames & Moore
PLATE 13


LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5										
10	TXCU									
15	CON	51	28	UC	3989					
20										
25										
30										
35										
40										

BORING B-11

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE



NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with benonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
PLATE 14

BORING B-12

ELEVATION: +100.0 Feet (Rockwell Datum)

LABORATORY TEST DATA									
DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA				TYPE OF TEST	TESTS REPORTED ELSEWHERE	
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)	MOISTURE CONTENT (%)			
0									
5									
10									
15									
20									
25									
30									
35									
40									

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
8-inch thick CONCRETE slab	
6-inch thick AGGREGATE BASE	
34-inch thick LIME STABILIZED SOIL	
CL	Mottled dark brown and brown silty CLAY with trace sand (very stiff) [FILL]
SC	Gray clayey fine to coarse SAND (dense) [FILL]
SM SC	Reddish-brown to brown silty clayey SAND (very dense)

NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

Dames & Moore
PLATE 15

LABORATORY TEST DATA

DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0									
5			UC		1382			19	106
10								19	106
								18	112
								12	121
								18	111
15									
20									
25									
30									
35									
40									

BORING B-13

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
	8-inch thick CONCRETE slab
	4-inch thick AGGREGATE BASE
	36-inch thick LIME STABILIZED SOIL
CL	Mottled dark brown and brown silty CLAY (stiff) [FILL]
	Grades with trace sand (stiff)
SC	Gray clayey fine to coarse SAND (dense) [FILL] Very wet
CL	Mottled dark brown and brown silty CLAY (hard) [FILL]
CL	Reddish-brown to brown sandy silty CLAY (hard)

NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 29, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

Dames & Moore
PLATE 16

LABORATORY TEST DATA

DEPTH IN FEET	ATTERBERG LIMITS		TYPE OF TEST	STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)		NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)	(PSF)			
TESTS REPORTED ELSEWHERE										
5	-200 (76)							21	103	
10								20	108	
15	CON -200 (26)							18	102	
								18	111	
20										
25										
30										
35										
40										

BORING B-14

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
	8-inch thick CONCRETE slab
	4-inch thick AGGREGATE BASE
	36-inch thick LIME STABILIZED SOIL
CL	Mottled dark brown and brown silty CLAY (very stiff) [FILL]
	Grades with trace sand
	Grades to include seams of gray fine to coarse sand
SC	Reddish-brown to brown clayey fine to coarse SAND with some silt (dense)
	Grades with more sand

NOTES:

1. Boring drilled using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with benonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
PLATE 17









LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5		47	26						24	96
10	-200 (77)								20	105
15	-200 (50)								16	112
20	-200 (55)								12	120
25									13	119
30										
35										
40										

BORING B-15

ELEVATION: +100.0 Feet (Rockwell Datum)

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
	8-inch thick CONCRETE slab
	4-inch thick AGGREGATE BASE
	36-inch thick LIME STABILIZED SOIL
	CL Mottled dark brown and brown silty CLAY with trace sand (hard) [FILL]
	Grades to include seams of olive-gray silty fine to medium sand
	Grades without seams of silty sand (very stiff)
	ML Reddish-brown to brown sandy clayey SILT (hard)
	Grades with more sand and less clay

NOTES:

1. Boring drilled using hand-auger equipment.
2. Boring completed to a depth of 16.5 feet on September 28, 1996.
3. No groundwater encountered.
4. Boring backfilled with bentonite chips and capped with concrete upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
 PLATE 18

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5									15	119
10									23	102
15									11	104
20										
25										
30										
35										
40										

BORING B-16

ELEVATION: +99.5 Feet (Rockwell Datum)

BLOMS/F00T

SYMBOL	DESCRIPTION
CL	Reddish-brown fine sandy silty CLAY (stiff)
ML	Brownish-yellow to brown fine sandy SILT with trace clay (stiff)
SM	Dark brown to brown silty fine to medium SAND (dense)

NOTES:

1. Boring drilled manually using hand-auger equipment.
2. Boring completed to a depth of 15.5 feet on October 13, 1996.
3. No groundwater encountered.
4. Boring backfilled with Volclay grout upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.


Dames & Moore
PLATE 19

BORING B-17

ELEVATION: +99.5 Feet (Rockwell Datum)

BLOMS/F00T
SAMPLE TYPE

LABORATORY TEST DATA										
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5									16	105
10									9	98
15									19	102
20										
25										
30										
35										
40										



- NOTES:
1. Boring drilled using hand-auger equipment.
 2. Boring completed to a depth of 15.5 feet on October 13, 1996.
 3. No groundwater encountered.
 4. Boring backfilled with Volclay grout upon completion.

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
PLATE 20

LABORATORY TEST DATA

DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0	TESTS REPORTED ELSEWHERE								
5									
10								20	105
15								23	
20								28	97
25								7	
30								4	103
35								19	
40	CON								

BORING B-18

ELEVATION: +99.5 Feet (Rockwell Datum)

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
Bk	7-inch thick CONCRETE slab on 2 inches of pea gravel
CL	Dark brown silty CLAY with trace fine sand and organics (very stiff) [FILL]
46	Grades brown with more fine sand
38	Greenish-gray to olive-gray silty CLAY with trace fine sand and iron staining (hard)
110	
53	Light brown to brown silty fine SAND (very dense)
100 / 6	
78	Gray to light gray fine to medium SAND with silt, wet (very dense)
CL	Greenish-gray to olive-gray silty CLAY (very stiff)

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
PLATE 21

BORING B-18 Continued

LABORATORY TEST DATA									
DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
40								40	83
45								36	
50								36	89
55								22	
60								19	110
65								2	
70								12	96
75									
80									

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
CL	Greenish-gray to olive-gray silty CLAY (very stiff) [Continued]
SM	Gray silty fine SAND (dense)
SP	Grades greenish-gray with some clay (very dense)
SM	Light gray fine to coarse SAND with silt (very dense)
SM SC	Gray silty clayey fine to medium SAND (very dense)

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA

For Rockwell International, Inc.

Dames & Moore
PLATE 21 (cont.)

DRAFT

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			

BORING B-19

ELEVATION: +99.5 Feet (Rockwell Datum)

BLOMS/FOOT
SAMPLE TYPE

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)		MOISTURE CONTENT (%)	DRY DENSITY (PCF)	SYMBOL	DESCRIPTION
0												4-inch thick AC pavement
												2-inch thick AB section
												2-inch thick AC pavement
												Yellow-red clayey fine to coarse SAND with some gravel and silt [FILL]
5											CL	Dark brown silty CLAY with some sand and organics (very stiff) [FILL]
10									13		21	
15									18	115	62	Yellowish-red silty CLAY with some sand (very stiff)
20									11		40	Brownish-yellow to yellowish-red silty clayey fine to medium SAND (dense)
25									10	104	100 / 6"	Brownish-yellow silty fine SAND (very dense)
30									10		50 / 6"	Gray fine to medium SAND with silt (very dense)
35									21	106	76	Grades dark gray, wet
40												Dark brown silty CLAY with some iron staining (very stiff)

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

DRAFT

Dames & Moore
PLATE 22

BORING B-19 Continued

DEPTH IN FEET	LABORATORY TEST DATA						
	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA			
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)
40							
45							
50							
55							
60							
65							
70							
75							
80							

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
CL	Dark brown silty CLAY with some iron staining (very stiff) (Continued)
	Grades dark gray to gray

NOTES:

1. Boring drilled using a truck-mounted hollow-stem auger drilling rig.
 2. Boring completed to a depth of 51.5 feet on October 12, 1996.
 3. Groundwater encountered at a depth of 35 feet.
 4. Boring backfilled with Volclay grout upon completion.
- Hammer Weight: 140 lbs
Drop Height: 30 inches

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

Dames & Moore
PLATE 22 (cont.)

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		TYPE OF TEST	STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)		NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)				
0											
5											
10									13	120	
15									19		
20	CON								29	95	
25									13		
30									11	110	
35									14		
40											

BORING B-20

ELEVATION: +99.5 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
CL	Brown silty CLAY with some sand [FILL]
SC	Yellowish-red clayey fine to coarse SAND with some silt (dense)
CL	Mottled brown fine sandy CLAY (hard)
SM	Brownish-yellow to yellowish-red silty fine SAND (dense)
Grades gray	
Grades wet	
SP SM	Brown fine to coarse SAND with silt (very dense)

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA

For Rockwell International, Inc.

Dames & Moore
PLATE 23

DRAFT

BORING B-20 Continued

LABORATORY TEST DATA										
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		TYPE OF TEST	STRENGTH TEST DATA				MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)		NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
40									17	106
45									37	
50									14	120
55										
60										
65										
70										
75										
80										

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
SP	Brown fine to coarse SAND with silt (very dense)
SM	[Continued]
CL	Mottled greenish-gray and yellowish-red silty CLAY (hard)
	Grades (very stiff)
SM	Dark gray silty fine SAND (dense)

NOTES:

1. Boring drilled using a truck-mounted hollow-stem auger drilling rig.
 2. Boring completed to a depth of 51.5 feet on October 12, 1996.
 3. Groundwater encountered at a depth of 32 feet.
 4. Boring backfilled with Volclay grout upon completion.
- Hammer Weight: 140 lbs
Drop Height: 30 inches

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
PLATE 23 (cont.)

BORING B-21 Continued

LABORATORY TEST DATA											
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA						MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)				
80										20	106
85										25	
90										21	110
95										22	
100										20	105
105											
110											
115											
120											

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
SP	Gray fine to medium SAND with silt (very dense)
SM	[Continued]
SM	Dark gray silty fine to medium SAND (very dense)
SP	Dark gray fine to coarse SAND (very dense)

- NOTES:
- Boring drilled using a truck-mounted hollow-stem auger drilling rig.
 - 4-inch diameter Schedule 80 PVC pipe installed to a depth of 100 feet.
 - Boring completed to a depth of 101 feet on October 11, 1996.
 - Groundwater encountered at a depth of 30 feet.
 - Boring backfilled with Volclay grout upon completion.
- Hammer Weight: 140 lbs
Drop Height: 30 inches

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
For Rockwell International, Inc.

Dames & Moore
PLATE 24 (cont.)

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		TYPE OF TEST	STRENGTH TEST DATA				MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)		NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5										
10									16	105
15									26	
20	CON								31	87
25									22	
30	CON								23	103
35									30	
40										

BORING B-22

ELEVATION: +99.5 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
CL	Dark brown silty CLAY [FILL]
SM SC	Brown to yellowish-red silty clayey fine to medium SAND [FILL]
SC	Brownish-yellow clayey fine to medium SAND (medium dense) [FILL]
ML	Brown fine sandy clayey SILT (very stiff)
CL	Brown fine sandy silty CLAY (very stiff)
	Grades olive-gray
CL	Brown to olive-gray clayey fine to medium SAND (dense)
▽	Grades wet
SP SM	Gray silty fine to medium SAND with silt
CL	Olive-gray silty CLAY (stiff)

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA

For Rockwell International, Inc.

Dames & Moore
PLATE 25

DRAFT

LABORATORY TEST DATA

DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
	TESTS REPORTED ELSEWHERE	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)		
0									
5									
10								16	113
15								23	
20								22	108
25								5	
30	CON							28	96
35								34	
40									

BLOWS/FOOT
SAMPLE TYPE

BORING B-23

ELEVATION: +99.5 Feet (Rockwell Datum)

SYMBOL	DESCRIPTION
SC	4-inch thick CONCRETE slab Dark brown clayey fine to medium SAND (dense)
CL	Brown silty CLAY (very stiff)
SC	Olive-gray clayey fine to medium SAND (very dense)
SP SM	Brownish-yellow fine to medium SAND with silt (very dense)
CL	Olive-gray silty CLAY, wet (stiff to very stiff)

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA

For Rockwell International, Inc.

Dames & Moore
PLATE 26

DRAFT

BORING B-23 Continued

LABORATORY TEST DATA										
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
40									25	101
45									19	
50									6	101
55										
60										
65										
70										
75										
80										

BLOMS/FOOT	SYMBOL	DESCRIPTION
18	CL	Olive-gray silty CLAY (stiff to very stiff) [Continued]
90 /6	CL	Olive-gray to gray clayey fine to medium SAND (dense to very dense)
33		Grades with more sand

NOTES:

1. Boring drilled using a truck-mounted hollow-stem auger drilling rig.
 2. Boring completed to a depth of 51.5 feet on October 11, 1996.
 3. Groundwater encountered at a depth of 30 feet.
 4. Boring backfilled with Volclay grout upon completion.
- Hammer Weight: 140 lbs
Drop Height: 30 inches

DRAFT

LOG OF BORING
ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
PLATE 26 (cont.)

LABORATORY TEST DATA

DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0										
5										
10									23	
15									22	99
20									12	
25	CON								16	106
30									35	
35	CON								36	87
40										

BORING B-24

ELEVATION: +99.5 Feet (Rockwell Datum)

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
SC	4-inch thick CONCRETE slab
	Brown to reddish-brown clayey fine to medium SAND (medium dense to dense)
SM	Brownish-yellow silty fine SAND (medium dense to dense)
CL	Brown to olive-green fine sandy silty CLAY (very stiff)
SM SC	Grades to include more sand Olive-green to brownish-yellow silty fine to medium SAND with clay (dense)
SC	Brownish-yellow fine to medium clayey SAND with some silt (very dense)
CL	Dark gray silty CLAY, wet (stiff to very stiff)

LOG OF BORING

ROCKWELL BUILDING 503
NEWPORT BEACH, CALIFORNIA

For Rockwell International, Inc.

Dames & Moore
PLATE 27

BORING B-24 Continued

DEPTH IN FEET	LABORATORY TEST DATA								
	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS	STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
			LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)		
40								31	
45								7	96
50								21	
55									
60									
65									
70									
75									
80									

BLOMS/FOOT

44

34

95
/6"

SYMBOL	DESCRIPTION
CL	Dark gray silty CLAY (stiff to very stiff) [Continued]
SP SM	Gray fine to medium SAND with silt (dense)
CL	Gray to mottled brown fine sandy silty CLAY (hard)

NOTES:

1. Boring drilled using a truck-mounted hollow-stem auger drilling rig.
 2. Boring completed to a depth of 51 feet on October 11, 1996.
 3. Groundwater encountered at a depth of 30 feet.
 4. Boring backfilled with Volclay grout upon completion.
- Hammer Weight: 140 lbs
Drop Height: 30 inches

RECEIVED

LOG OF BORING
 ROCKWELL BUILDING 503
 NEWPORT BEACH, CALIFORNIA
 For Rockwell International, Inc.

Dames & Moore
 PLATE 27 (cont.)

UNIFIED SOIL CLASSIFICATION SYSTEM			
MAJOR DIVISIONS		GRAPHIC SYMBOL	LETTER SYMBOL
			TYPICAL DESCRIPTIONS
COARSE GRAINED SOILS	GRAVEL AND GRAVELLY SOILS		A F
			ARTIFICIAL FILL
	MORE THAN 50% OF COARSE FRACTION RETAINED ON NO. 4 SIEVE	CLEAN GRAVELS (LITTLE OR NO FINES)	G W
		GRAVELS WITH FINES (APPRECIABLE AMOUNT OF FINES)	G P
MORE THAN 50% OF MATERIAL IS LARGER THAN NO. 200 SIEVE SIZE			G M
			SILT GRAVELS, GRAVEL-SAND MIXTURES
	SAND AND SANDY SOILS		G C
			CLAYEY GRAVELS, GRAVEL-SAND-CLAY MIXTURES
FINE GRAINED SOILS	MORE THAN 50% OF COARSE FRACTION PASSING NO. 4 SIEVE	CLEAN SAND (LITTLE OR NO FINES)	S W
		SANDS WITH FINES (APPRECIABLE AMOUNT OF FINES)	SP
			S M
			SILT SANDS, SAND-SILT MIXTURES
MORE THAN 50% OF MATERIAL IS SMALLER THAN NO. 200 SIEVE SIZE	SILTS AND CLAYS LIQUID LIMIT LESS THAN 50		SC
			CLAYEY SANDS, SAND-CLAY MIXTURES
			M L
			INORGANIC SILTS AND VERY FINE SANDS, ROCK FLOUR, SILTY OR CLAYEY FINE SANDS OR CLAYEY SILTS WITH SLIGHT PLASTICITY
HIGHLY ORGANIC SOILS	SILTS AND CLAYS LIQUID LIMIT GREATER THAN 50		CL
			INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
			OL
			ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
			M H
			INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS FINE SAND OR SILTY SOILS
			CH
			INORGANIC CLAYS OF HIGH PLASTICITY, FAT CLAYS
			OH
			ORGANIC CLAYS OF MEDIUM TO HIGH PLASTICITY, ORGANIC SILTS
			PT
			PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

NOTE: DUAL SYMBOLS ARE USED TO INDICATE BORDERLINE SOIL CLASSIFICATIONS

KEY TO LOG OF BORINGS

SAMPLES & BLOWCOUNTS

- ☐ 30 HAMMER BLOWS PER FOOT OF PENETRATION
☐ INDICATES UNDISTURBED DAMES & MOORE SAMPLE
☒ INDICATES DISTURBED OR BULK DAMES & MOORE SAMPLE
☒ STANDARD PENETRATION TEST SAMPLE
☐ INDICATES NO RECOVERY
 DAMES & MOORE AND SPT SAMPLERS DRIVEN WITH A 140-POUND HAMMER DROPPING 30 INCHES

LABORATORY TESTS

- AL ATTERBERG LIMITS TEST
 TXCU TRIAXIAL TEST (Consolidated, Undrained)
 -200 PERCENT PASSING NO. 200 SIEVE (Test results in parentheses)
 CON CONSOLIDATION (Confined Compression) TEST
 UC UNCONFINED COMPRESSION TEST

APPENDIX VII

LABORATORY TESTING BY OTHERS

LOE OF BORING NO 510

DATE DRILLED: Feb. 20, 1967
EQUIPMENT USED: Bucsek Auger

FLY. OF SURFACE: 46.3

EQUIPMENT USED: BUCKET AUGER									
DESCRIPTION OF SOILS									
Depth in Feet	Samples	Densities per foot	CLASSIFICATION				Unit	COHESION OR SHEAR RES. KIPS PER SQUARE FOOT	
			Color	Moisture	Consistency	lb. Per cu. ft.	MOISTURE PERCENT DRY / WET		
								2	3
								4	5
								6	7
								8	9
								10	11
								12	13
								14	15
								16	17
								18	19
								20	21
								22	23
								24	25
								26	27
								28	29
								30	31
								32	33
								34	35
								36	37
								38	39
								40	41
								42	43
								44	45
								46	47
								48	49
								50	51
								52	53
								54	55
								56	57
								58	59
								60	61
								62	63
								64	65
								66	67
								68	69
								70	71
								72	73
								74	75
								76	77
								78	79
								80	81
								82	83
								84	85
								86	87
								88	89
								90	91
								92	93
								94	95
								96	97
								98	99
								100	101
								102	103
								104	105
								106	107
								108	109
								110	111
								112	113
								114	115
								116	117
								118	119
								120	121
								122	123
								124	125
								126	127
								128	129
								130	131
								132	133
								134	135
								136	137
								138	139
								140	141
								142	143
								144	145
								146	147
								148	149
								150	151
								152	153
								154	155
								156	157
								158	159
								160	161
								162	163
								164	165
								166	167
								168	169
								170	171
								172	173
								174	175
								176	177
								178	179
								180	181
								182	183
								184	185
								186	187
								188	189
								190	191
								192	193
								194	195
								196	197
								198	199
								200	201
								202	203
								204	205
								206	207
								208	209
								210	211
								212	213
								214	215
								216	217
								218	219
								220	221
								222	223
								224	225
								226	227
								228	229
								230	231
								232	233
								234	235
								236	237
								238	239
								240	241
								242	243
								244	245
								246	247
								248	249
								250	251
								252	253
								254	255
								256	257
								258	259
								260	261
								262	263
								264	265
								266	267
								268	269
								270	271
								272	273
								274	275
								276	277
								278	279
								280	281
								282	283
								284	285
								286	287
								288	289
								290	291
								292	293
								294	295
								296	297
								298	299
								300	301
								302	303
								304	305
								306	307
								308	309
								310	311
								312	313
								314	315
								316	317
								318	319
								320	321
								322	323
								324	325
								326	327
								328	329
								330	331
								332	333
								334	335
								336	337
								338	339
								340	341
								342	343
								344	345
								346	347
								348	349
								350	351
								352	353
								354	355
								356	357
								358	359
								360	361
								362	363
								364	365
								366	367
								368	369
								370	371
								372	373
								374	375
								376	377
								378	379
								380	381
								382	383
								384	385
								386	387
								388	389
								390	391
								392	393
								394	395
								396	397
								398	399
								400	401
								402	403
								404	405
								406	407
								408	409
								410	411
								412	413
								414	415
								416	417
								418	419
								420	421
								422	423
								424	425
								426	427
								428	429
								430	431
								432	433
								434	435
								436	437
								438	439
								440	441
								442	443
								444	445
								446	447
								448	449
								450	451
								452	453
								454	455
								456	457
								458	459
								460	461
								462	463
								464	465
								466	467
								468	469
								470	471
								472	473
								474	47

101-5004-750-11 p-25


CONSOLIDATED UNDRAINED TRIAXIAL TEST

Project Name: Rockwell
Project No.: 10839-211-004
Boring No.: B-1
Sample No.: 1T
Depth (feet): 5

Sample Type: Undisturbed
Soil Description: Gray Silty Clay, m. stiff
Dry Density (pcf): 106.3
Moisture Content (%): 20.3

Sample Diameter (inch): 2.415
Sample Height (inch): 5.5
Sample Weight (gms): 846.16

Wet Wt of Soil + Tare (gms) 1045.32
Dry Wt of Soil + Tare (gms) 902.48
Wt of Tare (gms) 199.43



Vertical Stress (psf)	Deformation (inch)	Area (sq.in)	Lateral Stress (psf)	Vertical Strain (%)
3500	0.0000	4.5808	1750	0.00
3500	0.0005	4.5810	1808	0.01
3500	0.0010	4.5815	1462	0.02
3500	0.0035	4.5835	1318	0.06
3500	0.0065	4.5860	1174	0.12
3500	0.0130	4.5915	1030	0.24
3500	0.0270	4.6032	888	0.49
3500	0.0560	4.6277	742	1.02
3500	0.1000	4.6655	598	1.82
3500	0.1650	4.7223	454	3.00
3500	0.2200	4.7715	310	4.00
3500	0.3150	4.8589	166	5.73
3500	0.4650	5.0037	0	8.45
3344	0.5000	5.0397		9.09
3339	0.5500	5.0896		10.00
3361	0.6000	5.1415		10.91
3382	0.6500	5.1945		11.82
3429	0.7000	5.2486		12.73
3421	0.7500	5.3039		13.64
3385	0.8000	5.3603		14.55
3375	0.8500	5.4179		15.45
3339	0.9000	5.4768		16.36
3329	0.9500	5.5370		17.27
3282	1.0000	5.5985		18.18

DRAFT


CONSOLIDATED UNDRAINED TRIAXIAL TEST

Project Name: Rockwell
Project No.: 10839-211-004
Boring No.: B-1
Sample No.: 1T
Depth (feet): 5

Sample Type: Undisturbed
Soil Description: Gray Silty Clay, m. stiff
Dry Density (pcf): 106.3
Moisture Content (%): 20.3

Sample Diameter (inch): 2.415
Sample Height (inch): 5.5
Sample Weight (gms): 846.16

Wet Wt of Soil + Tare (gms) 1045.32
Dry Wt of Soil + Tare (gms) 902.48
Wt of Tare (gms) 199.43



Vertical Stress (psf)	Deformation (inch)	Area (sq.in)	Lateral Stress (psf)	Vertical Strain (%)
3500	0.0000	4.5808	1750	0.00
3500	0.0005	4.5810	1808	0.01
3500	0.0010	4.5815	1462	0.02
3500	0.0035	4.5835	1318	0.06
3500	0.0065	4.5860	1174	0.12
3500	0.0130	4.5915	1030	0.24
3500	0.0270	4.6032	888	0.49
3500	0.0560	4.6277	742	1.02
3500	0.1000	4.6655	596	1.82
3500	0.1650	4.7223	454	3.00
3500	0.2200	4.7715	310	4.00
3500	0.3150	4.8569	166	5.73
3500	0.4650	5.0037	0	8.45
3344	0.5000	5.0397		9.09
3339	0.5500	5.0896		10.00
3361	0.6000	5.1415		10.91
3382	0.6500	5.1945		11.82
3429	0.7000	5.2486		12.73
3421	0.7500	5.3039		13.64
3385	0.8000	5.3603		14.55
3375	0.8500	5.4179		15.45
3339	0.9000	5.4768		16.36
3329	0.9500	5.5370		17.27
3282	1.0000	5.5985		18.18

DRAFT


CONSOLIDATED UNDRAINED TRIAXIAL TEST

Project Name: Rockwell
Project No.: 10839-211-004
Boring No.: B-3
Sample No.: 3T
Depth (feet): 10

Sample Type: Undisturbed
Soil Description: Red. Brn Silty Clay, stiff
Dry Density (pcf): 107.9
Moisture Content (%): 19.7

Sample Diameter (inch): 2.415
Sample Height (inch): 5.7
Sample Weight (gms): 885.91

Wet Wt of Soil + Tare (gms) 1082.65
Dry Wt of Soil + Tare (gms) 936.93
Wt of Tare (gms) 196.75



Vertical Stress (psf)	Deformation (inch)	Area (sq.in)	Lateral Stress (psf)	Vertical Strain (%)
3500	0.0000	4.5806	1750	0.00
3500	0.0002	4.5808	1606	0.00
3500	0.0005	4.5810	1462	0.01
3500	0.0010	4.5814	1318	0.02
3500	0.0015	4.5818	1174	0.03
3500	0.0025	4.5826	1030	0.04
3500	0.0035	4.5834	886	0.06
3500	0.0055	4.5851	742	0.10
3500	0.0080	4.5871	598	0.14
3500	0.0125	4.5907	454	0.22
3500	0.0210	4.5976	310	0.37
3500	0.0330	4.6073	166	0.58
3500	0.0550	4.6253	0	0.96
5652	0.1000	4.6624		1.75
6152	0.1500	4.7044		2.63
6461	0.2000	4.7472		3.51
6703	0.2500	4.7908		4.39
6850	0.3000	4.8351		5.26
6993	0.3500	4.8803		6.14
7074	0.4000	4.9263		7.02
7152	0.4500	4.9733		7.89
7170	0.5000	5.0211		8.77
7229	0.6000	5.1195		10.53
7225	0.7000	5.2219		12.28
7189	0.8000	5.3285		14.04
7095	0.9000	5.4395		15.79
6999	1.0000	5.5552		17.54

DRAFT


CONSOLIDATED UNDRAINED TRIAXIAL TEST

Project Name: Rockwell
Project No.: 10839-211-004
Boring No.: B-3
Sample No.: 3T
Depth (feet): 10

Sample Type: Undisturbed
Soil Description: Red. Brn Silty Clay, stiff
Dry Density (pcf): 107.9
Moisture Content (%): 19.7

Sample Diameter (inch): 2.415
Sample Height (inch): 5.7
Sample Weight (gms): 885.91

Wet Wt of Soil + Tare (gms) 1082.65
Dry Wt of Soil + Tare (gms) 936.93
Wt of Tare (gms) 196.75



Vertical Stress (psf)	Deformation (inch)	Area (sq.in)	Lateral Stress (psf)	Vertical Strain (%)
3500	0.0000	4.5806	1750	0.00
3500	0.0002	4.5808	1806	0.00
3500	0.0005	4.5810	1462	0.01
3500	0.0010	4.5814	1318	0.02
3500	0.0015	4.5818	1174	0.03
3500	0.0025	4.5826	1030	0.04
3500	0.0035	4.5834	886	0.06
3500	0.0055	4.5851	742	0.10
3500	0.0080	4.5871	598	0.14
3500	0.0125	4.5907	454	0.22
3500	0.0210	4.5976	310	0.37
3500	0.0330	4.6073	166	0.58
3500	0.0550	4.6253	0	0.96
5652	0.1000	4.6624		1.75
6152	0.1500	4.7044		2.63
6461	0.2000	4.7472		3.51
6703	0.2500	4.7908		4.39
6850	0.3000	4.8351		5.26
6993	0.3500	4.8803		6.14
7074	0.4000	4.9263		7.02
7152	0.4500	4.9733		7.89
7170	0.5000	5.0211		8.77
7229	0.6000	5.1195		10.53
7225	0.7000	5.2219		12.28
7189	0.8000	5.3285		14.04
7095	0.9000	5.4395		15.79
6999	1.0000	5.5552		17.54

DRAFT


CONSOLIDATED UNDRAINED TRIAXIAL TEST

Project Name: Rockwell
Project No.: 10839-211-004
Boring No.: B-11
Sample No.: 2T
Depth (feet): 7.5

Sample Type: Undisturbed
Soil Description: Red. Brn Silty Clay, v. stiff
Dry Density (pcf): 114.9
Moisture Content (%): 15.9

Sample Diameter (inch): 2.415
Sample Height (inch): 5.55
Sample Weight (gms): 889.71

Wet Wt of Soil + Tare (gms) 1088.93
Dry Wt of Soil + Tare (gms) 966.62
Wt of Tare (gms) 198.31



Vertical Stress (psf)	Deformation (inch)	Area (sq.in)	Lateral Stress (psf)	Vertical Strain (%)
3500	0.0000	4.5806	1750	0.00
3500	0.0002	4.5808	1606	0.00
3500	0.0005	4.5810	1462	0.01
3500	0.0011	4.5815	1318	0.02
3500	0.0018	4.5821	1174	0.03
3500	0.0028	4.5829	1030	0.05
3500	0.0038	4.5838	886	0.07
3500	0.0050	4.5848	742	0.09
3500	0.0065	4.5860	598	0.12
3500	0.0080	4.5872	454	0.14
3500	0.0115	4.5901	310	0.21
3500	0.0140	4.5922	166	0.25
3500	0.0185	4.5959	0	0.33
4829	0.0500	4.6223		0.90
5649	0.1000	4.6647		1.80
6148	0.1500	4.7079		2.70
6455	0.2000	4.7519		3.60
6695	0.2500	4.7967		4.50
6840	0.3000	4.8424		5.41
6981	0.3500	4.8889		6.31
7059	0.4000	4.9364		7.21
7151	0.5000	5.0342		9.01
7206	0.6000	5.1359		10.81
7188	0.7000	5.2418		12.61
7157	0.8000	5.3521		14.41
7059	0.9000	5.4672		16.22
6959	1.0000	5.5874		18.02

DRAFT


CONSOLIDATED UNDRAINED TRIAXIAL TEST

Project Name: Rockwell
Project No.: 10839-211-004
Boring No.: B-11
Sample No.: 2T
Depth (feet): 7.5

Sample Type: Undisturbed
Soil Description: Red. Brn Silty Clay, v. stiff
Dry Density (pcf): 114.9
Moisture Content (%): 15.9

Sample Diameter (inch): 2.415
Sample Height (inch): 5.55
Sample Weight (gms): 889.71

Wet Wt of Soil + Tare (gms) 1088.93
Dry Wt of Soil + Tare (gms) 966.62
Wt of Tare (gms) 198.31



Vertical Stress (psf)	Deformation (inch)	Area (sq.in)	Lateral Stress (psf)	Vertical Strain (%)
3500	0.0000	4.5806	1750	0.00
3500	0.0002	4.5808	1606	0.00
3500	0.0005	4.5810	1462	0.01
3500	0.0011	4.5815	1318	0.02
3500	0.0018	4.5821	1174	0.03
3500	0.0028	4.5829	1030	0.05
3500	0.0038	4.5838	886	0.07
3500	0.0050	4.5848	742	0.09
3500	0.0065	4.5860	598	0.12
3500	0.0080	4.5872	454	0.14
3500	0.0115	4.5901	310	0.21
3500	0.0140	4.5922	166	0.25
3500	0.0185	4.5959	0	0.33
4829	0.0500	4.6223		0.90
5649	0.1000	4.6647		1.80
6148	0.1500	4.7079		2.70
6455	0.2000	4.7519		3.60
6695	0.2500	4.7967		4.50
6840	0.3000	4.8424		5.41
6981	0.3500	4.8889		6.31
7059	0.4000	4.9364		7.21
7151	0.5000	5.0342		9.01
7206	0.6000	5.1359		10.81
7188	0.7000	5.2418		12.61
7157	0.8000	5.3521		14.41
7059	0.9000	5.4672		16.22
6959	1.0000	5.5874		18.02

DRAFT


CONSOLIDATED UNDRAINED TRIAXIAL TEST

Project Name: Rockwell
Project No.: 10839-211-004
Boring No.: B-12
Sample No.: 1
Depth (feet): 5

Sample Type: Undisturbed
Soil Description: Strong Brn Silty Clay, m. stiff
Dry Density (pcf): 106.5
Moisture Content (%): 19.1

Sample Diameter (inch): 2.415
Sample Height (inch): 5.85
Sample Weight (gms): 893.28

Wet Wt of Soil + Tare (gms) 1093.67
Dry Wt of Soil + Tare (gms) 949.55
Wt of Tare (gms) 196.7



Vertical Stress (psf)	Deformation (inch)	Area (sq.in)	Lateral Stress (psf)	Vertical Strain (%)
3500	0.0000	4.5806	1750	0.00
3500	0.0005	4.5810	1606	0.01
3500	0.0020	4.5822	1462	0.03
3500	0.0040	4.5838	1318	0.07
3500	0.0065	4.5857	1174	0.11
3500	0.0165	4.5936	1030	0.28
3500	0.0380	4.6106	886	0.65
3500	0.0750	4.6401	742	1.28
3500	0.1310	4.6856	598	2.24
3500	0.2150	4.7554	454	3.68
3500	0.3250	4.8501	310	5.56
3500	0.4540	4.9660	166	7.76
3500	0.6370	5.1404	0	10.89
3238	0.7000	5.2032	0	11.97
3234	0.7500	5.2543	0	12.82
3202	0.8000	5.3063	0	13.68
3171	0.8500	5.3593	0	14.53
3165	0.9000	5.4135	0	15.38
3160	0.9500	5.4687	0	16.24
3154	1.0000	5.5251	0	17.09

DRAFT


CONSOLIDATED UNDRAINED TRIAXIAL TEST

Project Name: Rockwell
Project No.: 10839-211-004
Boring No.: B-12
Sample No.: 1
Depth (feet): 5

Sample Type: Undisturbed
Soil Description: Strong Brn Silty Clay, m. stiff
Dry Density (pcf): 106.5
Moisture Content (%): 19.1


Sample Diameter (inch): 2.415
Sample Height (inch): 5.85
Sample Weight (gms): 893.28

Wet Wt of Soil + Tare (gms) 1093.67
Dry Wt of Soil + Tare (gms) 949.55
Wt of Tare (gms) 196.7



Vertical Stress (psf)	Deformation (inch)	Area (sq.in)	Lateral Stress (psf)	Vertical Strain (%)
3500	0.0000	4.5806	1750	0.00
3500	0.0005	4.5810	1606	0.01
3500	0.0020	4.5822	1462	0.03
3500	0.0040	4.5838	1318	0.07
3500	0.0065	4.5857	1174	0.11
3500	0.0165	4.5936	1030	0.28
3500	0.0380	4.6106	886	0.65
3500	0.0750	4.6401	742	1.28
3500	0.1310	4.6856	598	2.24
3500	0.2150	4.7554	454	3.68
3500	0.3250	4.8501	310	5.56
3500	0.4540	4.9660	166	7.76
3500	0.6370	5.1404	0	10.89
3238	0.7000	5.2032	0	11.97
3234	0.7500	5.2543	0	12.82
3202	0.8000	5.3063	0	13.68
3171	0.8500	5.3593	0	14.53
3165	0.9000	5.4135	0	15.38
3160	0.9500	5.4687	0	16.24
3154	1.0000	5.5251	0	17.09

DRAFT



LEGEND:


- At Field Moisture
● After Addition of Water

Boring No. B-1 Initial Dry Density (pcf) 116.5
Sample No. 2R Moisture Content (%):
Depth (feet) 10.0 Before 17.3
Soil Type CL After 15.1
Soil Description Dk Brn Sandy Clay

DRAFT

CONSOLIDATION CURVE

Project No. 10839-211-004
Project Name Rockwell
Date 10/29/96 Figure No.



LEGEND:


- At Field Moisture
● After Addition of Water

Boring No. B-1 Initial Dry Density (pcf) 116.5
Sample No. 2R Moisture Content (%):
Depth (feet) 10.0 Before 17.3
Soil Type CL After 15.1
Soil Description Dk Brn Sandy Clay

DRAFT

CONSOLIDATION CURVE

Project No. 10839-211-004
Project Name Rockwell
Date 10/29/96 Figure No.




LEGEND: ○ At Field Moisture
● After Addition of Water

Boring No. B-3 Initial Dry Density (pcf) 108.8
Sample No. 3R Moisture Content (%):
Depth (feet) 10.0 Before 20.6
Soil Type CL After 21.3
Soil Description Dk Brn Sandy Clay

DRAFT

CONSOLIDATION CURVE
ASTM D 2435

Project No. 10839-211-004
Project Name Rockwell
Date 11/13/96 Figure No.



LEGEND:


- At Field Moisture
● After Addition of Water

Boring No. B-3 Initial Dry Density (pcf) 108.8
Sample No. 3R Moisture Content (%):
Depth (feet) 10.0 Before 20.6
Soil Type CL After 21.3
Soil Description Dk Brn Sandy Clay

DRAFT

CONSOLIDATION CURVE
ASTM D 2435

Project No. 10839-211-004
Project Name Rockwell
Date 11/13/96 Figure No.



LEGEND:


- At Field Moisture
● After Addition of Water

Boring No. B-3 Initial Dry Density (pcf) 108.8
Sample No. 3R Moisture Content (%):
Depth (feet) 10.0 Before 20.6
Soil Type CL After 21.3
Soil Description Dk Brn Sandy Clay

DRAFT

CONSOLIDATION CURVE
ASTM D 2435

Project No. 10839-211-004
Project Name Rockwell
Date 11/13/96 Figure No.



LEGEND:


- At Field Moisture
- After Addition of Water

Boring No.	B-3	Initial Dry Density (pcf)	108.8
Sample No.	3R	Moisture Content (%):	
Depth (feet)	10.0	Before	20.6
Soil Type	CL	After	21.3
Soil Description	Dk Brn Sandy Clay		

DRAFT

CONSOLIDATION CURVE
ASTM D 2435

Project No. 10839-211-004
Project Name Rockwell
Date 11/13/96 Figure No.



LEGEND:


- At Field Moisture
● After Addition of Water

Boring No. B-5 Initial Dry Density (pcf) 105.6
Sample No. 3 Moisture Content (%):
Depth (feet) 12.5 Before 19.5
Soil Type CL After 20.8
Soil Description Dk Brn Sandy Clay

DRAFT

CONSOLIDATION CURVE

Project No. 10839-211-004
Project Name Rockwell
Date 10/29/96 Figure No.



LEGEND:

- At Field Moisture
- After Addition of Water

Boring No. B-5 Initial Dry Density (pcf) 105.6

Sample No. 3 Moisture Content (%):

Depth (feet) 12.5 Before 19.5

Soil Type CL After 20.8

Soil Description Dk Brn Sandy Clay


DRAFT

CONSOLIDATION CURVE

Project No. 10839-211-004

Project Name Rockwell

Date 10/29/96 Figure No.



LEGEND: ○ At Field Moisture
 ● After Addition of Water

Boring No.	B-11	Initial Dry Density (pcf)	100.1
Sample No.	5R	Moisture Content (%):	
Depth (feet)	15.0	Before	18.2
Soil Type	CL	After	24.4
Soil Description	Sandy Clay		


DRAFT

CONSOLIDATION CURVE

Project No. 10839-211-004

Project Name Rockwell

Date 10/29/96 Figure No.



LEGEND: ○ At Field Moisture
● After Addition of Water

Boring No.	B-11	Initial Dry Density (pcf)	100.1
Sample No.	5R	Moisture Content (%):	
Depth (feet)	15.0	Before	18.2
Soil Type	CL	After	24.4
Soil Description	Sandy Clay		


DRAFT

CONSOLIDATION CURVE

Project No. 10839-211-004

Project Name Rockwell

Date 10/29/96 Figure No.




BORING : B-18 #7
DEPTH (ft) : 40 Ft
ASSUMED Gs : 2.70


DESCRIPTION : SILTY CLAY (CL)
LIQUID LIMIT :
PLASTIC LIMIT :


	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	44.7	77.2	97	1.339
FINAL	43.6	79.8	100	1.261


DRAFT



DRAFT







BORING : B-20 / #3
DEPTH (ft) : 20'
SPEC. GRAVITY : 2.73

DESCRIPTION : DARK GRAY CLAY
LIQUID LIMIT :
PLASTIC LIMIT :

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	18.6	108.8	90	.568
FINAL	20.4	109.4	100	.559

DRAFT


Remark :

10839-218-004

ROCKWELL

Dames & Moore

CONSOLIDATION TEST



BORING : B-20 / #3
DEPTH (ft) : 20'
SPEC. GRAVITY : 2.73

DESCRIPTION : DARK GRAY CLAY
LIQUID LIMIT :
PLASTIC LIMIT :

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	18.6	108.8	90	.568
FINAL	20.4	109.4	100	.559

DRAFT


Remark :

10839-218-004


ROCKWELL

Dames & Moore


CONSOLIDATION TEST




DRAFT




DRAFT



DRAFT




DRAFT




10839-21B-004	ROCKWELL NEWPORT BEACH
DAMES & MOORE	CONSOLIDATION TEST

DRAFT



10839-21B-004	ROCKWELL NEWPORT BEACH
DAMES & MOORE	CONSOLIDATION TEST



BORING : B-23 / #5 DESCRIPTION : OLIVE SILTY CLAY (CL)
DEPTH (ft) : 30' LIQUID LIMIT :
SPEC. GRAVITY : 2.70 PLASTIC LIMIT :

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	30.2	90.0	93	.874
FINAL	28.2	94.4	97	.786

DRAFT


Remark :

10839-218-004

ROCKWELL

Dames & Moore

CONSOLIDATION TEST



BORING : B-23 / #5 DESCRIPTION : OLIVE SILTY CLAY (CL)
DEPTH (ft) : 30' LIQUID LIMIT :
SPEC. GRAVITY : 2.70 PLASTIC LIMIT :

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	30.2	90.0	93	.874
FINAL	28.2	94.4	97	.786

DRAFT


Remark :

10839-218-004

ROCKWELL

Dames & Moore

CONSOLIDATION TEST



BORING : B-24 / #4 DESCRIPTION : LIGHT BROWN CLAYEY SAND (SC)
DEPTH (ft) : 25' LIQUID LIMIT :
SPEC. GRAVITY : 3.00 PLASTIC LIMIT :

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	24.2	98.4	81	.905
FINAL	28.4	101.1	100	.854

DRAFT


Remark :

10839-218-004

ROCKWELL

Dames & Moore

CONSOLIDATION TEST



BORING : B-24 / #4 DESCRIPTION : LIGHT BROWN CLAYEY SAND (SC)
DEPTH (ft) : 25' LIQUID LIMIT :
SPEC. GRAVITY : 3.00 PLASTIC LIMIT :

	MOISTURE CONTENT (%)	DRY DENSITY (pcf)	PERCENT SATURATION	VOID RATIO
INITIAL	24.2	98.4	81	.905
FINAL	28.4	101.1	100	.854

DRAFT


Remark :


10839-218-004

ROCKWELL

Dames & Moore

CONSOLIDATION TEST





APPENDIX A

**PREVIOUS LOG OF BORING
(Dames & Moore 1995 Investigation)**

S:\RCKBASE.503

APPENDIX A

**PREVIOUS LOG OF BORING
(Dames & Moore 1995 Investigation)**

S:\RCKBASE.503


LABORATORY TEST DATA										BORING B-1		
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA				MOISTURE CONTENT (%)	DRY DENSITY (PCF)	BLOWS/FOOT	SYMBOL	DESCRIPTION
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)					
0								24	102	3	CL	Dark brown silty fine sandy CLAY with trace organics (soft) [Fill]
5								29		24	CL	Brown to olive-gray and dark gray silty CLAY (very stiff)
10	-200 (39)							23		11	SM	Brown and dark brown silty fine SAND (loose)
15								31		17	CL	Brown and olive-gray silty CLAY, mottled (stiff to very stiff)
20								23	103	17		Grades brownish-gray with trace fine sand
25	-200 (22)							20		42		Grades with alternating gray silty fine sand and silty clay lenses
30								32	92	19	SP SM	Grades olive gray (medium stiff)
35	-200 (6)							22		39	CL	Gray fine to medium SAND with silt and shells (dense)
40								39				Brownish-gray with reddish-brown silty CLAY (medium stiff)
45								32	91	14		Grades to gray silty clay with trace shell fragments
50	-200 (32)							21		94	SC	Gray fine to medium clayey SAND (very dense)
55								28	97	35		Grades with more clay and shells, less sand (medium dense)
60												

Boring completed to a depth of 51-1/2 feet on March 7, 1995.
Boring backfilled with cement/bentonite slurry upon completion.

LOG OF BORING
PROPOSED SEISMIC RETROFIT
BUILDINGS 503 & 505
 For Rockwell International

Dames & Moore
 PLATE 11

**LOG OF BORING
PROPOSED SEISMIC RETROFIT
BUILDINGS 503 & 505
For Rockwell International**



BORING B-2

LABORATORY TEST DATA										
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0	-200 (71)								21	
5	-200 (54)								16	117
10	-200 (58)								16	
15	-200 (74)								21	107
20	-200 (38)								21	
25									26	100
30	-200 (9)								16	
35	-200 (3)								21	106
40									45	
45									45	79
50									38	
55										
60										

BLOMS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
CL	5-inch thick concrete slab on 5-inch thick base Brown to dark brown and reddish-brown silty fine sandy CLAY (medium stiff to stiff) [Fill]
CL	Grades with AC fragments
CL	Brown to dark brown fine sandy silty CLAY (stiff to very stiff)
	Grades with some gravel and trace organics
	Grades to include light brown sand and clayey sand lenses
SP SM	Gray fine to coarse SAND with silt(very dense)
	Grades with less silt (dense)
CL	Olive-gray to gray silty CLAY with trace shell fragments

Boring completed to a depth of 51-1/2 feet on
March 7, 1995
Boring backfilled with cement/bentonite slurry upon completion.

LOG OF BORING

PROPOSED SEISMIC RETROFIT

BUILDINGS 503 & 505

For Rockwell International

Dames & Moore
PLATE 12

BORING B-2

LABORATORY TEST DATA									
DEPTH IN FEET	ATTERBERG LIMITS		STRENGTH TEST DATA				MOISTURE CONTENT (%)	DRY DENSITY (PCF)	BLOMS/FOOT SAMPLE TYPE
	TESTS REPORTED ELSEWHERE	LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)		
0	-200 (71)							21	8
5	-200 (54)							16	9
10	-200 (58)							16	19
15	-200 (74)							21	19
20	-200 (38)							21	25
25								26	20
30	-200 (9)							16	87
35	-200 (3)							21	57
40								45	16
45								45	10
50								38	17
55									
60									

SYMBOL	DESCRIPTION
CL	5-inch thick concrete slab on 5-inch thick base Brown to dark brown and reddish-brown silty fine sandy CLAY (medium stiff to stiff) [Fill]
CL	Grades with AC fragments Brown to dark brown fine sandy silty CLAY (stiff to very stiff)
	Grades with some gravel and trace organics
	Grades to include light brown sand and clayey sand lenses
SP SM	Gray fine to coarse SAND with silt(very dense)
	Grades with less silt (dense)
CL	Olive-gray to gray silty CLAY with trace shell fragments

Boring completed to a depth of 51-1/2 feet on March 7, 1995
Boring backfilled with cement/bentonite slurry upon completion.

LOG OF BORING

PROPOSED SEISMIC RETROFIT

BUILDINGS 503 & 505

For Rockwell International

Dames & Moore
PLATE 12

APPENDIX B


**PREVIOUS LOG OF BORING
(Dames & Moore 1996 Investigation)**


S:\RCKBASE.503

APPENDIX B

**PREVIOUS LOG OF BORING
(Dames & Moore 1996 Investigation)**

S:\RCKBASE.503






LABORATORY TEST DATA

LABORATORY TEST DATA									
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA				MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)		
0								19	
5				UC		1000		21	101
10	SL -200 (42)			UC		2500		13	124
15	CORR -200 (6)	47	27					14	
20	CORR -200 (82)							6	99
25								8	
30	-200 (31)							26	95
35	-200 (39)							23	
40	-200 (94)							22	102
45	-200 (9)							31	
50								11	91
55								13	
60	-200 (5)							14	92
65								4	

BLOWS/FOOT
SAMPLE TYPE



BORING B-1

LOG OF BORING

PROPOSED ADDITION

BUILDING 503

For Rockwell International

Dames & Moore

Plate 4

Boring completed to a depth of 60 1/2 feet on
March 26, 1996.
Boring grouted upon completion with
cement-bentonite slurry and resurfaced.

LABORATORY TEST DATA

LABORATORY TEST DATA									
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA				MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)		
0								19	
5				UC		1000		21	101
10	SL -200 (42)			UC		2500		13	124
15	CORR -200 (6)	47	27					14	
20	CORR -200 (82)							6	99
25								8	
30	-200 (31)							26	95
35	-200 (39)							23	
40	-200 (94)							22	102
45	-200 (9)							31	
50								11	91
55								13	
60	-200 (5)							14	92
65								4	

BLOWS/FOOT
SAMPLE TYPE

SYMBOL	DESCRIPTION
SM	4-inches asphaltic concrete
CL	Brownish yellow silty gravelly fine SAND (Fill)
CL	Brown fine to medium sandy silty CLAY (Stiff to very stiff) (Fill)
SM	Grades gray
SM	Grades yellowish red
CL	Dark gray silty clayey fine to coarse SAND (Medium dense) (Fill)
CL	Yellowish red silty fine to coarse sandy CLAY (Stiff)
SM	Grades with less medium to coarse sand
SP	Yellowish red to brownish yellow fine to medium SAND with silt (Dense)
CL	Grades with sandy clay lenses
SM	Yellowish red silty CLAY (Very stiff)
CL	Brown to olive gray silty fine SAND (Dense)
CL	Greenish gray silty CLAY (Very stiff)
SM	Gray silty fine SAND (Dense)
ML	Gray and brownish yellow clayey fine sandy SILT (Hard)
SM	Grades with more clay
SM	Gray fine SAND with silt (Very dense)
SM	Grades with medium to coarse sand

Boring completed to a depth of 60 1/2 feet on
March 26, 1996.
Boring grouted upon completion with
cement-bentonite slurry and resurfaced.

LOG OF BORING

PROPOSED ADDITION

BUILDING 503

For Rockwell International

Dames & Moore

Plate 4

BORING B-2

LABORATORY TEST DATA									
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA				MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)		
0								22	
5	CORR SL (75)			UC		1770		20	111
10		37	21	UC		7240		17	118
15	CORR							17	
20	CON			UC		6125		21	110
25	-200 (66) CON							15	
								12	120
30								33	91
35								37	
40								35	89
45	-200 (26)							29	
50								24	
55									
60									
65									
70									

BLOWS/FOOT

SYMBOL	DESCRIPTION
CL	4 inches asphaltic concrete
CL	6 inches Brown fine sandy silty fine to coarse GRAVEL (Base)
	Brown, dark brown, and dark gray fine sandy silty CLAY (Very stiff) [FII] Grades with silty sand lenses and trace organics
CL	Brown to yellowish red fine to coarse sandy silty CLAY (Hard)
	Grades brown
CL	Brownish yellow silty fine to medium sandy CLAY (Hard) Grades light brown and light gray with coarse sand
CL	Greenish gray and brownish yellow silty CLAY with occasional sand lense (Hard)
SM	Gray silty fine SAND with shells (Very dense)

Boring completed to a depth of 51 1/2 feet on March 26, 1996.
Boring backfilled upon completion with cement-bentonite slurry and resurfaced.

LOG OF BORING

PROPOSED ADDITION

BUILDING 503

For Rockwell International

Dames & Moore

Plate 5

BORING B-2

LABORATORY TEST DATA										
DEPTH IN FEET	TESTS REPORTED ELSEWHERE	ATTERBERG LIMITS		STRENGTH TEST DATA					MOISTURE CONTENT (%)	DRY DENSITY (PCF)
		LIQUID LIMIT (%)	PLASTICITY INDEX (%)	TYPE OF TEST	NORMAL OR CONFINING PRESSURE (PSF)	SHEAR STRENGTH (PSF)	DEVIATOR STRESS (PSF)			
0									22	
5	CORR SL (75)			UC		1770			20	111
10		37	21	UC		7240			17	118
15	CORR								17	
20	CON			UC		6125			21	110
25	-200 (66) CON								15	
									12	120
30									33	91
35									37	
40									35	89
45	-200 (26)								29	
50									24	
55										
60										
65										
70										

BLOWS/FOOT

SYMBOL	DESCRIPTION
CL	4 inches asphaltic concrete
CL	6 inches Brown fine sandy silty fine to coarse GRAVEL (Base)
	Brown, dark brown, and dark gray fine sandy silty CLAY (Very stiff) [Fill] Grades with silty sand lenses and trace organics
CL	Brown to yellowish red fine to coarse sandy silty CLAY (Hard)
	Grades brown
CL	Brownish yellow silty fine to medium sandy CLAY (Hard) Grades light brown and light gray with coarse sand
CL	Greenish gray and brownish yellow silty CLAY with occasional sand lense (Hard)
SM	Gray silty fine SAND with shells (Very dense)

Boring completed to a depth of 51 1/2 feet on March 26, 1996.
Boring backfilled upon completion with cement-bentonite slurry and resurfaced.

LOG OF BORING

PROPOSED ADDITION

BUILDING 503

For Rockwell International

Dames & Moore

Plate 5

KEY TO LOG OF BORINGS

SAMPLE TYPES	LABORATORY TESTS	
<div>45</div> <div><div><div>—</div><div>■</div><div>☒</div><div>☑</div></div><div>HAMMER BLOWS PER FOOT OF PENETRATION</div><div>INDICATES DAMES & MOORE UNDISTURBED SAMPLE</div><div>INDICATES DISTURBED OR BULK SAMPLE</div><div>INDICATES A STANDARD PENETRATION TEST</div><div>DAMES & MOORE AND SPT SAMPLERS DRIVEN USING A 140-POUND HAMMER DROPPING 30-INCHES</div></div>	UC CORR -200 CON SL EI	UNCONFINED COMPRESSION TEST CORROSIIVITY TEST PERCENT PASSING THE NO.200 SIEVE (Test Results in Parentheses) CONSOLIDATION TEST SWELL LOAD TEST EXPANSION INDEX (Test Result in Parentheses)
<div>PROPOSED ADDITION BUILDING 503 For Rockwell International</div> <div>Dames & Moore Plate 6 - Continued</div>		

KEY TO LOG OF BORINGS

SAMPLE TYPES	LABORATORY TESTS	
<div>45</div> <div><div><div>—</div><div>■</div><div>☒</div><div>☑</div></div><div>HAMMER BLOWS PER FOOT OF PENETRATION</div><div>INDICATES DAMES & MOORE UNDISTURBED SAMPLE</div><div>INDICATES DISTURBED OR BULK SAMPLE</div><div>INDICATES A STANDARD PENETRATION TEST</div><div>DAMES & MOORE AND SPT SAMPLERS DRIVEN USING A 140-POUND HAMMER DROPPING 30-INCHES</div></div>	<div>UC</div> <div>CORR</div> <div>-200</div> <div>CON</div> <div>SL</div> <div>EI</div>	<div>UNCONFINED COMPRESSION TEST</div> <div>CORROSIVITY TEST</div> <div>PERCENT PASSING THE NO.200 SIEVE (Test Results in Parentheses)</div> <div>CONSOLIDATION TEST</div> <div>SWELL LOAD TEST</div> <div>EXPANSION INDEX (Test Result in Parentheses)</div>
<div>PROPOSED ADDITION</div> <div>BUILDING 503</div> <div>For Rockwell International</div> <div>Dames & Moore</div> <div>Plate 6 - Continued</div>		

APPENDIX C

**PREVIOUS LOG OF BORINGS
(MHLA 1967 Investigation)**

S:\RCKBASE.503

APPENDIX C

**PREVIOUS LOG OF BORINGS
(MHLA 1967 Investigation)**

ELEV. OF SURFACE: 45.1

DEPTH IN FEET		SAMPLES	DIA. OF CORE	DESCRIPTION OF SOILS				COHESION OR SHEAR RES. O KIPS PER SQUARE FOOT											
				Color	Moisture	Consistency	Unit lb Dry Weight per cu. ft.	MOISTURE - PERCENT DRY WT											
								4	10	20	30	40	50	60	70	80	90	100	Saturated Unit Weight (G) / (C) / (A) drained
				CLAY, silty, (15-20-65)39 (plastic) (16-22-62)40	dark brown			mod. stiff	102										
-5-				SILT, clayey (stiff plastic) very clayey calcareous concretions	light brown			firm	94										
-10-				(stiff plastic)					110										
-15-				calcareous concretions	gray & brown				95										
-20-				SAND, fine, very silty	gray			comp	98										
-25-				SAND, fine, clean	light gray				95										
-30-				abundant cholla	gray blue				107										
-35-				CLAY, very silty, scattered shells (stiff plastic)	gray gray & brown			stiff	89										
-40-				End of Boring @ 40'					95										
				(15-20-65)39 Indicates - 15% Sand 20% Silt 65% Clay 39% Colloids															

79- Ground Water Surface encountered during drilling

Collins Radio Company - Newport Beach, California

PLATE NO. R-3

WALTERS HOME LOCKWOOD & ASSOC.

FILE NO. 5-47-5-1

056-7005-131

ELEV. OF SURFACE: 45.1

DATE DRILLED: 2/28/67

EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 45.1

DEPTH IN FEET		SAMPLES	DESCRIPTION OF SOILS					COHESION OR SHEAR RES. IN P.S.F.			
			Color	Moisture	Consistency	Unit Weight	MOISTURE PERCENT	DRY WEIGHT	WET WEIGHT		
0-5	2	1	CLAY, silty (15-20-65)39 (plastic)	dark brown	mod. stiff	102	10	20	4		
5-10	5	2	SILT, clayey (stiff plastic)	brown	firm	106	10	20	4		
10-15	13	3	very clayey calcareous concretions	light brown		94	10	20	4		
15-20	17	4	(stiff plastic)			110	10	20	4		
20-25	9	5	calcareous concretions	gray & brown		95	10	20	4		
25-30	15	6	SAND, fine, very silty	gray	comp	98	10	20	4		
30-35	30	7	SAND, fine, clean	light gray		95	10	20	4		
35-40	35	8	abundant cholla	gray & blue		107	10	20	4		
40-45	13	9	CLAY, very silty, scattered shells (stiff plastic)	gray & brown	stiff	89	10	20	4		
45-50	19	10	End of Boring @ 40'			95	10	20	4		
50-55			(15-20-65)39 indicates - 15% Sand 20% Silt 65% Clay 39% Colloids								

---)S- Ground Water Surface encountered during drilling;

Collins Radio Company - Newport Beach, California

PLATE NO. R-3

WALTER H. HENRY LOCKWOOD & ASSOC.

FILE NO. 47-5-1

056-7005-131

LOG OF BORING NO 504

DATE DRILLED: 2/28/67

DATE DRILLED: _____ **Bucket Auger:** _____
EQUIPMENT USED: _____

ELEV. OF SURFACE: 40.3

EQUIPMENT USED: Bucket Auger		DESCRIPTION OF SOILS				COHESION OR SHEAR RES. O KIPS PER SQUARE FOOT	
Depth in Feet	Samples	Blows Per Foot	CLASSIFICATION	Consistency		Unit Dry Weight lb. per cu. ft.	MOISTURE PERCENT DRY / WT
				Color	Moisture		
2			SAND, fine, silty	dark brown	mod. loose	115	
13			CLAY, silty, (plastic)	brown	mod. stiff	114	
15			(stiff plastic)	brown to light brown	stiff	104	
19						117	
10							
15			silt nodules	gray	GWS (2)	108	
20			scattered shells	gray	GWS (1) comp	106	
25			SILT, sandy SAND, fine, silty fine to coarse, clean	blue gray		108	
30			CLAY, silty (stiff plastic)	gray brown	stiff	92	
35			scattered shells	dark gray		83	
40			End of Boring @ 40'			77	

(1) GWS ... encountered (2) after 16 hours

Collins Radio Company - Newport Beach, California

MAURETH; HOWE LOCKWOOD & ASSOC.

PLATE NO. B-4

FILE NO. 3347-F

101-5004-756 TCCP-19

LOG OF BORING NO 504

DATE DRILLED: 2/28/67

DATE DRILLED:
EQUIPMENT USED:
Bucket Auger:

FLYEV. OF SURFACE: +0.3

EQUIPMENT USED: Bucket Auger		DESCRIPTION OF SOILS				COHESION OR SHEAR RES. O KIPS PER SQUARE FOOT	
Depth in Feet	Blows Per Foot	CLASSIFICATION	Color	Moisture	Consistency	Unit Dry Weight lb. per cu. ft.	MOISTURE PERCENT DRY / WET
							20 30 40 50
2	2	SAND, fine, silty	dark brown	mod. loose		115	
5	13	CLAY, silty, (plastic)	brown	mod. stiff		114	
10	15	(stiff plastic)	brown to light brown	stiff		104	
15	19					117	
20	3	silt nodules	gray	GWS(2)		108	
25	3	scattered shells	blue	GWS(1) comp		108	
30	20	CLAY, silty (stiff plastic)	gray brown	stiff		92	
35	19	scattered shells	dark gray			83	
40	17	End of Boring @ 40'				77	

(1) GWS ... encountered (2) after 16 hours

Collins Radio Company - Newport Beach, California

MAUNZET; MO./E LOCKWOOD & ASSOC.

PLATE NO. B-4

FILE NO. 3347-F

101-5004-750 TCCP-19

LOG OF BORING NO 505

DATE DRILLED: 2/20/67

EQUIPMENT USED: Bucke Auger

ELEV. OF SURFACE: 37.6

DESCRIPTION OF SOILS										COHESION & OR SHEAR RES. IN KIPS PER SQUARE FOOT									
Depth in Foot		Samples Per Foot		CLASSIFICATION	Color	Moisture	Consistency	Unit Dry Weight lb. per cu. ft.	GWS #	MOISTURE - PERCENT DRY / WET									
										Saturated & drained					Saturated & undrained				
				CLAY, silty (plastic)	dark brown	mod. moist	stiff	114		20	25	30	35	40	45				
				(stiff plastic)	brown		stiff	114		20	25	30	35	40	45				
	-5-				gray			116		20	25	30	35	40	45				
	-10-				brown			109		20	25	30	35	40	45				
				SILT, clayey	tan & white														
	-15-			(stiff plastic)	gray &		firm	102		20	25	30	35	40	45				
				CLAY, sandy	brown		stiff	108		20	25	30	35	40	45				
	-20-			SAND, fine, silty	gray		comp												
					gray		firm	89		20	25	30	35	40	45				
	-25-			SILT	green		stiff	86		20	25	30	35	40	45				
				(stiff plastic)															
	-30-			very clayey	brown			89		20	25	30	35	40	45				
				(stiff plastic)															
	-35-																		
				SAND, fine, clean	gray		comp	108		20	25	30	35	40	45				
	-40-			End of Boring @ 40'															

* GWS - at completion. -ing

Collins Radio Company - Newport Beach, California

PLATE NO. B-5

MARSHALL HOWE LOGWOOD & ASSOC.

FILE NO. 3347-E-

101-5004-750 T.L. P-20

LOG OF BORING NO 505

DATE DRILLED: 2/20/67

DATE DRILLED: 2/20/01
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 37.6

DEPTH IN FOOT		SAMPLES PER LOG		DESCRIPTION OF SOILS					COHESION & OR SHEAR RES. IN KIPS PER SQUARE FOOT								
				CLASSIFICATION	Color	Moisture	Consistency	Unit Dry Weight lb. per cu. ft.	MOISTURE - PERCENT DRY / WET								
									mod. moist	stiff	114	114	116	109	102	108	89
2		2		CLAY, silty (plastic)	dark brown												
8		8		(stiff plastic)	brown												
19		19			gray												
19		19			brown												
13		13		SILT, clayey	tan & white												
15		15		(stiff plastic)	gray & brown												
20		20		CLAY, sandy	gray												
25		25		SAND, fine, silty	gray												
25		25			green												
30		30		SILT (stiff plastic)	gray												
30		30		very clayey	green												
35		35		(stiff plastic)	brown												
35		35															
40		40		SAND, fine, clean	gray												
40		40		End of Boring @ 40'													

* GWS - at completion. ...ing

Collins Radio Company - Newport Beach, California

PLATE NO. B-5

MAURSETT HOWE LOCKWOOD & ASSOC.

FILE NO. 3347-E-

101-5004-750 T.L. P-20

LOG OF BORING NO 507

DATE DRILLED: 3/1/67
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 44.9

Depth in Feet	Ditch for 1001	DESCRIPTION OF SOILS				Unit Weight lb. per cu. ft.	COHESION OR SHEAR RES. KIPS PER SQUARE FOOT
		Color	Moisture	Consistency	Moisture		
		CLASSIFICATION	dark moist	mod. soft	107		
		CLAY, silty (sec. plastic)	brown	mod. stiff	103		
		(plastic)			94		
		SILT, sandy		firm	104		
		SAND, fine, silty		comp	103		
		SILT CLAY, silty		firm stiff	98		
		SAND, fine, clean		comp	111		
		very silty			96		
		CLAY, silty (stiff plastic)	gray blue				
		SAND, fine, silty clean					
		End of Boring @ 30'					

*GWS - at completion of boring

Collins Radio Company - Newport Beach, California

MAURSETH HOVE LOCKWOOD & ASSOCIATES

PLATE NO. 3-7

FILE NO. 3347-F 1

101-5604-7507 ✓ p-21

LOG OF BORING NO 507

DATE DRILLED: 3/1/67
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 44.9

Depth in Feet	Ditch for 1001	DESCRIPTION OF SOILS				Unit Weight lb. per cu. ft.	COHESION OR SHEAR RES. O KIPS PER SQUARE FOOT				MOISTURE PERCENT DRY/WET			
		CLASSIFICATION	Color	Moisture	Consistency									
2		CLAY, silty (sec. plastic)	dark moist brown		mod. soft	107								
3						103								
5		(plastic)			mod. stiff	94								
9		SILT, sandy			firm	104								
10														
17		SAND, fine, silty			comp	103								
15														
17		SILT CLAY, silty			firm stiff	98								
20		SAND, fine, clean			comp									
20		very silty												
25		CLAY, silty (stiff plastic)			stiff	111								
25		SAND, fine, silty clean	gray blue		comp	96								
30		End of Boring @ 30'												

*GWS - at completion of boring

Collins Radio Company - Newport Beach, California

MAURSETH HOVE LOCKWOOD & ASSOCIATES

PLATE NO. 3-7

FILE NO. 3347-F 1

101-5604-7507 ✓ p-21

LOG OF BORING NO 506

DATE DRILLED: 3/1/67
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 45.5

DEPTH IN FEET			SAMPLES	DESCRIPTION OF SOILS				Unit lb. Dry Weight per cu. ft.	COHESION OR SHEAR RES. C KIPS PER SQUARE FOOT	MOISTURE PERCENT DRY / WET
				Color	Moisture	Consistency				
CLASSIFICATION										
			CLAY, silty (soft plastic)	dark moist	mod. soft	106				
		12	SAND, fine, clayey	brown	comp	112				
-5			SILT, sandy		firm	92				
		3	SAND, fine, silty		comp	101				
-10		11	CLAY, silty	light brown	stiff					
			calcareous concretions		firm	95				
-15		6	CLAY, silty (stiff plastic)	gray & brown	stiff	104				
-20		11	SAND, fine, silty	gray	comp	107				
			SILT, sandy		firm					
-25		11	CLAY, silty		comp	98				
			SILT, sandy coarse, fine clean		comp					
-30		45								
			End of Boring @ 30'							

*GWS - at completion of Boring

Collins Radio Company - Newport Beach, California

MAURSETH HOVE LOCKWOOD & ASSOC.

PLATE NO. B-6

FILE NO. 5347. E.

101-5004-750 T p-21

LOG OF BORING NO 506

DATE DRILLED: 3/1/67
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 45.5

DEPTH IN FEET			SAMPLES	DESCRIPTION OF SOILS				Unit lb. Dry Weight per cu. ft.	COHESION OR SHEAR RES. C KIPS PER SQUARE FOOT	MOISTURE PERCENT DRY / WET
				Color	Moisture	Consistency				
CLASSIFICATION										
			CLAY, silty (soft plastic)	dark moist	mod. soft	106				
		12								
		20	SAND, fine, clayey	brown	comp	112				
	-5-									
		3	SILT, sandy		firm	92				
		11	SAND, fine, silty		comp	101				
	-10-									
			CLAY, silty	light	stiff					
			calcareous concretions	brown						
	-15-	6		brown	firm	95				
			CLAY, silty (stiff plastic)	gray & brown	stiff	104				
	-20-	11								
			SAND, fine, silty	gray	comp	107				
	-25-	11	SILT, sandy		firm					
			CLAY, silty							
			SILT, sandy							
			SAND, fine, coarse, clean							
	-30-	45			comp	98				
			End of Boring @ 30'							

*GWS - at completion of Boring

Collins Radio Company - Newport Beach, California

MAURSETH HOVE LOCKWOOD & ASSOC.

PLATE NO. B-6

FILE NO. 5347. F.

101-5004-750 T p-21

LOG OF BORING NO 508

DATE DRILLED: 2/28/67
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 46.3

DEPTH IN FEET			SCISSORS			Days for Test			DESCRIPTION OF SOILS				COHESION OR SHEAR RES. 0 KIPS PER SQUARE FOOT				MOISTURE PERCENT DRY UNIT			
Color			Moisture			Consistency			Unit lb. Dry Weight per cu. ft.			Scattered & drained				4 10 20 30 40				
CLASSIFICATION																				
CLAY, silty (plastic)			dark moist			Ingr. stiff			103											
calcareous concretions & brown						stiff			100											
-5 (stiff plastic)			brown																	
SAND, silty			light			comp			105											
			brown						95											
CLAY, silty			brown			stiff			107											
-15 (stiff plastic)			& tan																	
SILT, clayey			tan			firm			105											
-20 CLAY, silty			brown			stiff			108											
SAND, fine, clean			brown & tan			comp														
-25 SILT			gray & brown			firm			99											
SAND, fine, silty			brown			comp														
-30 SAND, med. to coarse			tan			GWS			91											
CLAY, silty			gray			stiff			91											
-35 (stiff plastic)																				
scattered shells									91											
-40									92											
End of Boring @ 40'																				

*GWS - at completion of boring

Collins Radio Company - Newport Beach, California

PLATE NO. B-8

MAURSETN HOWE LOCKWOOD & ASSOC.

FILE NO. 334-1-1

101-5004-750 ✓ p 23

LOG OF BORING NO 508

DATE DRILLED: 2/28/67
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 46.3

Depth in Feet	Scissors	Days for Test	DESCRIPTION OF SOILS				Unit lb. Dry Weight per cu. ft.	COHESION OR SHEAR RES. 0 KIPS PER SQUARE FOOT
			Color	Moisture	Consistency	Remarks		
			CLASSIFICATION					
			CLAY, silty (plastic)	dark moist brown	stiff		103	Scattered
		11	calcareous concretions & (stiff plastic)	brown	stiff		100	drained
-5		15						
		13	SAND, silty	light brown	comp		105	
-10		12					95	
			CLAY, silty (stiff plastic)	brown & tan	stiff		107	
-15		9						
			SILT, clayey	tan	firm		105	
-20		15	CLAY, silty	brown	stiff		108	
			SAND, fine, clean	tan	comp			
-25		13					99	
			SILT	gray & brown	firm			
		8	SAND, fine, silty	brown	comp			
-30		3	SAND, med. to coarse	tan	stiff		91	
			CLAY, silty (stiff plastic)	gray				
-35		19	scattered shells				91	
-40		9					92	
			End of Boring @ 40'					

*GWS - at completion of boring

Collins Radio Company - Newport Beach, California

PLATE NO. B-8

MAURSETN HOWE LOCKWOOD & ASSOC.

FILE NO. 3341-1

101-5004-750 ✓ p 23

LOG OF BORING NO 509

DATE DRILLED: Feb. 20, 1967
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 48.0

Depth in feet	CLASSIFICATION	Color	Moisture	Consistency	Unit lb. per cu. ft.	COHESION OR SHEAR RES. KIPS PER SQUARE FOOT	MOISTURE PERCENT DRY WEIGHT
2	CLAY, silty (soft plastic)	brown	mod. moist	mod. soft	104		
3	SILT, clayey (plastic)	brown & tan	mod. firm	mod. firm	93		
5	(stiff plastic)		firm	firm	99		
13	SAND, fine, very silty	tan	Comp.	Comp.	100		
15	SILT, clayey (stiff plastic)	Brown to tan	firm	firm	96		
20					94		
25	SAND, fine, silty	tan	comp.	comp.	100		
30	SILT, sandy	gray	light seep	stiff	97		
35	very clayey (stiff plastic)	gray brown	* GWS		91		
40	End of boring @ 40'				86		

*GWS - after 16 hours

COLLINS RADIO CORP. NEWPORT BEACH

MAURETHI MOVE LOCKWOOD & ASSOC.

PLATE NO. B-9

FILE NO. 3247

101-5004-750 P-28

LOG OF BORING NO 509

DATE DRILLED: Feb. 20, 1967
EQUIPMENT USED: Bucket Auger

ELEV. OF SURFACE: 48.0

Depth in feet	CLASSIFICATION	Color	Moisture	Consistency	Unit Weight lb. per cu. ft.	COHESION OR SHEAR RES. C KIPS PER SQUARE FOOT	MOISTURE PERCENT DRY WEIGHT
2	CLAY, silty (soft plastic)	brown	mod. moist	mod. soft	104		
3	SILT, clayey (plastic)	brown & tan	mod. firm	mod. firm	93		
5	(stiff plastic)		firm	firm	99		
13	SAND, fine, very silty	tan	Comp.		100		
15	SILT, clayey (stiff plastic)	Brown to tan	firm		96		
20					94		
25	SAND, fine, silty	tan	comp.		100		
30	SILT, sandy	gray	light seep		97		
35	very clayey (stiff plastic)	gray brown	* GWS	stiff	91		
40	End of boring @ 40'				86		

*GWS - after 16 hours

COLLINS RADIO CORP. NEWPORT BEACH

MAURETH MOVE LOCKWOOD & ASSOC.

PLATE NO. B-9

FILE NO. 3247

101-5004-750 P-28

LOE OF BORING NO 510

DATE DRILLED: Feb. 20, 1967
EQUIPMENT USED: Bucsek Auger

FLY. OF SURFACE: 46.3

EQUIPMENT USED: BURET AUGER										DESCRIPTION OF SOILS										COHESION OR SHEAR RES. KIPS PER SQUARE FOOT									
Depth in Feet		Samples		Days for Test		CLASSIFICATION		Color		Moisture		Consistency		Unit Dry Weight lb. per cu. ft.		MOISTURE-PERCENT DRY/WET													
																1 2 3 4 20 30 40 50													
																drained													
						CLAY, silty; piece of wood		medd moist mod		100																			
						sand lenses (soft plastic)		soft		102																			
						CLAY, silty (stiff plastic)		brown to light		107																			
						sandy with depth		brown		109																			
								EWS(2)		119																			
						SAND, fine, clayey, silty		light brown		comp		119																	
						CLAY, silty		brown		stiff		109																	
						SAND, fine, silty, slightly clayey		gray		comp		109																	
						SAND, fine to med. clean				EWS(1)		106																	
						SAND, fine, very silty																							
						SAND, fine, clean																							
						SILT, clayey (stiff plastic)		gray & gray		firm		89																	
						End of boring @ 40'																							

101-5004-750-11 p-25